

**LIBRARY**

FINAL ENGINEERING REPORT  
FOR  
SURVEYOR EJECTA DETECTOR  
MODEL ML 256-1 AND 185-1  
AND  
SURVEYOR EJECTA DETECTOR  
GROUND SUPPORT EQUIPMENT  
MODEL ML 260-1

N67 13019

FACILITY FORM 602	159	(ACCESSION NUMBER)		(THRU)
	CP-79300	(NASA CR OR TMX OR AD NUMBER)		(CODE)
				11
				(CATEGORY)

GPO PRICE \$ \_\_\_\_\_

CFSTI PRICE(S) \$ \_\_\_\_\_

Hard copy (HC) 5.00

Microfiche (MF) 1.00

ff 663 July 65

R. Carden  
D. Rose  
H. Rosenberg  
D. Sassa

Prepared By  
MARSHALL LABORATORIES  
3530 Torrance Boulevard  
Torrance, California

For  
GODDARD SPACE FLIGHT CENTER

### ABSTRACT

The following is the Final Engineering Report on the Surveyor Ejecta Detector (ML 256-1 & ML 185-1) and the Ground Support Equipment (ML 260-1) for this experiment. This equipment was designed, developed and fabricated by Marshall Laboratories under National Aeronautics and Space Administration Contract No. NAS 5-3417.

The objective of the experiment is to measure momentum, energy and direction of particles, close to the lunar surface, were built on an exposed rectangular plate. In general, these particles will be secondary particles which are emitted from the lunar surface when a primary particle impacts.

Goddard Space Flight Center personnel and Marshall Laboratories jointly designed the basic sensor plate. Goddard Space Flight Center was then responsible for supplying the thin films and acoustic transducers for the sensor while Marshall Laboratories was responsible for fabrication of the sensor plate. Marshall Laboratories was also responsible for building the sensor electronics package (ML 256-1) and the electronics in the main body of the spacecraft (ML 185-1). The Marshall Laboratories electronics packages performed the following functions:

1. Amplify the sensor signals and convert them into a binary form which is compatible with the spacecraft telemetry system.
2. Storage of data until a new impact occurs and counting of acoustic signals and film signals.
3. Supply in-flight calibration signals.
4. Convert spacecraft power into various regulated voltages.

The electronic units were constructed of welded modules which were interconnected by means of a welded matrix. Soldered wires connected the matrices to connectors on the housings. Three complete prototype units and one sensor thermal unit were built.

Two GSE units were built with the following functions:

1. Simulate all spacecraft power and signals.
2. Provide simulated impact signals to sensors.

3. Provide visual display of experiment outputs.
4. Be capable of operating on external batteries.

Wherever possible, welded modules and welded matrices were used with soldered interconnections employed between matrices and other components.

In addition, three battery operated calibration units were supplied. These units can be plugged into the sensor electronics when the experiment is on the spacecraft and supply five additional calibration signals to the experiment.

All units were successfully built, tested and calibrated. Test data is included in the report.

TABLE OF CONTENTS

	Page
INTRODUCTION. . . . .	1
FUNDAMENTALS . . . . .	1
EXPERIMENT DESCRIPTION . . . . .	4
TESTS AND TEST RESULTS . . . . .	41
MECHANICAL DESIGN AND TEST RESULTS. . . . .	48
APPENDIX A . . . . .	55
New Modules Used in the Experiment	
APPENDIX B . . . . .	78
New Modules Used in the Ground Support Equipment	
APPENDIX C . . . . .	83
Master Drawing List	
Operating Manual	
Test Specifications	



ILLUSTRATIONS

Figure		Page
1	Ejecta Detector Experiment	5
2	Ejecta Detector Blivets and Covers	6
3	Schematic Diagram Lunar Ejecta Detector	8
4	Ejecta Detector Experiment and Ground Support Equipment	24
5	Schematic Diagram Micrometeorite	25
6	Mic Pulse Height Analysis Data, SN1	42
7	Film Pulse Height Analysis Data, SN1	43
8a	Pulse Height Analysis Data, Microphone, SN3 & 4	44a
8b	Microphone Channel Calibration Graph, SN4	44b
9a	Pulse Height Analysis Data, Film A	45a
9b	Film A Channel Calibration Graph, SN4	45b
10a	Pulse Height Analysis Data, Film B	46a
10b	Film B Channel Calibration Graph, SN4	46b
11	Overall Transfer Functions	49
12	Temperature Probe Calibration Curves	50

## INTRODUCTION

This final engineering report is submitted in partial fulfillment of NAS 5-3417 for the Surveyor Ejecta Detector which was designed and built by Marshall Laboratories for the Goddard Space Flight Center. The Ejecta Detector is a scientific instrument which will become an integral part of the Surveyor Lander Spacecraft which will be landed on the surface of the moon. The objectives of the contract were to design, fabricate and test four units of electronic instrumentation for dust particle detection; to design, fabricate and test two units of Ground Support Equipment; and design, fabricate and test three battery operated calibrate units. Finally, to give support necessary to integrate electronic units, and to provide documentation on the above units.

This report discusses the design philosophy and presents the detailed engineering analysis of the Ejecta Detector and Ground Support Equipment. It discusses the test results of the flight qualified prototype instruments, and includes those illustrations and documents necessary for a thorough understanding of the instrument and its associated ground support equipment.

## FUNDAMENTALS

This instrument is designed to measure the characteristics of the particles of mass ejected from the lunar surface as a result of primary meteroid bombardment from interplanetary space. These pieces of lunar surface material which are ejected upon impact of a primary particle are expected to be more numerous than the

primary particles and have ballistic trajectories which, it is postulated, will cause a significant flux of secondary particles near the surface of the moon.

Since the mass, velocity, and number of these particles is of extreme importance in considerations of future lunar landings, and of general interest to the scientific community, it is apparent that the first instrument landing on the moon will provide an opportunity to measure these particle fluxes and accumulate scientific statistics on their abundance and significance in the lunar environment.

The instrument sensor consists of two different types of detectors, an acoustical sensor which has an output proportional to, or related to, the momentum of the particle, and a thin film capacitor detector. The acoustical detector consists of a planar metallic plate which will be oriented normal to the surface of the moon. Impacts on the plate will result in acoustical transmissions which will be sensed by a acoustic transducer mounted in the center of the plate. On both sides of the acoustical detector plate are deposited thin film capacitors. The impinging particle momentarily shorts both sides of the capacitors together causing a reduction in the potential difference across the plates of the capacitors and a redistribution of the charge which is sensed in the input amplifier and yields information regarding the particle energy. The momentary flow of charge through the shorted part of the capacitor causes the short to burn-out immediately thereby enabling the sensor to receive new impacts. The exact relationships between the particle mass, velocity or momentum for the particular sensors used in this experiment are determined for each instrument at, by hypervelocity tests using particle accelerators, one of which is located at Goddard Space Flight Center. The directional sensors are the capacitors which are deposited on each side of the acoustical plate, and electrically isolated. The direction from which the particle

has originated is sensed by identification of which side of the plate was hit, by means of the two capacitor sensors.

The processing of the signals from the acoustical sensor and two capacitors is provided in an electronics assembly located directly under the sensors and in an inboard electronics unit located in Compartment B within the Surveyor spacecraft. The processing of the two types of signals include a pulse height analysis to determine the momentum and energy parameters, and a counting of particle events as well as identification of which of the capacitor sensors was activated thereby determining the direction of the impact. The data collected is stored in binary form and immediately transmitted in a serial readout pattern to the spacecraft telemetry system. Thus a readout occurs for every change in the status of the data. The accumulation of data which may occur during a readout is also provided, since the readout interval may be significant compared to the expected data rates of the ejecta flux. This accumulation of data after a readout has been initiated consists of the counting of particles which have been sensed by the acoustical detector and the counting of particles which have been sensed by the two capacitor detectors. These totals are stored in separate accumulators and are provided because of the probability that the meteor flux will be in the form of concentrated bursts of many impacts at one time. The experiment performs a pulse height analysis on the event which initiates the readout, and during the readout records all subsequent impacts in the accumulation portion of the experiment only.

The other functions of the electronics are to provide operating power to the electronics from the spacecraft central power supply, to provide a means for in-flight or on-the-surface-of-the-moon calibration of the sensor channels, to provide a means for sending a repeated data transmission upon receipt of a readout command from the central spacecraft telemetry system, and provide a capacitor film

clear signal to the capacitor sensors, in the event a particle has caused a short in these sensors which has not self-healed. This sensor short may be "burned-out" by a command from the central spacecraft telemetry system which will provide the current necessary to burn out the shorted capacitor thereby making the capacitor sensor operable again.

The initiation of a readout upon impact of a particle can be due to either a capacitor sensor signal or a acoustical sensor signal, but once such a signal has occurred provision has been made to restrict the pulse height analysis to only that initial impact. This restriction insures that the pulse height analysis and thereby the mass and velocity parameters which have been derived from the acoustical sensor will be on the same particle as that derived from the capacitor sensors. Simultaneous solution for mass and velocity on a single particle is possible. In the event that simultaneous solution for the individual parameters is not necessary, this restriction insures a redundancy in the analysis which may prove to be valuable in assessing the confidence level of the results of this experiment. For brevity in the rest of this discussion, the acoustical sensor will be termed "mic" or microphone and the capacitor sensors will be termed "film".

#### EXPERIMENT DESCRIPTION

The photographs of Figures 1 and 2 show the Ejecta Detector in its final flight configuration. In Figure 1, the sensor plate and the microphone are in the rear. The capacitor sensor is divided into two sections which are separated by a web which supports the microphone. The electronics housing is located immediately under the sensor plate and supports two Cannon connectors which are jutting out to the left.




Figure 1. Ejecta Detector Experiment




Figure 2. Ejecta Detector. Blivets and Covers

In the foreground is the inboard electronics package containing most of the digital circuitry for processing the data from the sensor electronics package. In the spacecraft these two units are separated by a seven foot length of cable. Since the sensor plate is exposed to the direct rays of the sun, the temperature extremes in the sensor electronics and on the sensor plate is expected to be quite different from those of the inboard electronics which is in a temperature controlled chamber.

The photograph in Figure 2 shows an exploded view of the inboard electronics. The covers being removed, exposing to the rear the power supply electronics which contains the low voltage power converter and regulators and the telemetry coding circuitry and command interfaces required to condition the signals before transmission to the central spacecraft. The connector at the top is the spacecraft cable connector and that on the side is the interconnecting connector to the housing in the foreground (Digital) which contains the pulse height analyzer circuitry as well as the data storage and accumulation registers. The connector at the top of this housing is from the sensor unit. The schematic diagram of the three units discussed: the sensor electronics, the digital housing and the power supply are shown in Figure 3. (ML Schematic Diagram No. 51114 sheets 1 and 2) Here, Sheet 1 is the sensor electronics and Sheet 2 is the inboard electronics; To the left is the digital portion, and to the right is the power supply portion. The connector on the far right is the interface between the spacecraft and the Ejecta Detector.

First, let us follow the signal flow through the two diagrams in a very brief manner, so that the reader may be oriented as to the functions of each major group, and as to the locations within the diagrams of each function. Consider first the acoustical detector, which we had decided to term "mic". As you see, the microphone input is



on the upper far left of the first sheet of the schematic diagram and is directed to a four-stage amplifier consisting of modules Z1 through Z5 and finally a conditioning emitter follower Q1. The output of this amplifier which has the individual stages with gains of 10 each and a bandpass filter which limits the frequency response to a 10 KC band around 100 KC, the natural frequency of the crystal sensor. The output signal of the composite amplifier is called the microphone signal, and if we go to the next sheet you will find it entering on Pin 1 of the left hand connector, and being applied to a detector.

This detector is a differential feedback detector. The output of the detector eventually follows the peak of the incoming signal - a modulated carrier of 100 KC - the envelope reaching peak within 10 cycles of the carrier. The output of the detector is applied to the gain of two amplifier, which is shown to the right of the detector, and from the gain of two amplifiers the signals are threshold detected in the differential comparator stages Z45 and Z44. These comparators detect if the signal is above or below threshold and thus control and gate, Z43, which gates astable multivibrator Z42 to generate the pulse height to pulse count conversion which is stored in accumulator Z28, Z27, and Z26. The greater the number of pulses stored in this accumulator the greater is the height of the pulse. The status of the accumulator is available on lines to the immediate right of the three accumulator binaries and is the data labeled MPHA 1, 2, and 4. This data is then made available to the right most portion of the schematic which will sample the d-c levels and transmit them as ones or zeroes as the telemetry sequence progresses.

The sequence of readout is determined by the sequencer counter Z13 through Z17 and the dual nand and dual parallel nand gates Z2 through Z11. The resulting serial readout word is applied to the SCO driver, Z1, which conditions the levels of the readout word to

be compatible with the spacecraft telemetry circuits. The output of this module to the telemetry is normally, in the absence of data, a square wave having a one hundred-cycle-per-second frequency. When data is present in the system, a code address 001 is transmitted in a return-to zero fashion whereby the pulse height and accumulator bits are transmitted. The total number of bits transmitted including code address is 19. The 100 cps signal originates at the 100-cps clock which is an astable multivibrator, Z24. This clock serves the dual function of telemetry waveform generator, and a continuous reset generator when data is not present. The clock is used to strobe the condition of gates Z2 through Z11 during the readout sequence. The other input to these gates are the signal data which are available from the bistable multivibrators in the digital portion, of which only the mic PHA storage binaries have been discussed.

Return to Sheet 1, the sensor electronics schematic, and trace the film signals as they pass through the electronics to the telemetry system. On the left hand side of the schematic we see the inputs Film A and Film B being applied to separate modules Z7 and Z8. These are high-gain amplifiers with a gain of approximately 50 db which amplify signals to usable levels at low impedances which can be transmitted on the cable as the Film Signals A and B. If we go to Sheet 2 we will see these signals appearing to the lefthand portion of the schematic as Film A and Film B. These lines are applied to differential feedback detectors Z58 and Z59 which constitute the beginning of the A and B channels of the film pulse height analyzer. The outputs of the detectors are respectively applied to comparators Z59 and Z67. These comparators control and gates Z62 and Z64 which, in turn, gate the clock pulse generator Z63 which performs the pulse height to time conversion. The data thus accumulated in the film pulse height analyzer is stored in bistable multivibrators Z32 through Z35. The outputs, labeled PHA 1 through 4, are d-c levels which are sampled by the telemetry conditioning section.

The readout of data to the telemetry system can be initiated by the occurrence of either a microphone or one of the two films. The occurrence of either of these signals is sensed by module Z70, dual nand gate which has as its output the beginning of readout line which initiates the telemetry cycle. The Beginning of Readout line triggers bistable multivibrator Z20 to enable the dual nand gate Z19 to allow clock pulses to strobe the nand gate chain Z2 through Z11. Since Z2 through Z11 dual nand gates have inputs from the bistable multivibrator countdown chain, Z1 through Z5, the nand gate which will be completely enabled is determined by the status of this countdown chain. This nand arrangement, module Z2, and Z11 form a NOR output gate from which the data are directed into the SCO Divider. When the readout is completed, a detect 20 circuit which is part of Z18 detects this fact and resets various circuit functions so that new pulse height data can be received.

If an In-flight Calibrate Command is generated within the spacecraft telemetry system, the command signal will be routed to the command interface module Z77 and from there to the sensor electronics section where the in-flight calibrate command sequence has begun. If the spacecraft generates a Readout Command signal, the command is directed to module Z23 and modules Z23 will set bistable multivibrator Z20 in the same manner that the beginning of readout sequence is initiated by the occurrence of a particle impacting either of the sensors. If the sensor telemetry system generates a Clear Command, this command is directed to module Z78 which generates a pulse which is also sent to the sensor electronics section where the needed current to clear the film sensor is generated.

The power for the detector electronics is derived from a +29 v regulated d-c source available in the spacecraft through a module Z81, a d-c to a-c inverter which is based on a design that originated with J. L. Jensen in an article "An Improved Squarewave Oscillator Circuit",

in the IRE transactions on Circuit Theory, C.T. -4, 276-277 Sept. 1957. This convert r has an oscillator transformer T1 and a voltage conversion transformer T2. The output of the voltage conversion transformer occurs on four secondary windings from which the +12, +6, +3 and -7 volts are generated. In the case of the +3 volts and the +6 volts, synchronous rectifiers are used and in the case of the 12 and -7 volts feedback differential regulators are used. The outputs of each of the detector lines are filtered by the means of tantalum capacitors and are further filtered in critical areas hence, noise pickup is minimized throughout the system.

Incorporated in this unit is a fail-safe system whereby if by some chance the films become noisy and generate pulses of sufficient amplitude to trigger the system erratically, this rapid data rate is sensed, and the films are disabled from starting a readout. This is accomplished in modules Z74 and Z75 and Z76. Z74 and Z75 constitute an integrating trigger circuit which senses the data rate of the film and if the data rate exceeds a preset value, the initiation of readout by the films is disabled through gate Z76.

We have now very rapidly scanned the high-lights of the Ejecta Detector. Let us now go back and examine each portion of the circuitry and discuss, in some detail, the operation involved. We shall begin with the microphone signal as it enters the sensor electronics. We shall then examine the film signals as they enter the sensor electronics and are converted to digital form. We shall see the origin of the Beginning of Readout pulse and the mechanism whereby readouts are initiated. We shall examine in detail the method of presenting the data to the telemetry in serial form and finally we shall investigate the various calibration and command sequences which form the peripheral part of this data processing.

Refer to sheet one of the schematic diagram of Figure 3. The microphone signal is a 100 KC modulated envelope. The first peak of this signal will occur between 3 and 10 periods of the 100 KC carrier. Since reflections are expected from the microphone due to the finite distance from the microphone to the edges, or discontinuities in the plate, and since it is undesirable to peak detect on these reflections, it is necessary to inhibit the detector from further peaking after the first sampling period which is determined to be 100 microseconds, or 10 periods, the inhibit being effected in the detector circuit. The inhibit lasts for 30 milliseconds and occurs by the action of the inhibit-and-hold module, W4168, Z47, which effectively shorts the emitters of the differential amplifier in the differential feedback detector to B+, thereby back biasing the differential feedback detector. Schematics of the detector and the inhibit-and-hold module are given in Appendix A. The inhibiting action is initiated by the 30 millisecond one shot, Z49. This one shot is triggered by the trailing edge of one shot Z50 which occurs immediately after the comparator, which is biased at 250 millivolts, reaches threshold.

When the comparator changes state, due to the fact that the signal has reached threshold, the output of the comparator, Pin 12 of Z44 triggers one shot Z50. A schematic diagram of the comparator module Z45 and Z44 is also given in Appendix A. The detector and comparator circuits were developed to withstand the extreme environments expected in the lunar landing. Tests have been run on these circuits which show them to be stable within a millivolt under extremes of temperature with wide dynamic ranges available. The circuits consume very little power and will operate at reasonably high speeds. The detector is a closed-loop amplifier with a diode rectifier in the feedback loop making the feedback unilateral. The output is taken off the feedback point such that the input will follow the output. Across the output is a capacitor of .047  $\mu$ farad which is used to smooth the signal peaks.

At the time of the incidence of the signal, the resistors R7 and R16 is not returned to ground due to the holding action of module Z47. This action is initiated by the output of Z50, Pin 6, the 100  $\mu$ second one shot, thereby the holding interval - the interval in which the capacitor is maintaining its charge, or adding to it, is 100  $\mu$ seconds. At the end of 100  $\mu$ seconds interval, the holding signal is released and the resistor R7 and R16 are returned to ground thereby discharging the capacitor. The rate of discharge is  $\mu$ seconds time constant, and provides the logarithmic time base for the pulse height to time conversion. The time difference between the time at which the signal originally passed the threshold on the comparator to the time at which the decaying pulse again passes threshold is the time allowed for the generation of clock pulses in the accumulator of the pulse height analyzer.

The gain of 2 amplifier is used to enable a wide dynamic range on the comparator while limiting the detector dynamic range to quite reasonable figures, thereby limiting the amount of charge necessary for the capacitor and hence the current demand of the detector. The comparator threshold is established by resistors R8 and R9, nominally 250 millivolts. The dynamic range of the comparator in this application is approximately 20 to 1. The maximum number of clock pulses generated in this circuit is 7 after which the detector and amplifiers preceding the detector saturate so that the maximum count for expected particle ranges is a 111 and the mic PHA storage binaries. The initiation of clock pulses occurs when the 100 microsecond one shot returns to its initial state after a delay of 100  $\mu$ seconds. At this time the comparator output Pin 7 Z44 is up and allows this positive-going-one-shot pulse to start the clock. The uncertainties due to pulse shape in the microphone signal have been eliminated in that the clock always starts on a very rapid rising edge of the 100  $\mu$ second one shot. The comparator, returning to its original state after the time decay in the detector, shuts the clock off and therefore the pulse height pulse/count conversion is accomplished. The and gate Z43 establishes the inhibiting of the

pulse height analyzer provided no mic hit has occurred, or inhibits the analyzer after one hit has occurred. This action is accomplished through gates Z52 and through the one shot Z53 and bistable multivibrator Z51. If a readout has been started by the film the data reset line will be actuated immediately setting bistable multivibrator Z51 to the enable state 3 and 5 going to a 1 enabling and gate Z43. It also actuates one shot Z53 which inserts a negative going signal on Nand gates Z52. The output of this Nand gate is the inhibiting lead and if the comparator Z44 is still up and has not been processing data in the analyzer, the trailing edge of the one shot will get through the Nand gate and trigger the bistable multivibrator to inhibit further data analysis after the one hundred  $\mu$ second interval of Z53. If data is in-process in the microphone pulse height analyzer.

If data is in-process in the PHA NAND gate Z52 will be inhibited, therefore the action of one shot Z53 is also inhibited. Z53, Pin 8, the output of the one shot, will return to the one state. At the conclusion of the data analysis the comparator output will also return to the one state. When both inputs to one half of the dual NAND gate Z52 are ones, its output will go to a zero. When this occurs, bistable multivibrator, Z51 will be set to the inhibit mode. The pulse height analysis channel is then inhibited through the action of gate Z 43 which requires all of its inputs to be up in order to gate the clock pulses and begin height analysis. Thus we have seen that the microphone signal occurs first, or it is allowed within 100 microseconds after the occurrence of either an A or B film. These signals start the beginning of readout pulse, which initiates the 100 microsecond waiting period for sampling the microphone data.

Let us now trace the initiation of film data from the sensors through the film pulse height analysis. Return to sheet one of the schematic diagram.

schematics of which are shown in Appendix A. These amplifiers have a 50 db gain and are especially designed to interface with the capacitor sensors. They are operational type amplifiers which have summing resistors at the input, so that calibration signals to this channel may be easily inserted. The three inputs to this amplifier consist of the film signals, the in-flight calibrate signals, and finally the ground support equipment signals which are used to run calibration curves on the film channels during manufacture and tests. The amplifier was designed as a three-stage inverting circuit, with two individual feedback loops used to achieve low input impedance, low output impedance, and at the same time, maintaining a large gain per stage in the individual transistors. The input stage of this amplifier contains shunt feedback with circuit parameters chosen so that the feedback resistance, or equivalent Miller effect resistance change under temperature exactly compensates the  $h_{fe}$  change with temperature, thereby enabling the gain to remain constant over the expected  $-55^{\circ}\text{C}$  to  $+100^{\circ}\text{C}$  temperature range. The second stage is a conventional high-impedance, input, low impedance output NPN and PNP pair, noninverting, designed to drive efficiently a long length of coaxial cable. The response time of this amplifier is less than 1/2 microsecond to the leading edge, while the trailing edge is sufficiently coupled through the stage to prevent serious under-shoot. The under-shoot of the trailing edge of the signal is important if the trailing edge is to be used to form a pulse height analysis, since this will result in a consequent over-shoot which may be detected in later stages as an additional film pulse giving erroneous data.

It is therefore by careful design that exact parameters were chosen in this amplifier so that the output is critically damped after one undershoot of the trailing edge. Also incorporated in this amplifier is a biased-diode feedback network which changes the gain of the amplifier if the signal at the output of the amplifier exceeds one volt.



This gain reduction reduces required dynamic range of the succeeding stages so that conventional power supply voltages may not be exceeded. The output of the capacitor amplifiers were both the film A and film B channels is applied by coaxial cable to the input of the digital section which is shown on sheet two of the schematic diagram.

We have seen how the mic signal analysis is performed and we have seen how the requirement has been placed on the microphone pulse height analyzer that this signal occur within 100 microseconds after the occurrence of a film hit. We now take the case where the microphone signal has occurred first, and we put the same restriction on the film signals-that they occur within 100 microseconds after the initiation of a Beginning of Readout pulse by the microphone.

We have seen that the microphone one shot, Z50 Pin 6 going to a one state actuated dual NAND gate Z70, the output of which was applied Z12 which when coming down initiated the beginning of readout. In parallel with the output Pin 12, Z70 are the outputs Pin 12 and 6 of Z76 which together with Z70 form an Nor circuit. Therefore either film channel which has been impacted caused the inputs to Z76 either 5 and 3, or 9 and 10, to go to a one, initiating a Beginning of Readout pulse. We see that the other output Pin 8 of Z50, the microphone one shot is applied to Pin 7 and 9 of dual NAND gate Z68 in the film section. Since this output of the one shot is negative going, the NAND gate will be activated, thereby its output going to a zero, when Pin 9 and 7 go to a one. There is also a requirement on this NAND gate that Pin 10 and 11 be at a 1 before a signal output on Pin 12 is obtained. This insures that a 100 microsecond waiting period has elapsed before an output can appear from this NAND. Since this output resets bistable multivibrators Z61 and Z65 to inhibit the film channel for the rest of the read out, this inhibiting is delayed from the beginning of a mic pulse by 100 microseconds, or it is delayed until film comparators are returned to their quiescent state. A zero on NAND gate

Z68 Pins 2 and 5 or 4 and 8 cause Pin 6 of the gate to go up and therefore Pin 10 and 11 of dual NAND gate to go down. When these Pins return to their upstate, the output on Pin 12 will go to zero causing a reset to occur on bistable multivibrators Z61 and Z65. NAND gates Z70 and Z68, then, reset the film channel to the inhibit state either after analysis of the film channels, or after 100 microsecond interval of the mic has occurred first.

The output of Pin 6 the dual NAND gate Z which is derived from the two comparators supplied to the film accumulator binaries Z41, Z40, Z39 and Z38. Since this happens when either comparator is actuated, the total count in the film channel is recorded. Notice that the accumulation will not be dependent on the status of the inhibits on the pulse height analyzer.

The resetting of all the storage binaries in the data chain is accomplished at the beginning of readout. This insures that all bits will be at the 0 state with the minimal probability that noise could occur to disturb the data prior to readout.

The identification of which the two bi-directional films was impacted, channel A or channel B is stored in bistable multivibrators Z36 and Z37. They are toggled at the end of analysis when the parallel NAND gate returns to its initial state. At this time one of the bistable multivibrators, Z61 or Z65 has a one and the other has a zero. These outputs are applied to the steering inputs of the film identification binaries Z36 and Z37.

We have now seen how the film and microphone signals have traversed through their amplification stages and have been pulse height analyzed. We have seen how the events in the microphone detector and in the two film detectors have been recorded in accumulators

and how film identification has been accomplished. We will now consider the ancillary circuits which are located in this part of the electronics.

The noisy film circuit, modules Z74 and Z75, and gate Z76, Z70 and Z76 generate the beginning of readout. If we were to inhibit the film channels we would necessarily do it at Z76. We require Pin 7, 4, 11 and 8 to be up before the initiation of readout can be accomplished by a film hit. This gate is controlled by trigger circuit Z75 which will be activated when the films become noisy.

Trigger circuit Z75 is a positive-feedback circuit which is initiated by an integrator Z74. The input to this integrator circuit is OR output of the comparators. The integrator time constant is such that if the data rate in the two comparators exceeds a preset level, the trigger circuit Z75 generates the required zero at Z76.

If we return to sheet one of the schematic, we may follow the signal as the calibration mode is initiated. We see that the calibration signal forms a positive going pulse which is applied to dual parallel NAND gates Z11 and Z12. The selection of which of these gates is actuated by this pulse is made by bistable multivibrator Z13 which is toggled by this same one shot. Alternate gates will be selected with the application of calibrate pulses. The output of Z11 (Pins 6 and 12) are applied to Z18, the mic calibrate module Z12; outputs Pins 12 and 6 go to the film calibrate modules Z16 and Z17. The mic and film calibrate modules are voltage dividers which generate levels for calibrating the channels. These modules which are capable of generating two different levels, alternately sampled, form the input levels of the pulses to the mic and film channels. The duration of these calibrate pulses is determined by the duration of the one shot pulse; the leading edge is utilized in the calibration.

In addition to the mic and film amplifiers and the calibrate logic, the sensor electronics contains the heater amplifier, Z15 and is a closed loop sensing circuit using RT4 and a 1 watt heater element supplied by collector current in Q3. Thermal studies recently made on the surveyor spacecraft and the micrometeorite experiment have cast some doubt as to the need of heating. This module does not appear in the final flight configuration. To the upper right hand section of the drawing we see RT3 which is the spacecraft temperature probe, a sensistor probe through which a constant current 5 ma is maintained.

We have now seen how the acoustical sensor signals as well as the capacitor signals have been amplified, detected and analyzed in the pulse height analyzers, and how the totalizing of this flux has been recorded in accumulators, and the job of the peripheral circuits such as the noisy film trigger circuits. The calibration circuits have been utilized in the sensor electronics and the upper section of the inboard electronics. We have seen that the occurrence of a particle impact, which triggers the microphone channel or the film channels, begins the readout by causing a negative pulse to appear on the Beginning of Readout line. A signal on this line establishes a new state in bistable multivibrators Z20 which enables NAND gate Z19 to allow the sequencer, modules 1 through 5, to begin counting. The sequencer is coded into the data NAND gates Z2 through Z11. The counts of 1, 2 and 3 in the sequencer chain transmit a 001 at the output of the experiment. With the occurrence of a 4, the first data bit is transmitted and so on. A one is transmitted when the clock pulse originating at Z24 is allowed to strobe the coding gates. The particular gate which will be sampled is determined by the status of the sequencer flip flops. The coding of the gates is binary/decimal which allows the gates to be sampled in the order of their intended readout. The data to be read out consists of mic pulse-height analysis, 3 bits, mic accumulation, 3 bits, film pulse height analysis 4 bits, film accumulation, 4 bits, film identification, 2 bits.

We are to return to the enabling of gate Z19 through the action of output of Z20 becoming a one, we see that the 4, 5 and 8 leads at that gate are brought to a 1, and if we examine the remaining input, Pin 3, we see that it comes from the 100 microsecond one shot which is actuated on the trailing edge of the clock strobe pulse, therefore, the toggling of the sequencer by this NAND gate of which the output is Pin 6, will occur on the trailing edge of the strobe pulse. Data is sampled and the sequencer toggled when bistable multivibrators Z20 output is Q in the one state, which indicates that new data is ready. Half of the gate, Z19, part of a logic network which is associated with half of Z17, the output being Pin 12, constitutes the microphone accumulator inhibit. These two gates sense when the microphone accumulator is being sampled and prevents any further accumulation during this particular interval of the readout. Data is accepted in the accumulators except when the data is being sampled, this accumulator inhibit is applied to NAND gate Z52, in the upper housing, to inhibit the microphone accumulator.

Now if we return to gate Z18, we see that the output Pin 6 of that gate supplies a pulse which resets the readout binary Z20. Pin 6, 3, 4, 5 and 8 of Z18 form a detect 20 circuit which detects the end of readout and supplies a reset pulse to multivibrator A20. Now if we examine the Pin 12 output of Z18, we see that the input associated with this output are 7, 9, 10 and 11. Pin 7 comes from  $\bar{Q}$  of the enabling flip flop Z20 which will normally be up when the flip flop is in its quiescent condition, therefore, with no readout occurring, this gate is enabled and is strobe by the same one shot that occurs on the trailing end of the clock pulse at Z21. The output of this gate is constantly activated when no data is present and as we see this output is used to reset the bistable multivibrators continuously so that no noise can enter and disturb the status of those bits, so that we are always assured of having a reset condition in the binaries at the beginning of the readout.

### GROUND SUPPORT EQUIPMENT

The ground support equipment for the Surveyor Ejecta Detector is a portable test set which supplies the ejector detector experiment with DC power, simulated impact stimuli, telemetry commands, and provides the experiment with a visual readout display.

The unit is housed in aluminum case which is extremely rugged and may easily be transported to various test locations. The readout of the data is in numeric form which can be easily correlated with input selection. The input selection is made by the use of array of lighted push button switches in conjunction with precision vernier potentiometers. The unit may be powered from a conventional 117 volt AC 60 cps, source or battery power may be used. If nixie readout is desired during battery operation, this portion of the GSE may still be AC powered. Otherwise an oscilloscope readout must be used.

The GSE is shown with the Ejecta Detector in Figure 4. The electrical schematic is shown in Figure 5. The system is divided schematically into four groups; they are: Sheet 1, Digital Readout and Commands; Sheet 2, Switch and Meter Circuits; Sheet 3, Sensor Stimulus; and Sheet 4, Power Converter.

The Digital Readout and Command section of the system contains the circuits necessary for storing the 19 bit readout word and driving the nixie displays, and also contains those circuits necessary to generate the telemetry commands.

We shall assume that the experiment has received a hit and begins to transmit a 001 code word. We shall follow the sequence of events which leads to a readout display. On the left hand side of the schematic (Sheet 1) we see the data input and the experiment clock




Figure 4. Ejecta Detector Experiment and Ground Support Equipment

brought into the GSE. Remember in the write up of the system that the data at the output of the experiment changes on the positive leading edge of the clock pulse, so that if we were to have a one of data it would occur at the time of the positive clock pulse. The clock is applied through an inverter Z9 to one shot Z10 so that on the positive edge of the clock the one shot will be triggered. The output Z10 is a positive-going signal applied to Z11. Z11, a one shot, will trigger on the trailing edge of Z10 after a three millisecond delay. We now have generated a 200 microsecond pulse at the output of Z11 which is positive-going and occurs on the leading edge of the clock pulse from the experiment. This positive going pulse is applied to gate Z12 and to the toggle inputs of shift register Z3, Z4 and Z5. This shift register is driven from the data line which consists of the incoming data and the Z6 inverted output Pin 6. The delayed negative transition occurring at Pin 6, Z11 acts as the toggling or sampling pulse for the three-bit shift register, Z3, Z4, Z5. It samples the incoming data which is continuously applied to this register. We see that gate Z1 is coded to be conditioned when a 001 exists in the shift register; therefore, its output will come down at the time of the trailing edge of the 200 microsecond pulse at Z11. That is, the time when the shift register has just changed to the new status-001. At this time bistable multivibrator Z2 is set, so that the output, Pin 5, goes to a one. This output lead is the other input to gate Z12 which is also driven from the 200 microsecond pulse. Since that pulse had just terminated by the time the bistable multivibrators Z2 had assumed a one status, Z12 gate will not be enabled until the next positive going edge of the experiment clock pulse occurs, and 3 ms later this gate will be conditioned to cause a negative transition of the input to driver Z13. This driver will generate the toggling or sampling pulse on the main shift register Z8, Z20, Z21 through Z34. Therefore, we see that the sampling of the principle shift register Z8, Z20 through Z24 does not occur until after the code address 001 has been registered in the ancillary shift register Z3 through Z5; at this time, the system will

PRECEDING PAGES BLANK NOT FILMED.



wait for the next positive clock pulse from the experiment, and 3 milliseconds later, will generate the sampling pulse for the main shift register. The sampling pulse will occur approximately in the middle of the positive-going half of the clock when a one should be present in the RZ experiment data.

This principal register will continue to be sampled and will continue to shift as long as gate Z12 remains conditioned by bistable multivibrator Z2. This multivibrator will stay in the one state until its reset line, Pin 8, is pulsed. This reset line is driven by one shot, Z7 which is, in turn driven by the AC driver, Z19. The AC driver, Z19, will receive a pulse when a count down chain, Z14, Z15, Z16 and Z17 has reached a full recycle count of 16. This occurs when the Q output of bistable multivibrator Z17 returns to a zero. A negative pulse will be generated at capacitor Z33 and diode CR2, and be applied to input of driver Z19 on Pin 7. When 16 clock pulses have sampled the main shift register, bistable multivibrator Z2 will be reset after a 400 microsecond delay which is generated by one shot Z7. The AC driver, Z19 resets the count down chain. One shot Z7 will reset the auxilliary register. If a 001 had appeared in the data, gate Z1 would be again enabled; however, since bistable multivibrator, Z2 has been previously set, the enabling of gate Z1 is ignored during the readout and this condition does not disturb the operation.

At the end of readout, the shift register will store the data until new data is received. Until a new code recognition occurs, this data is displayed by nixies, binary-to-decimal conversion assemblies DS1, DS2, DS3, DS4, DS5 and DS6. These are assemblies accept, the 3 v logic levels convert to decimal form. The ancillary register Z3, Z4, Z5, at the conclusion of a readout is reset to ones.

Had the register been reset to zeroes, upon receipt of the first one of the quiescent transmission of the experiment, (which

transmits a continuous stream of ones) erroneous code recognition would have taken place. We eliminate this problem by storing all ones in the register prior to receipt of the continuous data transmission of all ones.

The count-down chain and ancillary register is reset by driver Z19 at the conclusion of a readout cycle. This driver is triggered by the count of 16 being reached in count-down chain, but it may be also triggered by two other signals, the Sensor Actuate signal and the Command Actuate signal. These signals are applied to the driver through C13 and C12. Immediately before putting data into the sensor channels, the circuits in the readout portion are reset so that, had noise triggered a flip flop to the wrong state, the resetting would occur, and make this flip flop go to its proper state. The input through C12 comes from a one shot, Z38 at the application of a push-button switch which initiates the commands. Before a command is inserted into the experiment, the flip flop in this section of the GSE are reset.

The commands are generated in Parallel AND gates Z35, Z36, and Z39, in conjunction with voltage dividers R2, R1, R3, R4, R5 and R6. These AND circuits are noninverting gates having PNP outputs. The inputs to these gates are a strobe one shot Z37 and levels from enabling selection switches on the front panel. The strobe one shot, Z37 is actuated by one shot Z38 which in turn is triggered by the actuation of the Enter Command switch on the front panel. The command is first selected by depressing the selection switch and the command is entered by pressing the momentary push button switch which sends a pulse through resistors R7 and R7A at the input of one shot Z38. This one shot, in turn, triggers one shot Z37, which strobes the gate selected to give the command. The command pulse width is 20 milliseconds conforming with the spacecraft telemetry specification and simulates those commands that would actually occur in the spacecraft.

The circuits in the lower right hand corner of the schematic are those which generate either continuous data impacts or ultimately enable the insertion of data by push button switch. If continuous data is desired, that is, if continuous hits are to be inserted, Z44, clock module, produces pulses which strobe 1/2 of dual NAND gate Z43. Now this half of the NAND gate is selected when the Manual / Repeat selection switch is in the Repeat position, putting a one into inputs 5 and 8. The output of this section of the gate is Pin 6, and Pin 6 toggles bistable multivibrator Z42, and triggers one shot Z40, which pulses the Sensor Actuate line. This line eventually produces all of the sensor analog signals. Pin 6 of Z42 is also applied to Pin 9 of Z41 which produces the Enable Stimulus signal which occurs prior to the Sensor Actuate signal. The relation between these two signals will be explained as we explore the sensor signal generation.

The other half of Z43 is used to set the bistable multivibrators and begin a data readout. This setting will occur when the repeat manual switch is in the manual position and when the Enter / Data push-button is depressed. When lines 10, 7, 9 and 11 are at ones, the output, Pin 12, will go to a zero. Z43 will be reset when the push-button is returned to its normal position since Pin 8 will be grounded as the push-button returns to its quiescent condition.

In this discussion we have seen how data from the experiment is stored in the GSE and section how the 001 code recognition takes place, and we have seen how the commands are generated, and how Sensor Actuate signal is produced, either by continuous clock or by depression of the Enter Data push-button switch. We will now go to Sheet 2 of the schematic, the Sensor Stimulus section and see how the actual analog calibration pulses are generated upon receipt of a Sensor Actuate Signal.

The Sensor Actuate signal is applied to module Z45; the output module Z45; is applied to Z46. The output of Z46 is applied to Z47 and Z47 to Z48. Each of these modules contributes a delay which corresponds to the numbers in microseconds of the delays of the second through the fourth columns of selector switches on the front panel: 50 microseconds, 500 microseconds, and 50 milliseconds. One shots Z49, Z50 and Z51 are triggered on the leading edge of the outputs of the first three modules so that the first one shot pulse occurs immediately upon receipt of the Sensor Actuate signal. The second occurs after a 50 microsecond delay and the third occurs after a 500 microsecond delay. The output of these one shots are positive going pulses which strobe AND/OR circuit Z53, Z54, Z55 and Z56. The output of the last one shot in the one shot chain Z48, strobes gate Z57 and part of Z56.

These gates generate pulses which are applied to NOR gates Z59, Z62 and Z63 which generate the strobe waveform for the microphone, Film A and the Film B channels. The strobe pulses from these one shots are applied to parallel AND gates Z64, Z67, Z69, Z72 and Z74. These parallel AND gates are used to drive the cable driver modules Z65, Z68, Z70, Z73 and Z75. The DC voltage supply for these driver modules is selected to be the analog level of the pulse that is desired. The output stage of the driver module is simply a saturating transistor switch which saturates from the B+ supply that is generated by the analog selection level as determined by the switch settings on the front panel.

Arranged sequence at which pulses are generated in each of these channels is so as to insert signals throughout the duration of a readout. Signals are inserted, in addition to the beginning of readout, during the times that inhibit functions should be occurring in the system such as the microphone accumulator inhibit, the microphone PHA inhibit, the film PHA inhibit, and film accumulator inhibits. To check

out all of these inhibit functions, some signals are injected automatically whenever a readout occurs and some signals are selected from the push-button array on the front panel.

Pulses may be selected in any of the three channels at intervals of 50 microseconds, 500 microseconds, 50 milliseconds and 150 milliseconds. The 150 millisecond timing is accurately made by taking a signal off the countdown chain which is counting down during the readout and using this signal to generate the 150 millisecond strobe. A sequence of hits and the relative timing between them is shown in Appendix C.

The logic provided by modules Z52, Z53, Z54, Z55, Z56, Z57, Z59, Z60 and Z61 is simply an AND arrangement whereby the strobe pulse occurring from one of the one shot modules Z49 and Z50 or Z51 is required to have coincidence with a one which occurs from any of the inputs from the delay time selector switches on the front panels. If this coincidence occurs, the signals are inserted; the output of these AND circuits drives a transistor NOR circuit so that various pulses which have been selected may be taken in sequence through a common output gate to the desired channel; these NOR circuits are Z59, Z60 and Z61. They form the summation point at which the pulses at the various time intervals are summed onto the one line of each channel.

Since it is desired to interlock the system to the extent that we do not want to insert rapid hits during pulse height analysis, the outputs of one shots Z58, Z62 and Z63 are fed back to certain AND gates as inhibit functions, so that once these channels are excited during PHA interval, no other excitations can occur in that particular interval. These one shots are chosen with widths which correspond to the PHA interval. The lights on the front panel are coded to indicate

hits which have been selected will not get through to excite the system. If we press the zero microsecond on the mic we cannot

light the 50 microsecond button because this 50 microsecond signal will occur during the first 100 microsecond of the microphone PHA and this is not allowed.

The DC levels supplied to the driver circuits of Z65, Z68, Z70, Z73 and Z75 are established by either the vernier controls R63 and R73 or the preselect thumb wheel switches consisting of S26 and S27 and resistors R63 through R91. The selection is determined by the position of the Preset/Vernier switch on the front panel. If this switch is in the Preset condition, the DC level for the driver circuit is taken from the junction of R72 and the wiper arm of S26. If the switch is in the Vernier position, the DC voltage for the mic circuit is taken from the Mic vernier potentiometer arm. In similar fashion, for the film circuit, if the switch is in the preset position, the levels for the film drivers is taken from the junction of R96 and wiper arm of S27; if it is in the vernier position, the levels are taken from the wiper arm of R73. The mic preset switch S26 consists of a 8 position divider, the levels of which are adjusted to give those appropriate window 0 through 7 on the mic pulse height analyzer. In the film channel, the range is divided up into two sections, 0 through 9 and 10 through 15. If windows 0 through 9 are desired, the right most thumb wheel switch, S28A, is placed in the 0 position, and resistors R82 through R91 form part of the voltage divider network. If switch S28A is in the one position, we are considering levels 10 through 16 and the appropriate levels for those windows will be generated by the resistor divider network R96 and R75 through R81.

The film channel, unlike the mic channel, having a very wide dynamic range, necessitates the division of the signals into two different ranges: a high range and a low range. This division enables the signal levels on the coaxial line to be within the range where noise can be rejected easily and the signals can be easily handled. These lines have approximately the same voltage levels on them but at the experi-

ment end of the GSE/experiment cable, an attenuator (See Appendix) is placed in the line so that the whole dynamic range is transmitted with a minimal noise interference. The selection of which of these lines the film signal is to be transmitted on either high or low, is made in switch section S28B if the analog signal is being generated by the film vernier control. S29A is a toggle switch which is used only when the film vernier potentiometer is being used. Its position in relation with the preset controls is not important.

The outputs of driver modules Z65, Z68, Z70, Z73 and Z75 appear on coaxial lines from P6. The returns of these signals are brought through separate leads and are isolated from DC ground by inductors L7, L8, L9, L10 and L11. These inductors constrain the return currents to their appropriate shields, so that a common coupling problem does not exist on the mutual DC return between the GSE and the experiment. Across the variable B+ selected by the vernier or preset controls are capacitors C27, C28 and C29, which supply the current demands of the rapidly saturating transistor switches which form the output pulses to the experiment.

We notice in our observation of Sheet 1, that the Sensor Stimulus Enable signal came to a one prior to the Sensor Actuate signal. This level is applied to parallel AND gate modules Z64, Z67, Z69, Z72 and Z74. This DC level is down except when a Sensor Stimulus is desired, and reduce the probability of an extraneous signal appearing on one of the data output lines, and is added as a special precaution in this GSE. We require the coincidence of the Sensor Stimulus signal as well as the Sensor Stimulus Enable before an output pulse is generated. The probability of both occurring at the same time reduces the probability noise is greatly probability without the coincidence.

Let us now examine the operation of the circuits on Sheet 2 of the schematic, the Switch and Meter Circuits. We see the selector switches are four pole double throw switches being utilized. The data interval selection at which the microphone Film A and B channel pulses are inserted is in the upper left hand portion of the switch array. The Heat switch turns the heater power on. The Repeat Manual switch determines whether hits will be inserted by Push Button with the Enter Data switch or started by a continuous clock which runs at a second rate. The Preset Vernier switch was explained previously. The Battery/AC line switch controls where the suitcase derives its primary power from, that is, from a greater than 12 volt battery or from the 117 AC line. The Power switch turns the power to the GSE on and off. The three command switches, Calibrate Command, Clear Command and Read Command are generated by depressing one of these switches, S20, S21 or S22, and then by an Enter Command momentary contact switch S23. In a similar manner, data is injected by preselecting one of the time sequence switches in the upper left hand portion of the array and depressing the Enter Data switch.

All of the switches on the front panel are alternate action type, this meaning that they will stay in either of the alternate positions once depressed except S19 and S23 which are the initiating switches for entering data or commands.

The metering circuit is shown in the upper portion of the schematic, as is the constant current generator Q1 and Q2. This constant current generator is used to excite the sensistor temperature probe which is located in the sensor unit in the experiment. The current generator consists of driving transistor Q2 and output transistor Q1. The constant current is derived from the collector current generator internal to transistor Q1. The current to transistor Q1 is established by an accurate voltage reference across its emitter resistors R13 and R14. This current is established through the emitter



follower action of Q1 and Q2. The reference voltage is derived from CR2A, precision reference diode. The current from Q1 flows through the temperature sensor probe in the experiment. Voltage across Q1 to ground, is measured as the output voltage of the sensor as applied to the input position No. 1 of selector switch S25A.

This switch determines which of the circuits is to be metered by microamp meter M1, which serves as a null-detecting meter. The reference for null-detection consist of the voltage derived from precision voltage divider to the right hand portion of the schematic, beginning with R18 and ending with R56. The 100 ohm resistors in this divider are inserted to account for tolerance buildup in the resistor chain as well as for slight unbalances which may occur in the matched pair emitter follower Q3A and Q3B. The emitter resistance of the emitter followers in this case is replaced by constant current generators Q4 and Q5, maintaining the current through these matched emitter follower constant regardless of the level changes at the basis of the emitter follower. High current ratings and unbalances do to wide variations in emitter current are avoided. The current reference is established by CR7 on the basis of Q4 and Q5. The sensitivity of the meter is adjusted by the use of fixed resistors R21, R23, R25, R27, R29, R31, R28 and R25 in conjunction to variable potentiometers R20, R22, R24, R26, R28, R30, R32, R34, which are placed in series with the meter. These additional resistance variations allow for variations and transistor parameters as well as slight design tolerances.

The levels established for this potentiometer circuit when measuring the +3, +12, +6 and -7 volts are nominal. In the case of the temperature probe, the voltage of the bridge is 2 1/2 volts, and in the case of the 29 volt supply, this voltage is divided so as to reduce the dynamic range required on the metering circuit. Diode CR5 and CR6 are silicon diodes which are used to protect the meter; that is, if the drop across R19 and the meter exceed diode conduction voltage

the diode will carry the bulk of the current thereby protecting the meter from transient overloads. The meter circuit is designed to measure the temperature of the unit in  $^{\circ}\text{C}$ . The primary current appears directly in milliamps. The meter circuit is a direct reading 0 to 50 milliamp movement with no null detection. Meter point which is nominally 2.04 volts as a null detector, measures 28 volt primary supply. Calibration curves for the temperature sensor in unit 1 is included in the test results section along with the meter readings observed on the first unit.

Refer now to Sheet 4, the Power Converter section of GSE. This portion of GSE takes the 110 volt AC power and converts it to +29 volts for the experiment excitation and generates +3 volts for the logic circuitry as well as +30 volts for the meter circuits. It also generates the heater 22 volt. The 110 volt power is applied through an AC line noise suppression filter SP 30278, which is a  $\pi$  network filter and is applied to the power switch S24 which is an on-off switch. The power is supplied to the transformer T101 which converts to 6.3 volts for the lamps, and to PS1, the 180 volt high voltage power converter, and finally is applied to transformer T102 and fullwave rectifier CR101 and CR102, CR103 and CR104, filter L104 L106, C105 and C107. The output of this filter is a DC voltage of approximately 12 volts which is applied to the input regulator Q101. Q101 is driven by differential feedback regulator module Z101 which maintains the voltage output at the emitter of Q101 at exactly 11 volts. This 11 volt is applied to a DC inverter Z102 which oscillates at a frequency of 2500 cycles per second. The oscillator transformer is T103 and the voltage converter transformer is T104. The secondary to T104 contains the rectifier doubler windings 4, 5, 6, 7, 8 and 9 for the 30 volt regulator, the synchronous rectifier windings 10, 11, 12, 13 and 14 for synchronous 3v rectifier, and the regulator doubler windings for 15, 16 and 17 for the +29 volt regulator supply.

The outputs of these windings are applied respectively to rectifier doubler Z105 and 30 volt feedback regulator Z104. The 30 volt is filtered by capacitor C112 and appears at connector J8. The heater regulator is designed to always draw a constant current from the secondary of transformer T104 thereby maintaining a constant load of an input regulator Z101. This insures that the other voltages in the circuit and the Z101 regulator as well as the critical inductances of L104 and L105 need not be large. The constant current in this regulator is taken from transistor Q103 or is dissipated in transistor Q105 if no load is being drawn by the heater. This occurs through a feedback network consisting of the 36 ohm resistor and series with the emitter of Q105 and the regulation transistor Q104. The voltage at which the heater operates can be adjusted from 16 volts to 28 volts. The synchronous rectifier is a conventional one, the output voltage of which is filtered by C113. The rectifier-doubler Z105 and Z106 supply the 29 volts. Z106 is a feedback differential regulator, the output voltage is adjusted by resistor R110, and output current is sampled at R109, this is applied to the metering circuit which measures this voltage, thereby determining the current which is being demanded by the experiment.

If a battery operation is desired, the battery is applied to terminals J10 and J11. The battery should be in excess of 12 volts to allow for battery deterioration. The fuse F101 diode CR105 will protect the circuits in the event the battery is connected in reverse. If the battery potentials are applied in reverse, diode CR105 will conduct heavily, causing fuse F101 to blow immediately, thereby protecting the transistor circuits. The output voltages appear at the power converter board connector J8 and are transmitted on separate lines to the various circuit groups so as to minimize mutual coupling throughout the GSE. A complete operation manual of the GSE is included in Appendix C.

## TESTS AND TEST RESULTS

The first unit delivered was the thermal study unit which contained only resistors to simulate the power dissipated in each section of the electronics. Test data for Serial Numbers 2, 3 and 4 are included in this section. Serial Number 2, was the first working prototype which was to operate at room temperature only. The unit test results are shown in Figures 6 and 7. These data represent the input voltages applied to the microphone and film channels and represent the overall transfer function of the system from analog input to digital output.

After this system was designed and delivered, the sensor electronics was modified to account for new test data on the films which were being supplied by the Goddard Space Flight Center. The new electronics contained a highly sensitive film amplifier which was installed in Serial Numbers 3 and 4. The data for serial numbers 3 and 4 are shown in Figures 8a, 8b, 9a, 9b, 10a and 10b. These data include temperature runs which to simulate the temperature variations will be experienced by the two different assemblies on the moon. Two ovens were used, one which contained the sensor electronics assembly, and the other which contained the power converter and digital blivit assemblies. The sensor electronics assembly was run from  $-50^{\circ}\text{C}$  to  $100^{\circ}\text{C}$ , while, at the same time, the inboard electronics was run from  $-20^{\circ}\text{C}$  to  $+55^{\circ}\text{C}$ . Therefore, the headings at the top of the columns in the tables are so noted.

The test results for serial number 4, which is the latest unit that was shipped are plotted graphically in Figures 8b, 9b, 10b. Figure 8a, b is the data for the microphone channel and includes the calibration crystal which is mounted diametrically opposite to the microphone sensor crystal on the sensor plate; it includes the transfer function through this crystal, the microphone amplifier, PHA, and digital processing. The variation from the two temperature extremes

MIC DETECTOR INPUT(mv)	
SN/1	+25°C
PHA	
1	110
2	180
3	273
4	400
5	660
6	1230
7	2500

Figure 6. MIC PULSE HEIGHT ANALYSIS DATA,  
SN1 (Driving into Mic Amp)

FILM AMPLIFIER CALIBRATE INPUT (mv)		
	SN/1	+25°C
PHA	A	B
1	11	11
2	13	14
3	21	20
4	30	32
5	44	45
6	67	68
7	100	100
8	149	150
9	220	219
10	340	320
11	470	460
12	710	690
13	1030	1000
14	2950	2650
15	5400	6800

Figure 7. FILM PULSE HEIGHT ANALYSIS DATA  
SN 1

CALIBRATE CRYSTAL INPUT (millivolts)									
SN/3					SN/4				
	+25°C	-50°C -20°C	+100°C +55°C	+25°C	-50°C -20°C	+100°C +55°C	+25°C		
1	5.93	5.86	6.76	6.20	5.76	6.52	6.44		
2	9.11	9.14	10.5	9.82	9.50	10.3	10.9		
3	14.8	14.9	17.0	16.4	16.0	16.2	17.4		
4	25.1	25.6	28.6	26.5	27.0	26.6	28.6		
5	42.6	45.0	48.3	44.9	45.7	45.0	48.3		
6	74.0	77.6	83.7	84.0	81.8	79.4	85.4		
7	134	*	*	147	143	149	157		

Figure 8a. PULSE HEIGHT ANALYSIS DATA, MICROPHONE,  
SN 3 & 4

\*Step 7, on SN3 exceeded GSE Range capability.  
This anomaly was connected on SN4.




Figure 8b. MICROPHONE CHANNEL CALIBRATION  
GRAPH, SN 4



FILM A AMPLIFIER INPUT (nano-amps)

PHA	SN/3			SN/4		
	+25°C	-50°C -20°C	+100°C +55°C	+25°C	-50°C -20°C	+100°C +55°C
1	81.3	74.7	91.6	59.5	58.1	62.2
2	105	96.1	111	80.8	80.8	84.6
3	135	131	142	110	111	114
4	180	175	189	152	153	155
5	240	238	249	207	211	209
6	326	324	338	285	289	287
7	444	444	460	394	403	396
8	608	610	626	546	557	545
9	844	860	864	756	776	750
10	1170	1200	1190	1050	1080	1040
11	1630	1670	1640	1460	1490	1440
12	2440	2500	2440	2160	2290	2190
13	5600	3440	9140	3000	3150	3940
14	19800	13200	23300	12900	8140	15800
15	39800	34500	43300	30700	28200	32700

Figure 9a. PULSE HEIGHT ANALYSIS DATA, FILM.A




Figure 9b. FILM A CHANNEL CALIBRATION  
GRAPH, SN 4

FILM B AMPLIFIER INPUT (nano-amps)							
PHA	SN/3			SN/4			
	+25°C	-50°C -20°C	+100°C +55°C	+25°C	-50°C -20°C	+100°C +55°C	
1	77.5	68.5	80.3	59.8	57.2	62.1	
2	97.0	88.5	102	77.5	74.4	80.9	
3	130	119	133	106	102	109	
4	177	162	183	146	141	149	
5	236	218	246	202	196	207	
6	321	299	330	278	271	284	
7	440	410	448	384	378	392	
8	604	560	613	534	531	543	
9	833	787	840	740	745	747	
10	1150	1090	1160	1030	1050	1040	
11	1590	1510	1610	1440	1470	1440	
12	2360	2250	2380	2110	2150	2090	
13	5610	3110	8010	3350	2990	4320	
14	19250	13100	21600	15900	12900	16900	
15	38200	32100	40000	34500	33000	35000	

Figure 1Ca. PULSE HEIGHT ANALYSIS DATA, FILM B




Figure 10b. FILM B CHANNEL CALIBRATION  
GRAPH, SN 4

is noted at the lowest levels and is well within the expected noise of the calibrate crystal input and is within a millivolt of input signal. The data stability improves as the signal level increases. It may be noted that since the gain of the microphone amplifier channel is approximately  $0.3 \times 10^4$  from the microphone sensor to the gain of 2 amplifiers and is therefore, approximately  $.6 \times 10^4$  to the comparator, we see with the threshold of the microphone comparator is approximately 250 millivolts, which when divided by  $.6 \times 10^4$  is 40. Six millivolts at the calibrate crystal. At threshold, is equal to an impact occurring on the plate causing a 40 to 50 microvolt signal at the input of the microphone channel. The lowest levels in the test data correspond to these small signals at the input to the microphone amplifier channel through the two crystals. Figures 9a and 10a give the test data for the Serial Numbers 3 and 4, Film amplifiers and digital conversion logic. Here, the data could have been represented in equivalent nanovolts since the input impedance of the film amplifier is known (3K). The dynamic range from the first to the 15th step is approximately 500 to 1, and the stability of the numbers is quite good over the wide extreme of temperature. The results are plotted graphically in Figures 9b and 10b for serial number 4. We see the nonlinear region of the channel in the upper right hand corner including the 12th through the 15th steps. A gain change is inserted in the linear amplifier by a simple diode/capacitor network. The excursions here are those due to the diode temperature coefficient which have been only partially compensated. The gain of the amplifier in this region has been reduced drastically, so that a large dynamic range may be achieved on the high steps while maintaining a high resolution on the lower levels. The drift of the amplifier channel under temperature on the majority of the linear range is almost negligible. The 81 nanoamp threshold is a very realistic threshold for capacitor sensors. The physical size of the system being small, these data represent a significant advance in the state of the art in amplifiers, detection, and digital conversion.

The transfer function from GSE to sensor input for these temperature runs are shown in Figure 11.

The data in these graphs, enable the correlation of GSE test data in volts to actual sensor equivalent  $\mu\text{v}$  or na.

Figure 12 gives the nominal calibration of the sensistor temperature probe which is mounted in the sensor electronics unit and is excited by a 5 milliamper current, the voltages and resistances listed in this curve are those obtained from the manufacturer. An actual run using visual interpretation of the meter circuit in the GSE is also shown in Figure 12. Notice the close correlation with the manufacturers' data to that temperature reading which is actually observed on the front panel.

### MECHANICAL DESIGN AND TEST RESULTS

The logic unit of the Surveyor Ejecta Detector was designed with the concept of obtaining a structurally sound package with weight kept to a minimum. The logic unit is located on the spacecraft in a cantilevered position necessitating good structural strength with the package.

In order to meet the structural requirements the two housings were fabricated from solid blocks of magnesium giving each housing a homogeneous structure with excellent rigidity. The magnesium material, type AZ31B magnesium tooling plate, was used because of its good vibration dampening characteristics and high strength to weight ratio. Fabricating the housings out of solid blocks also simplified the design of a build-in wire well, a small channel shaped groove around the outside perimeter for inserting R-f gasketing for minimizing electrical interferences.




Figure 11. Overall Transfer Functions




Figure 12. TEMPERATURE PROBE CALIBRATION CURVES



Two cross member shear webs are incorporated into each housing for internal rigidity and relieved with lighting holes to minimize weight. Relief cutouts were used on all exterior surfaces wherever possible to reduce weight without sacrificing the strength of the housings.

The two covers are also fabricated from AZ31B magnesium tooling plate. Four stiffening webs are designed into each cover to give support to the package when mounted cantilevered on the spacecraft. Relief cutouts were also utilized on each cover to reduce weight without sacrificing strength.

The two housings and associated covers are entirely gold plated in order to obtain good electrical contact between the R-F gasketing mesh and the magnesium surfaces of the completed package.

All modules that are used in the logic unit were designed and fabricated by Marshall Laboratories. The modules are point-to-point welded and of the cordwood type construction. Components are positioned between two mylar wafers with their bodies in close physical proximity with one another and their leads parallel. The component leads are connected by means of welding interconnecting alloy 180 ribbon. The lead out wires from the module are also alloy 180, this material is used because of its non-magnetic properties. After electrical check of the module, they are dip coated with epoxy in order to provide greater resistance to environmental effects such as shock and vibration. The epoxy also provides an efficient means of conductive heat removal. The average size of the modules are .600 X .400 X .650 and the average weight 3.0 gram. The logic unit utilizes 76 welded modules of 29 different circuits.

A welded matrix was used for the interconnections required between modules. The welding process was decided upon because welding forms a permanent connection, whereas soldering suffers

the weakness of a separable connection. In addition, welding is a stable process, which permits repeatability and control during fabrication. Welding also assures the reliability of assembled electronic components, because heat is localized in the joining process and is less likely to induce thermal damage.

The welded matrix consists of an epoxy glass support .016" thick on which the modules are mounted. An .031 epoxy glass spacer separates the support board from the matrix, the matrix consists of two layers of alloy 180 wires at right angles to each other, separated by .008" mylar film. Wires on one side of the mylar all run vertically and all wires on the other side run horizontally. Welds are made through holes in the mylar film in order to make connections between the perpendicular matrix wires. An .031" thick epoxy glass spacer separates the bottom of the matrix from the interconnecting board which is .031" thick. Module lead out wires are inserted through holes in the support board and protrude through mating holes in interconnecting board. Interconnecting alloy 180 ribbon is welded between the module lead out wires and lead out wires from the matrix. Excess ribbon and lead out wires are clipped after welding. Terminals are swaged onto either the support board or interconnecting board for the termination of wires that lead out to the connectors.

After final calibration and electrical check, the completed matrix and module assembly was coated with solithane 113 a liquid urethane prepolymer. The unit was then foamed using eccofoam FPH a high temperature polyurethane, rigid, foam-in-place resin. To secure the electronics in each of the housings. This method was employed to maintain minimum weight and to meet the severe environmental requirements.

The completed package for the electronics of the logic unit measures 6.00" X 5.25" X 3.56" and weighs 1085 grams.

The packaging of the sensor electronics followed the same philosophy as that for the packaging of the logic unit. Magnesium was used in the fabrication of the housing and covers.

The sensor electronics with sensor plate mounted measures 10.00" X 2.25" X 9.34" and weighs 723 grams. The sensor plate was fabricated from aluminum alloy 6061-T651 and delivered to GSFC for the depositing of the films. The plate is isolated from the housing to which it is mounted by means of six silicone grommets. The initial prototype used silicone grommets with a Shore Durometer hardness of 50, the sensor assembly was vibrated at Jet Propulsion Laboratory to the Surveyor Vibration Specification. The results of the test indicated that the grommets were tearing away from their mounting holes. To alleviate this problem, the unit was refitted with silicone grommets that used a Shore Durometer hardness of 70, and an oversize flat washer was placed between the grommet and the bottom of the head of the mounting screw. The unit was again vibrated to the Surveyor vibration specification with the correction and the results being that the tearing of the grommets was eliminated.

The Surveyor Ejecta Detector GSE is packaged into a standard Optina Cabinet that measures 11 1/4" X 20" X 22". The electronics can be removed from the cabinet by pulling on the handles provided. The circuitry is distributed among 80 modules which are welded onto three welded matrix assemblies. The three module matrix assemblies are accessible and independently removable from the main chassis. This is accomplished by having each module matrix assembly having individual pigtailed plug-in connectors that tie into the main harnessing. A nulling printed circuit board is located accessibly so that calibration and trimming of the potentiometers can be done with all other circuitry intact. All printed circuit boards and welded module matrices are protected by solithane 113.

A cable compartment is provided in the rear of the cabinet for the storing of cables and miscellaneous items. A box that can be plugged into the rear of the cabinet and extend to the front is provided for monitoring pertinent data points by means of test jacks.

ML/TN 2300.55  
Page 55.

## APPENDIX A

### NEW MODULES USED IN THE EXPERIMENT

The following circuits were designed for the Surveyor Ejecta Detector. The design goals included operation of analog circuits within 1 percent of room temperature value over a temperature range of  $-55^{\circ}\text{C}$  to  $+100^{\circ}\text{C}$ . The additional limitations were space and power. They are listed numerically with increasing part number.

#### W233-7 One Shot Module.

This module was designed to have the characteristics of the W230 one shot module, with additional components R2 CR1, CR2 and CR3 added to give this module maximum noise rejection. The noise voltage on any line has to exceed at least 0.5 volt before triggering will occur. Resistor R2 and diode CR1 relieve collector load R1 of capacitance C1 and enables the collector waveform recovery time to be minimum.

#### W4151 Low Level Amplifier.

This module is used to amplify the microphone signals in the first three stages of the mic channel. It has an nominal gain of 10 which is established by the ratio of R6 to R7. It operates well above the 3 db frequency of the transistors; that is, the current drain of both transistors is minimized so as to conserve power. The total power dissipated in this stage is 1.8 milliwatts. The stability of this stage is nominally 1% over the  $-55^{\circ}\text{C}$  to  $100^{\circ}\text{C}$  temperature range. The input impedance is approximately 70K and the output impedance is approximately 300 ohms.

#### W4152 and W4153 High Speed Comparator Module.

This circuit was designed to operate at data rates up to 500 KC. It consists of a differential amplifier stage and emitter follower isolation state. A PNP amplifier stage driver state speed is achieved

through clamping the collector waveforms of the first differential amplifier stage with diodes CR1 and CR2, thereby limiting the charging of the stray capacitances in the circuit. Additional clamping occurs in diodes CR3 and CR4. The outputs of this comparator are Pin 7 and Pin 12 of W4153. When a positive signal is applied to input A of W4152, output Q will go to a one. Output  $\bar{Q}$  will go to a zero. Similarly, if a positive signal is applied to input B on W4152, output  $\bar{Q}$  will go to a one. The power dissipated in these two modules is 14.7 milliwatts on the +12, 1.68 milliwatts on the +6 v supply and 11.0 milliwatts on the -7 v, giving a total power dissipation of 27.4 milliwatts.

#### W4154 And Logic Module.

This is an noninverting gate requiring coincidence at the input for an output one. It is used to obtain a very fast leading edge on positive going waveform. It is designed for a +3 v power supply and is used to drive gated clock module W4159. Since both transistors are normally in the off state, the power dissipation in this module is caused by that current through R1, and is approximately 30 microwatts.

#### W4155 Parallel AND Logic Gate Module.

This is essentially the same as W4154; the collector load on Q2 has been omitted so that one or more of these modules may be in parallel at the output to form the "OR" function.

#### W4157 Command Interface Module.

This module is essentially a one shot. The input trigger level has been adjusted. The input impedance has been increased by the addition of R7 in the input line. The level at which the one shot triggers is established by the voltage divider R4, CR3, R5 and R6.

W4158 Sure Starting Clock Module.

This module is an astable multivibrator which was designed to run at 100 cycles per second continuously. This clock overcomes the difficulty of some astable multivibrators, which saturate both transistors immediately upon power turn-on. The nonsaturation of both transistors is accomplished by the choice of values of resistor R1 and the collector loads R5 and R4. If both transistors were saturated, the potential across R1 would be such that it would exceed either of the potentials at R4 or R5, thereby the transistors would have to be paradoxically turned-off. Therefore, since both cannot saturate, one of the transistors will be turned on and the other turned off after power turn-on. Transistor Q3 is a isolating amplifier which drives switch Q4 to a 3v logic level. This clock is designed to maintain a frequency stability of better than 1% over the temperature range of  $-55^{\circ}\text{C}$  to  $+100^{\circ}\text{C}$ .

W4159 Gated Clock Module.

This clock was designed to start very rapidly upon receipt of a clock control signal and is used in the pulse analyzer section where delay times in starting the gated time must be minimized since it is utilized in a pulse height to time conversion. This minimal delay is achieved by coupling the leading edge of the applied clock control pulse through transistor Q4 to the base of transistor Q1 which is to be turned on. Q1 immediately saturates, turning Q2 off. This signal results in a positive-going signal applied to the base of Q3, the saturating switch. The collector of Q3 is the output of the module. Upon application of the clock control pulse to Pin 11 the output at Q3 goes negative. The output is a square wave at the frequency determined by the external capacitors which are applied across Pins 3, 7, 12 and 9.



#### W4160 Final Amplifier Module.

This amplifier, which has a gain of 10, is the final stage in the microphone amplifier channel. Its input impedance is in excess of 70K and its output impedance is less than 300 ohms. The output has a wide dynamic swing accommodating signals within 50 millivolts to 2.5 volts. Its power dissipation is +1.8 milliwatts.

#### W4167 Detector Module.

This module is used in the microphone channel to detect peaks of the incoming wave. The input is applied through Pin 17 and C1 to one side of a matched pair differential amplifier transistor Q1. The other side of the differential pair is driven from the feedback network through amplifier stages Q2 and Q3. The output is taken off of the second base of the differential pair and appears across an external capacitor which charges to the highest level of the incoming signal. Since the feedback around the amplifier results in unity gain, the output level is equal to the input signal peak. The base drive of transistor Q3 is sufficient to charge the external capacitor at 100 KC rate. The detector is stable to within 1% over the -55°C to 100°C range.

#### W4168 Inhibit and Hold Module.

The inhibit portion of this module operates on a positive pulse applied at Pin 5 which causes Q1 and Q2 to conduct and saturate. The current through Q2 causes a large current in the output line of Pin 6 which comes from the common emitter point of detector module W4167. This effectively clamps the common emitters of the W4167 module at a high potential thereby disabling that detector from receiving further information. When the inhibit command is at a zero level, transistor Q2 is turned off; therefore, no current flows through R7

and the output lead. The hold section of this module operates on a positive command on Pin 8, turning transistor Q5 on, and thereby turning transistor Q4 off. When transistor Q4 turns off, the output transistor Q3 is also turned off and no current flows through the output lead in Pin 7. This output lead is attached through a resistor to the integrating capacitor at the output of the detector module. When current flows through transistor Q3, the capacitor is discharged. In the event that a hold signal is not present, transistor Q3 is conducting thereby maintaining the capacitor at the output of the detector continuously discharged.

#### W4169 Gain of Two Amplifier Modules.

This module is very similar to final amplifier module W4160. It is used in the microphone channel and its signal is taken from the output of the detector. The use of the gain of two relieves the detector of having to perform over an excessively large dynamic range.

#### W4170 SCO Driver Module.

This module is a three stage inverting amplifier which is used to condition the three volt logic level signals received at the output of the telemetry coding section and converts the signals to 6-volt-to-0 volt logic levels, with accurately controlled rise and fall times.

#### W4171 Trigger Module.

This module is a level detector circuit, the threshold level being established by resistors R2, CR1 and R5. If the level at the input drops below a given value, transistor Q1 will conduct causing transistor Q2 to go to a zero.

W4172 Integrator Module.

This module consists of an inverting amplifier stage which drives the integrating capacitor and a dual transistor feedback-type emitter follower. A high data rate of positive pulses applied at the input and hence to Q1, causes Q1 to discharge an external capacitor connected between Pin 7 to B+, thereby causing the DC level at the base of Q2 to drop. The DC level is transmitted at the output at a very low impedance to drive a logic circuit.



W4176 Detector Module.

This module is used to peak detect the film signal. It is designed to follow a very rapid rise time and to offer a high impedance to the charged capacitor, so that its discharging time constant will be very long. The high impedance is realized by the use of emitter follower matched pair differential transistor Q1 which is inserted in the closed feed back loop consisting of Q2 and Q3. This detector has a wide dynamic range and is capable of handling signals up to 5 volts.

W233

REV. 10/65

COMPONENTS & HEADER  
 OMITTED FOR SIMPLICITY



ELECTRONIC SCHEMATIC

W233

SEE SEPARATE LIST OF MATERIAL

DO NOT SCALE DRAWING


UNLESS OTHERWISE SPECIFIED

DIMENSIONS IN INCHES

SIZE	TOLERANCE	LIBRARY TOLERANCES
.0125 TO .031	.125	+.004-.001
.031 TO .062	.250	+.005-.001
.062 TO .125	.500	+.005-.001
.125 TO .250	.750	+.005-.001
.250 TO .500	1.000	+.010-.001
.500 TO 1.000	1.500	+.012-.001
1.000 TO 2.000	2.000	+.012-.001
2.000 TO 4.000	2.500	+.012-.001
4.000 TO 6.000	3.000	+.012-.001
6.000 TO 8.000	3.500	+.012-.001
8.000 TO 10.000	4.000	+.012-.001
10.000 TO 12.000	4.500	+.012-.001
12.000 TO 14.000	5.000	+.012-.001
14.000 TO 16.000	5.500	+.012-.001
16.000 TO 18.000	6.000	+.012-.001
18.000 TO 20.000	6.500	+.012-.001
20.000 TO 22.000	7.000	+.012-.001
22.000 TO 24.000	7.500	+.012-.001
24.000 TO 26.000	8.000	+.012-.001
26.000 TO 28.000	8.500	+.012-.001
28.000 TO 30.000	9.000	+.012-.001
30.000 TO 32.000	9.500	+.012-.001
32.000 TO 34.000	10.000	+.012-.001
34.000 TO 36.000	10.500	+.012-.001
36.000 TO 38.000	11.000	+.012-.001
38.000 TO 40.000	11.500	+.012-.001
40.000 TO 42.000	12.000	+.012-.001
42.000 TO 44.000	12.500	+.012-.001
44.000 TO 46.000	13.000	+.012-.001
46.000 TO 48.000	13.500	+.012-.001
48.000 TO 50.000	14.000	+.012-.001
50.000 TO 52.000	14.500	+.012-.001
52.000 TO 54.000	15.000	+.012-.001
54.000 TO 56.000	15.500	+.012-.001
56.000 TO 58.000	16.000	+.012-.001
58.000 TO 60.000	16.500	+.012-.001
60.000 TO 62.000	17.000	+.012-.001
62.000 TO 64.000	17.500	+.012-.001
64.000 TO 66.000	18.000	+.012-.001
66.000 TO 68.000	18.500	+.012-.001
68.000 TO 70.000	19.000	+.012-.001
70.000 TO 72.000	19.500	+.012-.001
72.000 TO 74.000	20.000	+.012-.001
74.000 TO 76.000	20.500	+.012-.001
76.000 TO 78.000	21.000	+.012-.001
78.000 TO 80.000	21.500	+.012-.001
80.000 TO 82.000	22.000	+.012-.001
82.000 TO 84.000	22.500	+.012-.001
84.000 TO 86.000	23.000	+.012-.001
86.000 TO 88.000	23.500	+.012-.001
88.000 TO 90.000	24.000	+.012-.001
90.000 TO 92.000	24.500	+.012-.001
92.000 TO 94.000	25.000	+.012-.001
94.000 TO 96.000	25.500	+.012-.001
96.000 TO 98.000	26.000	+.012-.001
98.000 TO 100.000	26.500	+.012-.001

REV.	PART NO.	DESCRIPTION	QTY. REQUIRED
LIST OF MATERIALS			
FINISH			
HEAT TREAT			
<div style="display: flex; justify-content: space-between;"> <div> <p>DATE: 10/1/64</p> <p>BY: [Signature]</p> <p>FOR: [Signature]</p> </div> <div> <p>ONE SHOT MODULE</p> </div> <div> <p>SCALE 10/1</p> </div> </div>			
<div style="display: flex; justify-content: space-between;"> <div> <p>7 APR 64</p> <p>RELEASED</p> </div> <div> <p>MARSHALL LABORATORIES</p> </div> <div> <p>W233</p> </div> </div>			
MFG CODE 10-10			

1. USE 2. SPECIFY		Part 15 DISPOSITIONS 3. DISPOSE AS REQUESTED 4. DISPOSE	W4151	1/1
REVISIONS				
REV	DATE	DESCRIPTION	BY	DATE
1	1/1	REMOVED PIN 18,	5.	1/1
2	1/1	SHIELD GRD IS NOW	6.	1/1
3	1/1	PIN 2	7.	1/1



W4151

DO NOT SCALE DRAWING

UNLESS OTHERWISE SPECIFIED

UNLESS OTHERWISE SPECIFIED

ITEM	QTY	DESCRIPTION	UNIT
1	1	100K 1/2W	RES
2	1	100K 1/2W	RES
3	1	100K 1/2W	RES
4	1	100K 1/2W	RES
5	1	100K 1/2W	RES
6	1	100K 1/2W	RES
7	1	100K 1/2W	RES
8	1	100K 1/2W	RES
9	1	100K 1/2W	RES
10	1	100K 1/2W	RES
11	1	100K 1/2W	RES
12	1	100K 1/2W	RES
13	1	100K 1/2W	RES
14	1	100K 1/2W	RES
15	1	100K 1/2W	RES
16	1	100K 1/2W	RES
17	1	100K 1/2W	RES
18	1	100K 1/2W	RES
19	1	100K 1/2W	RES
20	1	100K 1/2W	RES
21	1	100K 1/2W	RES
22	1	100K 1/2W	RES
23	1	100K 1/2W	RES
24	1	100K 1/2W	RES
25	1	100K 1/2W	RES
26	1	100K 1/2W	RES
27	1	100K 1/2W	RES
28	1	100K 1/2W	RES
29	1	100K 1/2W	RES
30	1	100K 1/2W	RES
31	1	100K 1/2W	RES
32	1	100K 1/2W	RES
33	1	100K 1/2W	RES
34	1	100K 1/2W	RES
35	1	100K 1/2W	RES
36	1	100K 1/2W	RES
37	1	100K 1/2W	RES
38	1	100K 1/2W	RES
39	1	100K 1/2W	RES
40	1	100K 1/2W	RES
41	1	100K 1/2W	RES
42	1	100K 1/2W	RES
43	1	100K 1/2W	RES
44	1	100K 1/2W	RES
45	1	100K 1/2W	RES
46	1	100K 1/2W	RES
47	1	100K 1/2W	RES
48	1	100K 1/2W	RES
49	1	100K 1/2W	RES
50	1	100K 1/2W	RES
51	1	100K 1/2W	RES
52	1	100K 1/2W	RES
53	1	100K 1/2W	RES
54	1	100K 1/2W	RES
55	1	100K 1/2W	RES
56	1	100K 1/2W	RES
57	1	100K 1/2W	RES
58	1	100K 1/2W	RES
59	1	100K 1/2W	RES
60	1	100K 1/2W	RES
61	1	100K 1/2W	RES
62	1	100K 1/2W	RES
63	1	100K 1/2W	RES
64	1	100K 1/2W	RES
65	1	100K 1/2W	RES
66	1	100K 1/2W	RES
67	1	100K 1/2W	RES
68	1	100K 1/2W	RES
69	1	100K 1/2W	RES
70	1	100K 1/2W	RES
71	1	100K 1/2W	RES
72	1	100K 1/2W	RES
73	1	100K 1/2W	RES
74	1	100K 1/2W	RES
75	1	100K 1/2W	RES
76	1	100K 1/2W	RES
77	1	100K 1/2W	RES
78	1	100K 1/2W	RES
79	1	100K 1/2W	RES
80	1	100K 1/2W	RES
81	1	100K 1/2W	RES
82	1	100K 1/2W	RES
83	1	100K 1/2W	RES
84	1	100K 1/2W	RES
85	1	100K 1/2W	RES
86	1	100K 1/2W	RES
87	1	100K 1/2W	RES
88	1	100K 1/2W	RES
89	1	100K 1/2W	RES
90	1	100K 1/2W	RES
91	1	100K 1/2W	RES
92	1	100K 1/2W	RES
93	1	100K 1/2W	RES
94	1	100K 1/2W	RES
95	1	100K 1/2W	RES
96	1	100K 1/2W	RES
97	1	100K 1/2W	RES
98	1	100K 1/2W	RES
99	1	100K 1/2W	RES
100	1	100K 1/2W	RES

LIST OF MATERIALS	
ITEM	DESCRIPTION
1	100K 1/2W
2	100K 1/2W
3	100K 1/2W
4	100K 1/2W
5	100K 1/2W
6	100K 1/2W
7	100K 1/2W
8	100K 1/2W
9	100K 1/2W
10	100K 1/2W
11	100K 1/2W
12	100K 1/2W
13	100K 1/2W
14	100K 1/2W
15	100K 1/2W
16	100K 1/2W
17	100K 1/2W
18	100K 1/2W
19	100K 1/2W
20	100K 1/2W
21	100K 1/2W
22	100K 1/2W
23	100K 1/2W
24	100K 1/2W
25	100K 1/2W
26	100K 1/2W
27	100K 1/2W
28	100K 1/2W
29	100K 1/2W
30	100K 1/2W
31	100K 1/2W
32	100K 1/2W
33	100K 1/2W
34	100K 1/2W
35	100K 1/2W
36	100K 1/2W
37	100K 1/2W
38	100K 1/2W
39	100K 1/2W
40	100K 1/2W
41	100K 1/2W
42	100K 1/2W
43	100K 1/2W
44	100K 1/2W
45	100K 1/2W
46	100K 1/2W
47	100K 1/2W
48	100K 1/2W
49	100K 1/2W
50	100K 1/2W
51	100K 1/2W
52	100K 1/2W
53	100K 1/2W
54	100K 1/2W
55	100K 1/2W
56	100K 1/2W
57	100K 1/2W
58	100K 1/2W
59	100K 1/2W
60	100K 1/2W
61	100K 1/2W
62	100K 1/2W
63	100K 1/2W
64	100K 1/2W
65	100K 1/2W
66	100K 1/2W
67	100K 1/2W
68	100K 1/2W
69	100K 1/2W
70	100K 1/2W
71	100K 1/2W
72	100K 1/2W
73	100K 1/2W
74	100K 1/2W
75	100K 1/2W
76	100K 1/2W
77	100K 1/2W
78	100K 1/2W
79	100K 1/2W
80	100K 1/2W
81	100K 1/2W
82	100K 1/2W
83	100K 1/2W
84	100K 1/2W
85	100K 1/2W
86	100K 1/2W
87	100K 1/2W
88	100K 1/2W
89	100K 1/2W
90	100K 1/2W
91	100K 1/2W
92	100K 1/2W
93	100K 1/2W
94	100K 1/2W
95	100K 1/2W
96	100K 1/2W
97	100K 1/2W
98	100K 1/2W
99	100K 1/2W
100	100K 1/2W

LOW LEVEL  
AMPLIFIER


MARSHALL  
LABORATORIES

W4151

1. 001	0010 0007 001000	W4152	L
2. 000001	3. 000-001 0000000		
REVISIONS			
REV	DATE	BY	REASON
4-18UP	A	REVISED	ERRON SIZE


LEAD N<sup>o</sup> 1

.900  
MAX.



W4152-200

LAST WELD N<sup>o</sup> 226



ELECTRONIC SCHEMATIC

W4152

1A

SEE SEPARATE LIST OF MATERIALS

ITEM	QUANTITY	DESCRIPTION	DATE
LIST OF MATERIALS			
FROM			
NEW TEST			
RELEASED APR 9 1967			
MARSHALL LABORATORIES			
W4152			

DO NOT SCALE DRAWING


UNLESS OTHERWISE SPECIFIED

DIMENSIONS IN INCHES

ITEM	QUANTITY	DESCRIPTION	DATE
LIST OF MATERIALS			
FROM			
NEW TEST			
RELEASED APR 9 1967			
MARSHALL LABORATORIES			
W4152			

HIGH SPEED  
COMPARATOR  
INPUT  
MODULE

CAST WELD N2 230



W 4153

NY 100		100-100000		100-100000	
LIST OF MATERIALS					
FROM		RELEASED APR 9 1964			
REAY TAYLOR					
Mr. J. Edgar Hoover Mr. J. A. Tamm Mr. Clegg Mr. Glavin Mr. Ladd Mr. Nichols Mr. Rosen Mr. Tracy Mr. Harbo Mr. Mohr Mr. Winterrowd Mr. Tele. Rm. Mr. Holloman Miss Gandy		HIGH SPEED COMPRESSOR OUTPUT MODULE		MARSHALL LABORATORIES W4153 100-100000	
DATE 10/1/63		WORK		D 100-100000	

1910

[illegible]

W4154



DO NOT SCALE DRAWING			
UNLESS OTHERWISE SPECIFIED			
DIMENSIONS IN INCHES			
		SOLE DIA.	TOLERANCE
		.6120 YTD	.125 ± .004 - .001
		.120 YTD	.250 ± .004 - .001
		.250 YTD	.500 ± .004 - .001
		.500 YTD	.750 ± .004 - .001
		1.000 YTD	1.000 ± .004 - .001
		1.500 YTD	1.500 ± .004 - .001
		2.000 YTD	2.000 ± .004 - .001
		2.500 YTD	2.500 ± .004 - .001
		3.000 YTD	3.000 ± .004 - .001
		3.500 YTD	3.500 ± .004 - .001
		4.000 YTD	4.000 ± .004 - .001
		4.500 YTD	4.500 ± .004 - .001
		5.000 YTD	5.000 ± .004 - .001
		5.500 YTD	5.500 ± .004 - .001
		6.000 YTD	6.000 ± .004 - .001
		6.500 YTD	6.500 ± .004 - .001
		7.000 YTD	7.000 ± .004 - .001
		7.500 YTD	7.500 ± .004 - .001
		8.000 YTD	8.000 ± .004 - .001
		8.500 YTD	8.500 ± .004 - .001
		9.000 YTD	9.000 ± .004 - .001
		9.500 YTD	9.500 ± .004 - .001
		10.000 YTD	10.000 ± .004 - .001
		10.500 YTD	10.500 ± .004 - .001
		11.000 YTD	11.000 ± .004 - .001
		11.500 YTD	11.500 ± .004 - .001
		12.000 YTD	12.000 ± .004 - .001
		12.500 YTD	12.500 ± .004 - .001
		13.000 YTD	13.000 ± .004 - .001
		13.500 YTD	13.500 ± .004 - .001
		14.000 YTD	14.000 ± .004 - .001
		14.500 YTD	14.500 ± .004 - .001
		15.000 YTD	15.000 ± .004 - .001
		15.500 YTD	15.500 ± .004 - .001
		16.000 YTD	16.000 ± .004 - .001
		16.500 YTD	16.500 ± .004 - .001
		17.000 YTD	17.000 ± .004 - .001
		17.500 YTD	17.500 ± .004 - .001
		18.000 YTD	18.000 ± .004 - .001
		18.500 YTD	18.500 ± .004 - .001
		19.000 YTD	19.000 ± .004 - .001
		19.500 YTD	19.500 ± .004 - .001
		20.000 YTD	20.000 ± .004 - .001
		20.500 YTD	20.500 ± .004 - .001
		21.000 YTD	21.000 ± .004 - .001
		21.500 YTD	21.500 ± .004 - .001
		22.000 YTD	22.000 ± .004 - .001
		22.500 YTD	22.500 ± .004 - .001
		23.000 YTD	23.000 ± .004 - .001
		23.500 YTD	23.500 ± .004 - .001
		24.000 YTD	24.000 ± .004 - .001
		24.500 YTD	24.500 ± .004 - .001
		25.000 YTD	25.000 ± .004 - .001
		25.500 YTD	25.500 ± .004 - .001
		26.000 YTD	26.000 ± .004 - .001
		26.500 YTD	26.500 ± .004 - .001
		27.000 YTD	27.000 ± .004 - .001
		27.500 YTD	27.500 ± .004 - .001
		28.000 YTD	28.000 ± .004 - .001
		28.500 YTD	28.500 ± .004 - .001
		29.000 YTD	29.000 ± .004 - .001
		29.500 YTD	29.500 ± .004 - .001
		30.000 YTD	30.000 ± .004 - .001
		30.500 YTD	30.500 ± .004 - .001
		31.000 YTD	31.000 ± .004 - .001
		31.500 YTD	31.500 ± .004 - .001
		32.000 YTD	32.000 ± .004 - .001
		32.500 YTD	32.500 ± .004 - .001
		33.000 YTD	33.000 ± .004 - .001
		33.500 YTD	33.500 ± .004 - .001
		34.000 YTD	34.000 ± .004 - .001
		34.500 YTD	34.500 ± .004 - .001
		35.000 YTD	35.000 ± .004 - .001
		35.500 YTD	35.500 ± .004 - .001
		36.000 YTD	36.000 ± .004 - .001
		36.500 YTD	36.500 ± .004 - .001

ITEMS	POST NO	DESCRIPTION	CAT	DATE
LIST OF MATERIALS				
FROM		RELEASED APR 9 1984		
TO				
BY				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				
REMARKS				
INITIALS				
SIGNATURE				
DATE				
TIME				
LOCATION				



1. USE 2. REVISED		PARTS DISPOSITION 3. CHANGE OF QUANTITY 4. RECORD		5. ....		W 4155		A	
REVISIONS									
DATE	BY	STA	DESCRIPTION			BY	DATE	APPROVAL	
11/1/54	EP	A	REVISED RIBBON SIZE			EP	11/1/54		

HEADER  
STRUCTURE




ELECTRONIC SCHEMATIC

W 4155  
A

SEE SEPARATE LIST OF MATERIALS.

DO NOT SCALE DRAWING			
UNLESS OTHERWISE SPECIFIED			
DIMENSIONS IN INCHES			
SIZE	TOLERANCE	SIZE	TOLERANCE
.0150 TO .0175	±.0005	.0175 TO .0200	±.0010
.0200 TO .0225	±.0010	.0225 TO .0250	±.0015
.0250 TO .0275	±.0015	.0275 TO .0300	±.0020
.0300 TO .0325	±.0020	.0325 TO .0350	±.0025
.0350 TO .0375	±.0025	.0375 TO .0400	±.0030
.0400 TO .0425	±.0030	.0425 TO .0450	±.0035
.0450 TO .0475	±.0035	.0475 TO .0500	±.0040
.0500 TO .0525	±.0040	.0525 TO .0550	±.0045
.0550 TO .0575	±.0045	.0575 TO .0600	±.0050
.0600 TO .0625	±.0050	.0625 TO .0650	±.0055
.0650 TO .0675	±.0055	.0675 TO .0700	±.0060
.0700 TO .0725	±.0060	.0725 TO .0750	±.0065
.0750 TO .0775	±.0065	.0775 TO .0800	±.0070
.0800 TO .0825	±.0070	.0825 TO .0850	±.0075
.0850 TO .0875	±.0075	.0875 TO .0900	±.0080
.0900 TO .0925	±.0080	.0925 TO .0950	±.0085
.0950 TO .0975	±.0085	.0975 TO .1000	±.0090
.1000 TO .1025	±.0090	.1025 TO .1050	±.0095
.1050 TO .1075	±.0095	.1075 TO .1100	±.0100
.1100 TO .1125	±.0100	.1125 TO .1150	±.0105
.1150 TO .1175	±.0105	.1175 TO .1200	±.0110
.1200 TO .1225	±.0110	.1225 TO .1250	±.0115
.1250 TO .1275	±.0115	.1275 TO .1300	±.0120
.1300 TO .1325	±.0120	.1325 TO .1350	±.0125
.1350 TO .1375	±.0125	.1375 TO .1400	±.0130
.1400 TO .1425	±.0130	.1425 TO .1450	±.0135
.1450 TO .1475	±.0135	.1475 TO .1500	±.0140
.1500 TO .1525	±.0140	.1525 TO .1550	±.0145
.1550 TO .1575	±.0145	.1575 TO .1600	±.0150
.1600 TO .1625	±.0150	.1625 TO .1650	±.0155
.1650 TO .1675	±.0155	.1675 TO .1700	±.0160
.1700 TO .1725	±.0160	.1725 TO .1750	±.0165
.1750 TO .1775	±.0165	.1775 TO .1800	±.0170
.1800 TO .1825	±.0170	.1825 TO .1850	±.0175
.1850 TO .1875	±.0175	.1875 TO .1900	±.0180
.1900 TO .1925	±.0180	.1925 TO .1950	±.0185
.1950 TO .1975	±.0185	.1975 TO .2000	±.0190
.2000 TO .2025	±.0190	.2025 TO .2050	±.0195
.2050 TO .2075	±.0195	.2075 TO .2100	±.0200
.2100 TO .2125	±.0200	.2125 TO .2150	±.0205
.2150 TO .2175	±.0205	.2175 TO .2200	±.0210
.2200 TO .2225	±.0210	.2225 TO .2250	±.0215
.2250 TO .2275	±.0215	.2275 TO .2300	±.0220
.2300 TO .2325	±.0220	.2325 TO .2350	±.0225
.2350 TO .2375	±.0225	.2375 TO .2400	±.0230
.2400 TO .2425	±.0230	.2425 TO .2450	±.0235
.2450 TO .2475	±.0235	.2475 TO .2500	±.0240
.2500 TO .2525	±.0240	.2525 TO .2550	±.0245
.2550 TO .2575	±.0245	.2575 TO .2600	±.0250
.2600 TO .2625	±.0250	.2625 TO .2650	±.0255
.2650 TO .2675	±.0255	.2675 TO .2700	±.0260
.2700 TO .2725	±.0260	.2725 TO .2750	±.0265
.2750 TO .2775	±.0265	.2775 TO .2800	±.0270
.2800 TO .2825	±.0270	.2825 TO .2850	±.0275
.2850 TO .2875	±.0275	.2875 TO .2900	±.0280
.2900 TO .2925	±.0280	.2925 TO .2950	±.0285
.2950 TO .2975	±.0285	.2975 TO .3000	±.0290
.3000 TO .3025	±.0290	.3025 TO .3050	±.0295
.3050 TO .3075	±.0295	.3075 TO .3100	±.0300
.3100 TO .3125	±.0300	.3125 TO .3150	±.0305
.3150 TO .3175	±.0305	.3175 TO .3200	±.0310
.3200 TO .3225	±.0310	.3225 TO .3250	±.0315
.3250 TO .3275	±.0315	.3275 TO .3300	±.0320
.3300 TO .3325	±.0320	.3325 TO .3350	±.0325
.3350 TO .3375	±.0325	.3375 TO .3400	±.0330
.3400 TO .3425	±.0330	.3425 TO .3450	±.0335
.3450 TO .3475	±.0335	.3475 TO .3500	±.0340
.3500 TO .3525	±.0340	.3525 TO .3550	±.0345
.3550 TO .3575	±.0345	.3575 TO .3600	±.0350
.3600 TO .3625	±.0350	.3625 TO .3650	±.0355
.3650 TO .3675	±.0355	.3675 TO .3700	±.0360
.3700 TO .3725	±.0360	.3725 TO .3750	±.0365
.3750 TO .3775	±.0365	.3775 TO .3800	±.0370
.3800 TO .3825	±.0370	.3825 TO .3850	±.0375
.3850 TO .3875	±.0375	.3875 TO .3900	±.0380
.3900 TO .3925	±.0380	.3925 TO .3950	±.0385
.3950 TO .3975	±.0385	.3975 TO .4000	±.0390
.4000 TO .4025	±.0390	.4025 TO .4050	±.0395
.4050 TO .4075	±.0395	.4075 TO .4100	±.0400
.4100 TO .4125	±.0400	.4125 TO .4150	±.0405
.4150 TO .4175	±.0405	.4175 TO .4200	±.0410
.4200 TO .4225	±.0410	.4225 TO .4250	±.0415
.4250 TO .4275	±.0415	.4275 TO .4300	±.0420
.4300 TO .4325	±.0420	.4325 TO .4350	±.0425
.4350 TO .4375	±.0425	.4375 TO .4400	±.0430
.4400 TO .4425	±.0430	.4425 TO .4450	±.0435
.4450 TO .4475	±.0435	.4475 TO .4500	±.0440
.4500 TO .4525	±.0440	.4525 TO .4550	±.0445
.4550 TO .4575	±.0445	.4575 TO .4600	±.0450
.4600 TO .4625	±.0450	.4625 TO .4650	±.0455
.4650 TO .4675	±.0455	.4675 TO .4700	±.0460
.4700 TO .4725	±.0460	.4725 TO .4750	±.0465
.4750 TO .4775	±.0465	.4775 TO .4800	±.0470
.4800 TO .4825	±.0470	.4825 TO .4850	±.0475
.4850 TO .4875	±.0475	.4875 TO .4900	±.0480
.4900 TO .4925	±.0480	.4925 TO .4950	±.0485
.4950 TO .4975	±.0485	.4975 TO .5000	±.0490
.5000 TO .5025	±.0490	.5025 TO .5050	±.0495
.5050 TO .5075	±.0495	.5075 TO .5100	±.0500
.5100 TO .5125	±.0500	.5125 TO .5150	±.0505
.5150 TO .5175	±.0505	.5175 TO .5200	±.0510
.5200 TO .5225	±.0510	.5225 TO .5250	±.0515
.5250 TO .5275	±.0515	.5275 TO .5300	±.0520
.5300 TO .5325	±.0520	.5325 TO .5350	±.0525
.5350 TO .5375	±.0525	.5375 TO .5400	±.0530
.5400 TO .5425	±.0530	.5425 TO .5450	±.0535
.5450 TO .5475	±.0535	.5475 TO .5500	±.0540
.5500 TO .5525	±.0540	.5525 TO .5550	±.0545
.5550 TO .5575	±.0545	.5575 TO .5600	±.0550
.5600 TO .5625	±.0550	.5625 TO .5650	±.0555
.5650 TO .5675	±.0555	.5675 TO .5700	±.0560
.5700 TO .5725	±.0560	.5725 TO .5750	±.0565
.5750 TO .5775	±.0565	.5775 TO .5800	±.0570
.5800 TO .5825	±.0570	.5825 TO .5850	±.0575
.5850 TO .5875	±.0575	.5875 TO .5900	±.0580
.5900 TO .5925	±.0580	.5925 TO .5950	±.0585
.5950 TO .5975	±.0585	.5975 TO .6000	±.0590
.6000 TO .6025	±.0590	.6025 TO .6050	±.0595
.6050 TO .6075	±.0595	.6075 TO .6100	±.0600
.6100 TO .6125	±.0600	.6125 TO .6150	±.0605
.6150 TO .6175	±.0605	.6175 TO .6200	±.0610
.6200 TO .6225	±.0610	.6225 TO .6250	±.0615
.6250 TO .6275	±.0615	.6275 TO .6300	±.0620
.6300 TO .6325	±.0620	.6325 TO .6350	±.0625
.6350 TO .6375	±.0625	.6375 TO .6400	±.0630
.6400 TO .6425	±.0630	.6425 TO .6450	±.0635
.6450 TO .6475	±.0635	.6475 TO .6500	±.0640
.6500 TO .6525	±.0640	.6525 TO .6550	±.0645
.6550 TO .6575	±.0645	.6575 TO .6600	±.0650
.6600 TO .6625	±.0650	.6625 TO .6650	±.0655
.6650 TO .6675	±.0655	.6675 TO .6700	±.0660
.6700 TO .6725	±.0660	.6725 TO .6750	±.0665
.6750 TO .6775	±.0665	.6775 TO .6800	±.0670
.6800 TO .6825	±.0670	.6825 TO .6850	±.0675
.6850 TO .6875	±.0675	.6875 TO .6900	±.0680
.6900 TO .6925	±.0680	.6925 TO .6950	±.0685
.6950 TO .6975	±.0685	.6975 TO .7000	±.0690
.7000 TO .7025	±.0690	.7025 TO .7050	±.0695
.7050 TO .7075	±.0695	.7075 TO .7100	±.0700
.7100 TO .7125	±.0700	.7125 TO .7150	±.0705
.7150 TO .7175	±.0705	.7175 TO .7200	±.0710
.7200 TO .7225	±.0710	.7225 TO .7250	±.0715
.7250 TO .7275	±.0715	.7275 TO .7300	±.0720
.7300 TO .7325	±.0720	.7325 TO .7350	±.0725
.7350 TO .7375	±.0725	.7375 TO .7400	±.0730
.7400 TO .7425	±.0730	.7425 TO .7450	±.0735
.7450 TO .7475	±.0735	.7475 TO .7500	±.0740
.7500 TO .7525	±.0740	.7525 TO .7550	±.0745
.7550 TO .7575	±.0745	.7575 TO .7600	±.0750
.7600 TO .7625	±.0750	.7625 TO .7650	±.0755
.7650 TO .7675	±.0755	.7675 TO .7700	±.0760
.7700 TO .7725	±.0760	.7725 TO .7750	±.0765
.7750 TO .7775	±.0765	.7775 TO .7800	±.0770
.7800 TO .7825	±.0770	.7825 TO .7850	±.0775
.7850 TO .7875	±.0775	.7875 TO .7900	±.0780
.7900 TO .7925	±.0780	.7925 TO .7950	±.0785
.7950 TO .7975	±.0785	.7975 TO .8000	±.0790
.8000 TO .8025	±.0790	.8025 TO .8050	±.0795
.8050 TO .8075	±.0795	.8075 TO .8100	±.0800
.8100 TO .8125	±.0800	.8125 TO .8150	±.0805
.8150 TO .8175	±.0805	.8175 TO .8200	±.0810
.8200 TO .8225	±.0810	.8225 TO .8250	±.0815
.8250 TO .8275	±.0815	.8275 TO .8300	±.0820
.8300 TO .8325	±.0820	.8325 TO .8350	±.0825
.8350 TO .8375	±.0825	.8375 TO .8400	±.0830
.8400 TO .8425	±.0830	.8425 TO .8450	±.0835
.8450 TO .8475	±.0835	.8475 TO .8500	±.0840
.8500 TO .8525	±.0840	.8525 TO .8550	±.0845
.8550 TO .8575	±.0845	.8575 TO .8600	±.0850
.8600 TO .8625	±.0850	.8625 TO .8650	±.0855
.8650 TO .8675	±.0855	.8675 TO .8700	±.0860
.8700 TO .8725	±.0860	.8725 TO .8750	±.0865
.8750 TO .8775	±.0865	.8775 TO .8800	±.0870
.8800 TO .8825	±.0870	.8825 TO .8850	±.0875
.8850 TO .8875	±.0875	.8875 TO .8900	±.0880
.8900 TO .8925	±.0880	.8925 TO .8950	±.0885
.8950 TO .8975	±.0885	.8975 TO .9000	±.0890
.9000 TO .9025	±.0890	.9025 TO .9050	±.0895
.9050 TO .9075	±.0895	.9075 TO .9100	±.0900
.9100 TO .9125	±.0900	.9125 TO .9150	±.0905
.9150 TO .9175	±.0905	.9175 TO .9200	±.0910
.9200 TO .9225	±.0910	.9225 TO .9250	±.0915
.9250 TO .9275	±.0915	.9275 TO .9300	±.0920
.9300 TO .9325	±.0920	.9325 TO .9350	±.0925
.9350 TO .9375	±.0925	.9375 TO .9400	±.0930





# ELECTRONIC SCHEMATIC

WELD NO.	USED	DELETED
-100	101 → 133	—
-200	201 → 226 240 → 243	227 → 239


W 4158

SEE SEPERATE LIST OF MATERIAL.

1		2		3		4		5		6		7		8		9		10		11		12		13		14		15		16		17		18		19		20		21		22		23		24		25		26		27		28		29		30		31		32		33		34		35		36		37		38		39		40		41		42		43		44		45		46		47		48		49		50		51		52		53		54		55		56		57		58		59		60		61		62		63		64		65		66		67		68		69		70		71		72		73		74		75		76		77		78		79		80		81		82		83		84		85		86		87		88		89		90		91		92		93		94		95		96		97		98		99		100		101		102		103		104		105		106		107		108		109		110		111		112		113		114		115		116		117		118		119		120		121		122		123		124		125		126		127		128		129		130		131		132		133		134		135		136		137		138		139		140		141		142		143		144		145		146		147		148		149		150		151		152		153		154		155		156		157		158		159		160		161		162		163		164		165		166		167		168		169		170		171		172		173		174		175		176		177		178		179		180		181		182		183		184		185		186		187		188		189		190		191		192		193		194		195		196		197		198		199		200		201		202		203		204		205		206		207		208		209		210		211		212		213		214		215		216		217		218		219		220		221		222		223		224		225		226		227		228		229		230		231		232		233		234		235		236		237		238		239		240		241		242		243		244		245		246		247		248		249		250		251		252		253		254		255		256		257		258		259		260		261		262		263		264		265		266		267		268		269		270		271		272		273		274		275		276		277		278		279		280		281		282		283		284		285		286		287		288		289		290		291		292		293		294		295		296		297		298		299		300		301		302		303		304		305		306		307		308		309		310		311		312		313		314		315		316		317		318		319		320		321		322		323		324		325		326		327		328		329		330		331		332		333		334		335		336		337		338		339		340		341		342		343		344		345		346		347		348		349		350		351		352		353		354		355		356		357		358		359		360		361		362		363		364		365		366		367		368		369		370		371		372		373		374		375		376		377		378		379		380		381		382		383		384		385		386		387		388		389		390		391		392		393		394		395		396		397		398		399		400		401		402		403		404		405		406		407		408		409		410		411		412		413		414		415		416		417		418		419		420		421		422		423		424		425		426		427		428		429		430		431		432		433		434		435		436		437		438		439		440		441		442		443		444		445		446		447		448		449		450		451		452		453		454		455		456		457		458		459		460		461		462		463		464		465		466		467		468		469		470		471		472		473		474		475		476		477		478		479		480		481		482		483		484		485		486		487		488		489		490		491		492		493		494		495		496		497		498		499		500		501		502		503		504		505		506		507		508		509		510		511		512		513		514		515		516		517		518		519		520		521		522		523		524		525		526		527		528		529		530		531		532		533		534		535		536		537		538		539		540		541		542		543		544		545		546		547		548		549		550		551		552		553		554		555		556		557		558		559		560		561		562		563		564		565		566		567		568		569		570		571		572		573		574		575		576		577		578		579		580		581		582		583		584		585		586		587		588		589		590		591		592		593		594		595		596		597		598		599		600		601		602		603		604		605		606		607		608		609		610		611		612		613		614		615		616		617		618		619		620		621		622		623		624		625		626		627		628		629		630		631		632		633		634		635		636		637		638		639		640		641		642		643		644		645		646		647		648		649		650		651		652		653		654		655		656		657		658		659		660		661		662		663		664		665		666		667		668		669		670		671		672		673		674		675		676		677		678		679		680		681		682		683		684		685		686		687		688		689		690		691		692		693		694		695		696		697		698		699		700		701		702		703		704		705		706		707		708		709		710		711		712		713		714		715		716		717		718		719		720		721		722		723		724		725		726		727		728		729		730		731		732		733		734		735		736		737		738		739		740		741		742		743		744		745		746		747		748		749		750		751		752		753		754		755		756		757		758		759		760		761		762		763		764		765		766		767		768		769		770		771		772		773		774		775		776		777		778		779		780		781		782		783		784		785		786		787		788		789		790		791		792		793		794		795		796		797		798		799		800		801		802		803		804		805		806		807		808		809		810		811		812		813		814		815		816		817		818		819		820		821		822		823		824		825		826		827		828		829		830		831		832		833		834		835		836		837		838		839		840		841		842		843		844		845		846		847		848		849		850		851		852		853		854		855		856		857		858		859		860		861		862		863		864		865		866		867		868		869		870		871		872		873		874		875		876		877		878		879		880		881		882		883		884		885		886		887		888		889		890		891		892		893		894		895		896		897		898		899		900		901		902		903		904		905		906		907		908		909		910		911		912		913		914		915		916		917		918		919		920		921		922		923		924		925		926		927		928		929		930		931		932		933		934		935		936		937		938		939		940		941		942		943		944		945		946		947		948		949		950		951		952		953		954		955		956		957		958		959		960		961		962		963		964		965		966		967		968		969		970		971		972		973		974		975		976		977		978		979		980		981		982		983		984		985		986		987		988		989		990		991		992		993		994		995		996		997		998		999		1000		1001		1002		1003		1004		1005		1006		1007		1008		1009		1010		1011		1012		1013		1014		1015		1016		1017		1018		1019		1020		1021		1022		1023		1024		1025		1026		1027		1028		1029		1030		1031		1032		1033		1034		1035		1036		1037		1038		1039		1040		1041		1042		1043		1044		1045		1046		1047		1048		1049		1050		1051		1052		1053		1054		1055		1056		1057		1058		1059		1060		1061		1062		1063		1064		1065		1066		1067		1068		1069		1070		1071		1072		1073		1074		1075		1076		1077		1078		1079		1080		1081		1082		1083		1084		1085		1086		1087		1088		1089		1090		1091		1092		1093		1094		1095		1096		1097		1098		1099		1100		1101		1102		1103		1104		1105		1106		1107		1108		1109		1110		1111		1112		1113		1114		1115		1116		1117		1118		1119		1120		1121		1122		1123		112	
---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	-----	--


W4159

REVISIONS




ELECTRONIC SCHEMATIC

LEAD NO. 1



900 MAX



WELD NO. USED  
-100: 101-133  
-200: 201-234

W4159


1. CH. 1		2. CH. 2		3. CH. 3		4. CH. 4		5. CH. 5		6. CH. 6		7. CH. 7		8. CH. 8		9. CH. 9		10. CH. 10		11. CH. 11		12. CH. 12		13. CH. 13		14. CH. 14		15. CH. 15		16. CH. 16		17. CH. 17		18. CH. 18		19. CH. 19		20. CH. 20		21. CH. 21		22. CH. 22		23. CH. 23		24. CH. 24		25. CH. 25		26. CH. 26		27. CH. 27		28. CH. 28		29. CH. 29		30. CH. 30		31. CH. 31		32. CH. 32		33. CH. 33		34. CH. 34		35. CH. 35		36. CH. 36		37. CH. 37		38. CH. 38		39. CH. 39		40. CH. 40		41. CH. 41		42. CH. 42		43. CH. 43		44. CH. 44		45. CH. 45		46. CH. 46		47. CH. 47		48. CH. 48		49. CH. 49		50. CH. 50		51. CH. 51		52. CH. 52		53. CH. 53		54. CH. 54		55. CH. 55		56. CH. 56		57. CH. 57		58. CH. 58		59. CH. 59		60. CH. 60		61. CH. 61		62. CH. 62		63. CH. 63		64. CH. 64		65. CH. 65		66. CH. 66		67. CH. 67		68. CH. 68		69. CH. 69		70. CH. 70		71. CH. 71		72. CH. 72		73. CH. 73		74. CH. 74		75. CH. 75		76. CH. 76		77. CH. 77		78. CH. 78		79. CH. 79		80. CH. 80		81. CH. 81		82. CH. 82		83. CH. 83		84. CH. 84		85. CH. 85		86. CH. 86		87. CH. 87		88. CH. 88		89. CH. 89		90. CH. 90		91. CH. 91		92. CH. 92		93. CH. 93		94. CH. 94		95. CH. 95		96. CH. 96		97. CH. 97		98. CH. 98		99. CH. 99		100. CH. 100		101. CH. 101		102. CH. 102		103. CH. 103		104. CH. 104		105. CH. 105		106. CH. 106		107. CH. 107		108. CH. 108		109. CH. 109		110. CH. 110		111. CH. 111		112. CH. 112		113. CH. 113		114. CH. 114		115. CH. 115		116. CH. 116		117. CH. 117		118. CH. 118		119. CH. 119		120. CH. 120		121. CH. 121		122. CH. 122		123. CH. 123		124. CH. 124		125. CH. 125		126. CH. 126		127. CH. 127		128. CH. 128		129. CH. 129		130. CH. 130		131. CH. 131		132. CH. 132		133. CH. 133		134. CH. 134		135. CH. 135		136. CH. 136		137. CH. 137		138. CH. 138		139. CH. 139		140. CH. 140		141. CH. 141		142. CH. 142		143. CH. 143		144. CH. 144		145. CH. 145		146. CH. 146		147. CH. 147		148. CH. 148		149. CH. 149		150. CH. 150		151. CH. 151		152. CH. 152		153. CH. 153		154. CH. 154		155. CH. 155		156. CH. 156		157. CH. 157		158. CH. 158		159. CH. 159		160. CH. 160		161. CH. 161		162. CH. 162		163. CH. 163		164. CH. 164		165. CH. 165		166. CH. 166		167. CH. 167		168. CH. 168		169. CH. 169		170. CH. 170		171. CH. 171		172. CH. 172		173. CH. 173		174. CH. 174		175. CH. 175		176. CH. 176		177. CH. 177		178. CH. 178		179. CH. 179		180. CH. 180		181. CH. 181		182. CH. 182		183. CH. 183		184. CH. 184		185. CH. 185		186. CH. 186		187. CH. 187		188. CH. 188		189. CH. 189		190. CH. 190		191. CH. 191		192. CH. 192		193. CH. 193		194. CH. 194		195. CH. 195		196. CH. 196		197. CH. 197		198. CH. 198		199. CH. 199		200. CH. 200		201. CH. 201		202. CH. 202		203. CH. 203		204. CH. 204		205. CH. 205		206. CH. 206		207. CH. 207		208. CH. 208		209. CH. 209		210. CH. 210		211. CH. 211		212. CH. 212		213. CH. 213		214. CH. 214		215. CH. 215		216. CH. 216		217. CH. 217		218. CH. 218		219. CH. 219		220. CH. 220		221. CH. 221		222. CH. 222		223. CH. 223		224. CH. 224		225. CH. 225		226. CH. 226		227. CH. 227		228. CH. 228		229. CH. 229		230. CH. 230		231. CH. 231		232. CH. 232		233. CH. 233		234. CH. 234		235. CH. 235		236. CH. 236		237. CH. 237		238. CH. 238		239. CH. 239		240. CH. 240		241. CH. 241		242. CH. 242		243. CH. 243		244. CH. 244		245. CH. 245		246. CH. 246		247. CH. 247		248. CH. 248		249. CH. 249		250. CH. 250		251. CH. 251		252. CH. 252		253. CH. 253		254. CH. 254		255. CH. 255		256. CH. 256		257. CH. 257		258. CH. 258		259. CH. 259		260. CH. 260		261. CH. 261		262. CH. 262		263. CH. 263		264. CH. 264		265. CH. 265		266. CH. 266		267. CH. 267		268. CH. 268		269. CH. 269		270. CH. 270		271. CH. 271		272. CH. 272		273. CH. 273		274. CH. 274		275. CH. 275		276. CH. 276		277. CH. 277		278. CH. 278		279. CH. 279		280. CH. 280		281. CH. 281		282. CH. 282		283. CH. 283		284. CH. 284		285. CH. 285		286. CH. 286		287. CH. 287		288. CH. 288		289. CH. 289		290. CH. 290		291. CH. 291		292. CH. 292		293. CH. 293		294. CH. 294		295. CH. 295		296. CH. 296		297. CH. 297		298. CH. 298		299. CH. 299		300. CH. 300		301. CH. 301		302. CH. 302		303. CH. 303		304. CH. 304		305. CH. 305		306. CH. 306		307. CH. 307		308. CH. 308		309. CH. 309		310. CH. 310		311. CH. 311		312. CH. 312		313. CH. 313		314. CH. 314		315. CH. 315		316. CH. 316		317. CH. 317		318. CH. 318		319. CH. 319		320. CH. 320		321. CH. 321		322. CH. 322		323. CH. 323		324. CH. 324		325. CH. 325		326. CH. 326		327. CH. 327		328. CH. 328		329. CH. 329		330. CH. 330		331. CH. 331		332. CH. 332		333. CH. 333		334. CH. 334		335. CH. 335		336. CH. 336		337. CH. 337		338. CH. 338		339. CH. 339		340. CH. 340		341. CH. 341		342. CH. 342		343. CH. 343		344. CH. 344		345. CH. 345		346. CH. 346		347. CH. 347		348. CH. 348		349. CH. 349		350. CH. 350		351. CH. 351		352. CH. 352		353. CH. 353		354. CH. 354		355. CH. 355		356. CH. 356		357. CH. 357		358. CH. 358		359. CH. 359		360. CH. 360		361. CH. 361		362. CH. 362		363. CH. 363		364. CH. 364		365. CH. 365		366. CH. 366		367. CH. 367		368. CH. 368		369. CH. 369		370. CH. 370		371. CH. 371		372. CH. 372		373. CH. 373		374. CH. 374		375. CH. 375		376. CH. 376		377. CH. 377		378. CH. 378		379. CH. 379		380. CH. 380		381. CH. 381	
----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--	--------------	--

LEAD NO. 1

W 4167-200

400 MAX

-200



WELD NO. USED: DELETED	
-100	101-129
-200	201-222, 230-236



W4167

SEE SEPARATE L/M

READ		PART NO		DESCRIPTION		CMT REF																									
LIST OF MATERIALS																															
FINISH																															
WEIGHT																															
<div style="display: flex; justify-content: space-between;"> <div> <p><b>DO NOT SCALE DRAWING</b></p> <p>UNLESS OTHERWISE SPECIFIED</p> <p>DIMENSIONS IN INCHES</p> <table border="1"> <thead> <tr> <th>HOLE DIA.</th> <th>TOLERANCE</th> <th>LINEAR TOLERANCES</th> </tr> </thead> <tbody> <tr> <td>.0150 THRU .125</td> <td>+.004-.001</td> <td>XXX = ±.010</td> </tr> <tr> <td>.125 THRU .250</td> <td>+.005-.001</td> <td>XX = ±.005</td> </tr> <tr> <td>.251 THRU .500</td> <td>+.006-.001</td> <td>X = ±.001</td> </tr> <tr> <td>.501 THRU .750</td> <td>+.007-.001</td> <td></td> </tr> <tr> <td>.751 THRU 1.000</td> <td>+.010-.001</td> <td>ANGLES = ± 0° 30'</td> </tr> <tr> <td>1.000 THRU 2.000</td> <td>+.012-.001</td> <td>SURFACE FINISH</td> </tr> <tr> <td>2.001 &amp; OVER</td> <td>+.015</td> <td>PR 13-470-15</td> </tr> </tbody> </table> </div> <div> <p>APPROVED BY: <i>[Signature]</i> DATE: 9/16/64</p> <p>BY: <i>[Signature]</i> DATE: 10/1/64</p> <p>SCALE: 10/1</p> <p>WEIGHT: 1</p> </div> <div> <p>DETECTOR MODULE</p> <p>W4</p> <p>7</p> <p>D SHEET</p> </div> </div>								HOLE DIA.	TOLERANCE	LINEAR TOLERANCES	.0150 THRU .125	+.004-.001	XXX = ±.010	.125 THRU .250	+.005-.001	XX = ±.005	.251 THRU .500	+.006-.001	X = ±.001	.501 THRU .750	+.007-.001		.751 THRU 1.000	+.010-.001	ANGLES = ± 0° 30'	1.000 THRU 2.000	+.012-.001	SURFACE FINISH	2.001 & OVER	+.015	PR 13-470-15
HOLE DIA.	TOLERANCE	LINEAR TOLERANCES																													
.0150 THRU .125	+.004-.001	XXX = ±.010																													
.125 THRU .250	+.005-.001	XX = ±.005																													
.251 THRU .500	+.006-.001	X = ±.001																													
.501 THRU .750	+.007-.001																														
.751 THRU 1.000	+.010-.001	ANGLES = ± 0° 30'																													
1.000 THRU 2.000	+.012-.001	SURFACE FINISH																													
2.001 & OVER	+.015	PR 13-470-15																													

PARTS DISPOSITION		W4168	
1. USE	2. DISCARD	3. REWORK	4. OTHER
REVISIONS			
REV	DATE	DESCRIPTION	BY

VENTS  
APPLICITY



WELD N2 USED  
-100: 101-127  
-200: 201-229



W4168

E-3		DESCRIPTION	
FORM		LIST OF MATERIALS	
DATE		RELEASED	
APR 24 1964		MARSHALL LABORATORIES	
INHIBIT & HOLD MODULE		W4168	
D		PAGE 1 OF 1	

DATE <u>APR 24 1964</u> TIME <u>10:00</u> LIST OF MATERIALS	
PROJECT <u>W4-160</u> NAME <u>W4-160</u>	DATE RECORDED <u>APR 24 1964</u>
GAIN OF TWO AMPLIFIER MODULE	MARSHALL LABORATORIES
SCALE <u>10/1</u> INCIDENT <u>—</u>	W4-160 PAGE 1 OF 1



W4170	
REVISIONS	
Rev	Date
1	10/1/64



ELECTRONIC SCHEMATIC



WELD NO. USED  
 -100: 101-131  
 -200: 201-226

W4170

DO NOT SCALE DRAWING		LIST OF MATERIALS	
CHECKS BY: [ ]		APPROVED: [ ]	
REVISIONS		SC0 DRIVER MODULE	
MATERIALS		MARSHALL LABORATORIES	
W4170		W4170	

1. DATE	2. REVISED	3. CHANGE OF RELEASED	4. RELEASED	5. ....	W4171	1
REVISIONS						
REV	DATE	DESCRIPTION	BY	DATE	CHK	APPROVAL

# ELECTRONIC SCHEMATIC



WELD NO. USED  
-100: 101-114  
-200: 201-219

W4171

DO NOT SCALE DRAWING

RELEASED

APR 28 1964



TRIGGER  
MODULE  
(.750)

MARSHALL  
LABORATORIES

W4171

PART NO.		DESCRIPTION		DATE	
LIST OF MATERIALS					
FRONT					
REAR VIEW					
INTEGRATOR MODULE		NATIONAL LABORATORIES			
W4172		DATE / OF			

W4176			
REVISIONS			
NO.	DATE	DESCRIPTION	BY
2	10/24/64	REMOVED GROUND, DELETED R1, R-RELOCATED GND TO -200	SC
4	1/20/65	REVISED LOCATION R9, C1: C1 HAS VTECHN TYPE	RP



WELD NO. USED	DELETED
-100	—
-200	—
-300	—

W4176

LIST OF MATERIALS			
QTY	DESCRIPTION	UNIT	REMARKS
1	DETECTOR MODULE		
1	MARSHALL LABORATORIES		

RELEASED APR 24 1964

APPENDIX B

NEW MODULES USED IN THE GSE

GW 4211

GW 4212

GW 4216

PRECEDING PAGES BLANK NOT FILMED

GW4211 AND-NOR Logic Gate Module.

This module consists of AND gate CR1, CR4 and R1 with the output on Pin 9. A 2-input NOR circuit consists of CR5, CR7, CR6 Q1, R3 and R2. The output of the NOR is Pin 6.


GW4212 AND-OR Logic Module.

CR1, CR2, CR3 and R1 form one AND circuit. CR4, CR5 and CR6 and R2 form another AND circuit. CR7 and CR8 are used to sum the outputs of two AND gates to provide the OR function.

GW4216 Sensor Line Driver Module.

This module is driven by a saturating PNP transistor which forms a fast leading edge. The module inverts the signal to produce a fast negative going pulse. The amplitude of the pulse is determined by the value of the variable B+.


1. <u>DATE</u> <u>10/1/64</u> 2. <u>TIME</u> <u>10:00</u> 3. <u>LOCATION</u> <u>RESEARCH</u> 4. <u>LIST OF MATERIALS</u> 5. <u>REMARKS</u> <u>JUL 21 1964</u> 6. <u>INITIALS</u> <u>W4211</u> 7. <u>LABORATORIES</u> 8. <u>W4211</u> 9. <u>REMARKS</u> <u>END</u>	
---	--



W4212

DO NOT SCALE DRAWING		PART NO. _____ REV. _____ LIST OF MATERIALS QUANTITY _____ RELEASED JUL 1964	
UNITED STATES SPECIFICATIONS MIL-STD-883C TEST METHOD 1010		AND-OR LOGIC GATE MODULE MARSHALL LABORATORIES W4212 PAGE 1 OF 1	





# ELECTRONIC SCHEMATIC

W4216

[illegible]

ML/TN 2300.55  
Page 83.

## APPENDIX C

### SPECIFICATIONS AND MASTER DRAWING LISTS

This section contains the following released documents:

S40533 Micrometeorite Ejecta Detector (GSE Surveyor)  
NL 260-1, Test Procedure for

S40534 Circuit Board Assembly - Digital Readout and Command  
(GSE Surveyor) Test Procedure for

S40535 Circuit Board Assembly - Power Supply (GSE Surveyor)  
Test Procedure for

• S40536 Circuit Board Assembly - Sensor Stimulus (GSE Surveyor)  
Test Procedure for

S40519 Surveyor Power Supply Blivet, Test Specification for

S40548 Surveyor Digital Blivet, Test Specification for

S40660 Surveyor Sensor Blivet, Test Specification for

S40682 Ejecta Detector (GSE Surveyor) ML 260-1, Operational Manual  
for

MDL No. 51117, Electronics Assembly

MDL No. 51259, Sensor Assembly

MDL No. 51304, GSE

[illegible]

## 1.0 SCOPE

- 1.1 This procedure covers the electrical checkout of the GSE after completion of the assembly.

## 2.0 APPLICABLE DOCUMENTS

- 2.1 The following documents, of the issue in effect, form a part of this specification to the extent specified herein.

### SPECIFICATIONS

#### Marshall Laboratories

S40534	Circuit Board Assembly, Digital Readout and Command, (GSE Surveyor), Test Procedure for
S40535	Circuit Board Assembly, Power Supply, (GSE Surveyor), Test Procedure for
S40536	Sensor Stimulus Board, Surveyor Ejecta Detector, Model ML 260-1, Test Specification for

### DRAWINGS

#### Marshall Laboratories

51114	Schematic, Ejecta Detector
51304-101	Assembly, Micrometeorite Ejecta Detector


RELEASED	FILED	1965	TITLE	<b>MARSHALL LABORATORIES</b>
PREPARED			Micrometeorite Ejecta Detector (GSE - Surveyor) ML 260-1, Test Procedure for	
CHECKED				
APPROVED				
				S40533
				SHEET 2 OF

### 3.0 TEST PROCEDURE

- 3.1 Make a continuity check of all connector, switches, and point-to-point wiring on the chassis. Refer to Marshall Laboratories Drawing 51114.
- 3.2 Check all fuses on the rear panel for proper value. Refer to Marshall Laboratories Drawing 51114.
- 3.3 Remove F104.
- 3.4 Apply 115V 60 cps A.C. to J9. Depress power switch on front panel.
- 3.5 Measure 180V from TP GRD to J3-27.
- 3.6 Set S101A (lamp switch) to LAMPS ON. Check all pushbutton switches on the front panel for proper operation.
- 3.7 Set S101A switch to LAMPS OFF. All pushbutton switch lights should be out.
- 3.8 Replace F104.
- 3.9 For GSE circuit board tests refer to the following specifications:
- A. S40534 Circuit Board Assembly, Digital Readout and Command, (GSE Surveyor), Test Procedure for
  - B. S40535 Circuit Board Assembly, Power Supply, (GSE Surveyor), Test Procedure for
  - C. S40536 Sensor Stimulus Board, Surveyor Ejecta Detector, Model M 260-1, Test Specification for

### 4.0 METER CIRCUIT CHECKOUT

- 4.1 Measure Meter Resistance and Record.



RELEASED/REMOVED	FE DATE 1965	WILE	<b>MICROMETEORITE EJECTA DETECTOR (GSE - SURVEYOR) ML 260-1, TEST PROCEDURE FOR</b>	<b>MARSHALL LABORATORIES</b>
PREPARED				
CHECKED				
APPROVED				
S40533			SHEET 3 OF 3	

S40533

CMS DTE

4.1 (Continued)

Increase voltage for full scale deflection of panel meter.

Make note of two voltage readings.

Repeat with reversed polarity.

Meter resistance =  $\frac{V1}{\frac{V2}{1K}}$  Use average of voltage reading.

4.2 Selection of R19.

R19 = 1580- $\Omega$  minus meter resistance.

Tack solder in the selected value of R19.

4.3 Selection of R14.

Set decade box across R14. Set for 1K.

Set decade box across J7-R and J7-D (simulated temperature probe).  
Set to 500- $\Omega$ .

DO NOT connect panel meter.

Apply power.

Measure across TB5-4(+) and TB5-1(-) and adjust R110 (28 volt adjust potentiometer on rear of chassis) for 28 volts  $\pm .1V$ .

Select R14 for 2.50 volt  $\pm .05V$  across simulated temperature probe.

4.4 30-Volt Reference.

Measure across TB5-6(+) and TB5-1(-) for 30 volts  $\pm 0.1$  volts.

Re-select R104, if needed.

RELEASE DATE	FEB 1960	TITLE	Micrometeorite Ejecta Detector (GSE - Surveyor) ML 260-1, Test Procedure for	MARSHALL LABORATORIES
PREPARED				
CHECKED				
APPROVED				
SHEET 4 OF			S40533	

4.5 29 Volt Meter Position.

Disconnect meter leads.

Measure across meter leads and adjust R43 on TB6 for a null.

Connect meter leads. Meter will read zero.

Increase 28 volt with R110 to 29.4 volts (+5%).

Adjust R26 for a full scale positive deflection of meter.

Reduce voltage with R110 for 26.6 volts.

Panel meter should read -5%. Vary 29 volts for a full negative deflection and record.

4.6 3 Volt Meter Position.

Disconnect meter leads.

Apply +3 volts  $\pm 0.05V$  to J7-L (+) and ground.

Adjust R47 (TB6) for a null across meter leads.

Reconnect meter leads. Meter will read zero.

Increase the applied 3 volts to 3.15V (5%).

Adjust R28 for a full positive scale deflection.

Reduce applied voltage for a full scale deflection to the left. Record voltage.

4.7 12 Volt Meter Position.

Disconnect meter leads.

Apply external 12 volts  $\pm 0.1V$  to J7-E (+) and ground.

Adjust R41 (TB-6) for a null across meter leads.

Reconnect the meter; meter will read zero.

Increase the applied voltage 5% (+12.60V)

Adjust R30 for a full positive scale deflection.

Decrease applied voltage for a full negative deflection and record voltage.

RELEASE: MARSHALL	FE 1 1965	TITLE	<b>MARSHALL LABORATORIES</b>
PREPARED		Micrometeorite Ejecta	
CHECKED		Detector (GSE -	
APPROVED		Surveyor) ML 260-1,	
		Test Procedure for	
			S40533
			SHEET 5 OF



4.8 6 Volt Meter Position.

Disconnect meter.

Apply +6 volt  $\pm 0.050$  to J7-K (+) and ground.

Adjust R45 (TB6) for a null across meter leads.

Reconnect meter; meter will read zero.

Increase applied voltage 5% to 6.3 volts.

Adjust R32 for a full scale positive deflection.

Decrease the applied voltage for a full negative deflection and record voltage.

4.9 Minus 7 Volt Position.

Disconnect panel meter leads.

Apply -7 volts  $\pm 0.1V$  to J7-F (-) and ground.

Adjust R55 (TB6) for a null across meter leads.

Connect the meter; meter shall read zero.

Increase the applied voltage 5% to -7.35 volts.

Adjust R34 for a full positive scale deflection.

Reduce the applied voltage for a full scale negative deflection and record voltage.

4.10 Heater Current Position.

Disconnect meter leads.

To simulate the heater load, connect a  $440\Omega$  (decade box) load across J7-U (+) and J7-T (-).

Place digital across meter leads and null out with R36.

Depress heat power switch.

Adjust R115 (rear of chassis) for a 22.0 volt  $\pm 0.1V$  across simulated heater load.

RELEASE	DATE	TITLE	<b>MARSHALL LABORATORIES</b>
PREPARED	FEB 1 1965	Micrometeorite Ejecta Detector (GSE - Surveyor) ML 260-1, Test Procedure for	
CHECKED			
APPROVED			
S40533			SHEET 6 OF

4.10 (Continued)

Voltage across meter leads should read 250 mv  $\pm 10$  mv.

Turn off heater power and connect meter.

With heater power off the meter will read zero and full scale with heater power turned on.

4.11 Total Current Position.

Disconnect meter.

Simulate load with a decade box set to 1.3K (21.5 ma) and a triplett in series.

Turn on experimental power and null meter lead with R53 (TB6).

Reconnect meter; meter shall read zero.

Decrease decade box to a load of 26.5 ma (approximately 1.06K).

Adjust R22 for a full scale positive deflection.

Increase decade box to a load of 16.5 ma (approximately 1.7K).

Meter should now read a full negative scale deflection.

4.12 Temperature Position.

Disconnect meter leads.

Simulate temperature sensor with a decade box. Set across J7-R (+) and J7-D (-) set at 470 .

Adjust R49 for a null across the meter leads.

Reconnect meter.

Place decade box to 790  $\Omega$ .

Adjust R20 (TB6) for 100°C reading on meter.

Decrease decade box to 230  $\Omega$ . °Meter should read -100°C.

RELEASE	DATE	TITLE	<b>MICROMETEORITE EJECTA DETECTOR (GSE - SURVEYOR) ML 260-1, TEST PROCEDURE FOR</b>	<b>MARSHALL LABORATORIES</b>
PREPARED	FEB 1 1966			
CHECKED				
APPROVED				
				S40533 SHEET 7 OF

4.13 2 Volt Meter Position.

Disconnect meter.

Apply 2.0V through a 15.7K (decade box) to J1-G (+) and ground.

Adjust R51 (TB6) for a null across meter leads.

Reconnect meter; meter shall read zero.

Increase voltage 5% (2.10 volts) and adjust R24 (TB6) for a full scale positive deflection.

Reduce voltage for a full scale negative deflection and record.

5.0 MIC VERNIER

- 5.1 Vernier potentiometer R63 is setup as follows: Set dial reading to 5000, select R94 for 5.00V  $\pm$  50 mv at the wiper of R63.

6.0 MIC PRESET

- 6.1 The select resistors located on TB8 are as follows:

R72 = 33K	R67 = 2.7K
R71 = 240	R66 = 5.1K
R70 = 620	R65 = 11K
R69 = 1.0K	R64 = 27K
R68 = 1.6K	

7.0 FILM VERNIER

- 7.1 Vernier potentiometer R73 is setup as follows: Set dial reading to 5000, select R74 for 5.00V  $\pm$  50 mv at the wiper of R73.

RELEASED	FF	DATE	1965	TIME	
PREPARED					
CHECKED					
APPROVED					
				Micrometeorite Ejecta Detector (GSE - Surveyor) ML 260. ., Test Procedure for	
				MARSHALL LABORATORIES	
				S40533	
				SHEET 8 OF	

## 8.0 FILM PRESET

8.1 The select resistors located on TB7 are as follows:

R96 = 33K	R83 = 5.6K
R91 = 300	R82 = 9.1K
R90 = 510	R81 = 325
R89 = 750	R80 = 430
R88 = 1.0K	R79 = 620
R87 = 1.5K	R78 = 2.2K
R86 = 2.0K	R77 = 7.5K
R85 = 3.0K	R76 = 16K
R84 = 3.9K	R75 = $\infty$

RELEASE	DATE	TITLE	<b>MARSHALL LABORATORIES</b>
PREPARED	FE 14 1960	Micrometeorite Ejecta Detector (GSE - Surveyor) ML 260-1, Test Procedure for	
CHECKED			
APPROVED			
S40533			
SHEET 9 OF			

FORM ML 77

MFG. CODE NUMBER 13126



## 1.0 SCOPE

- 1.0 Scope. This procedure describes the test required to verify proper operation of the electronics on Digital Readout and Commands Board. This assembly 51327-101 is a portion of the Surveyor Ejecta Detector ML 260-1.

## 2.0 APPLICABLE DRAWINGS

### Marshall Laboratories

51287 Sheet 1	Schematic
T51311-1-101	Matrix
51327-101	Digital Readout and Commands Assembly.

## 3.0 TEST EQUIPMENT

(Equivalent units are acceptable)

- 3.1 Oscilloscope - Tektronix Type 535A.
- 3.2 Plug-In Unit - Tektronix Type CA.
- 3.3 Digital Voltmeter - Non linear Systems Model 481.
- 3.4 Volt - Ohmeter - Triplet Model 630NA.
- 3.5 Pulse Generator - Intercontinental Instruments Incorporated, PG-2.
- 3.6 Power Supply - Harrison Laboratories Model 865B.

## 4.0 PRELIMINARY TEST

- 4.1 Make a continuity check from all pins on J4, J5 and P3 to proper modules and tie points.
- 4.2 Apply  $3.0 \pm .1$  v to P3-7 and ground to P3-2.

RELEASE MASTER	FEB 04 1965	TITLE	MARSHALL LABORATORIES	
PREPARED		Digital Readout and Commands Board Surveyor Ejecta Detector, ML 260-1 Test Procedure for	S40534	
CHECKED				
APPROVED				
			SHEET	2 OF

## 5.0 DIGITAL READOUT

- 5.1 Apply a  $100 \pm 2$  cps square wave  $.1 \pm .1v$  to  $1.5 \pm .1v$  to P3-21. Synchronize the scope on the positive going edge.
- 5.1.1 Observe waveform on Z9-6. Should be the inverse of the square wave in Section 5.1  $3.0v \pm .1v$  to  $.1v \pm .1v$ .
- 5.1.2 Wave form at Z10-6 should be a positive pulse  $.1v \pm .1v$  to  $2.2v \pm .1v$ , pulse width of 3.0 ms.
- 5.1.3 Waveform at Z11-6 should be a positive pulse delayed by  $3.0 \text{ ms} \pm .3 \text{ ms}$ , amplitude  $.1v \pm .1v$  to  $2.2v \pm .1v$ , and pulse width  $200 \mu\text{sec} \pm 20 \mu\text{sec}$ .
- 5.1.4 Connect Z2-6 to Ground. Observe a negative going pulse delayed by  $3.0 \text{ ms} \pm .3 \text{ ms}$ , amplitude  $3.0 \pm .1v$  to  $.1v \pm .1v$  on Z12-6.
- 5.1.5 Waveform at Z13-6 should be a negative pulse  $3.0v \pm .1v$  to  $.1v \pm .1v$ , delayed by  $3.0 \text{ ms} \pm .3 \text{ ms}$ , pulse width  $30 \mu\text{sec} \pm 5 \mu\text{sec}$ .
- 5.1.6 Synchronize scope on Z19-6, negative edge. Observe waveform at Z14-5. It should be a square wave starting at  $.1v \pm .1v$  and going to  $2.2v \pm .1$  at 10.0 ms delay from sync. Frequency is 50 cps (20 ms). Check Z14-6 wave inverted.
- 5.1.7 Observe waveform at Z15-5. It should be a square wave starting at  $.1v \pm .1v$  and going to  $2.2v \pm .1$  at 20 ms delay from sync. Frequency is 25 cps (40 ms). Check Z15-6 wave is inverted.
- 5.1.8 Observe waveform at Z16-5. It should be a square wave starting at  $.1v \pm .1v$  and going to  $2.2v \pm .1$  at 40 ms delay from sync. Frequency is 12.5 cps (80 ms). Check Z16-6 wave is inverted.
- 5.1.9 Observe waveform at Z17-5. It should be a square wave starting at  $.1v \pm .1v$  and going to  $2.2v \pm .1$  at 80 ms delay from sync. Frequency is 6.25 cps (160 ms). Check Z17-6 wave is inverted.

RELEASED	FEB 1965	DATE	TITLE	<b>MARSHALL LABORATORIES</b>
PREPARED			Digital Readout and Commands Board Surveyor Ejecta Detector, ML 260-1 Test Procedure for	NO.
CHECKED				
APPROVED				S40534
				SHEET 3 OF

- 5.1.10 Observe waveform at Z17-8. It should be a negative going pulse. Amplitude is  $3.0v \pm .1$  to  $.1v \pm .1v$ . Pulse width is approximately  $20 \mu\text{sec}$ .
- 5.1.11 Remove Ground that was connected in Section 5.1.4 and the pulse in section 5.1.10 should disappear. Connect P3-35 to  $3.0v$ .
- 5.1.12 Replace the Ground to Z2-6. Observe waveform at Z7-6. It should be a positive going pulse,  $.1v \pm .1v$  to  $2.2v \pm .1v$ . Pulse width is  $400 \mu\text{sec} \pm 40 \mu\text{sec}$ . Also Z41-5 should be at  $.1v \pm .1v$ .
- 5.1.13 Reset generator described in Section 5.1 to 1 cps.
- 5.1.14 Observe Z3-5, Z4-5, Z5-5, they should be at  $2.2v \pm .1v$ .
- 5.1.15 Remove P3-35 from  $3.0v$  and connect it to Ground.
- 5.1.16 Observe Z3-5, Z4-5, Z5-5, they should be at  $.1v \pm .1v$ .
- 5.1.17 Place scope on Z12-6. Within one second after the removal of the wire on P3-35, a negative pulse will appear. A total of sixteen pulses, one second apart will appear. After which, the output at Z12-6 will return to  $3.0v$  and hold.
- 5.1.18 Connect Z2-6 to ground. Connect  $\mu 3-35$  to  $+3.0v$ .
- 5.1.19 Observe Pin 5 of each of the following modules. Z8, 20, 21, 22, 23, 24, 25, 25, 27, 28, 29, 30, 31, 32, 33, and 34.
- 5.1.19.1 The output at Pin 5 of the modules should be  $2.2v \pm .1$ .
- 5.1.20 Remove P3-35 from  $3.0v$  and connect it to ground.
- 5.1.21 Repeat Section 5.1.19.
- 5.1.21.1 The output at Pin 5 of the modules should be  $.1v \pm .1v$ .
- 5.1.22 Remove all connections except  $+3v$  and ground.
- 5.2 Command Signals.

RELEASE RELEASED	DATE FEB 3 1965	TITLE	MARSHALL LABORATORIES
PREPARED		Digital Readout and Commands Board Surveyor Ejecta Detector, ML 260-1 Test Procedure for	
CHECKED			
APPROVED			
			NO. S40534
			SHEET 4 OF



S40534

CM3 LTR

- 5.2.1 Apply +29v  $\pm$  .5v P3-8.
- 5.2.2 Apply negative going pulse to P3-11. Amplitude 3.0v, pulse width 100  $\mu$ sec, at 1 cps.
- 5.2.3 Observe positive pulse at Z38-6, .1v  $\pm$  .1v to 2.2v  $\pm$  .1, pulse width 700  $\mu$ sec  $\pm$  100  $\mu$ sec.
- 5.2.4 Observe positive pulse at Z37-6, .1v  $\pm$  .1v to 2.2v  $\pm$  .1, pulse width 20  $\mu$ sec  $\pm$  .2  $\mu$ sec.
- 5.2.5 Observe positive pulse at Z35-6, the amplitude should be 0v to 29v  $\pm$  .2v, pulse width 20  $\mu$ sec  $\pm$  .2  $\mu$ sec. Observe pulse at the junction of R<sub>1</sub> and R<sub>2</sub>. The amplitude should be 23v  $\pm$  1v. Risetime 2msec  $\pm$  .5msec.
- 5.2.6 Connect Ground to P3-9 and then to P3-10. The pulse in Section 5.2.5 should disappear.
- 5.2.7 Remove Ground from P3-9 and P3-10.
- 5.2.8 Observe pulse at Z36-6. It should be the same as in Section 5.2.5. The pulse at the junction of R4 and R3 should have an amplitude of 23v  $\pm$  1v and a rise time of 2msec  $\pm$  .5msec.
- 5.2.9 Connect Ground to P3-10 and P3-12, the pulse in Section 5.2.3 should disappear.
- 5.2.10 Remove Ground from P3-10 and P3-12.
- 5.2.11 Observe pulse at Z39-6. It should be the same as in Section 5.2.5. The pulse at the junction of R6 and R5 should have an amplitude of 23v  $\pm$  .5v, and a rise time of 2msec  $\pm$  .5msec.
- 5.2.12 Connect Ground to P3-10 and P3-13, the pulse should disappear.
- 5.3 Commands (Enter Data)
- 5.3.1 Connect Ground to P3-10.
- 5.3.2 Observe the output at Z44-18, It should be a square wave 1.0  $\pm$  .5 cps amplitude 3.0v  $\pm$  .1 to .1v  $\pm$  .1v.

RELEASED		DATE	TITLE	MARSHALL LABORATORIES	
PREPARED					
CHECKED			Digital Readout and Commands Board Surveyor Ejecta Detector, ML 260-1 Test Procedure for	NO.	
APPROVED				S40534	
				SHEET 5 OF	

- 5.3.3 Observe the output at Z43-6, It should be the inverted signal of Z44-18. Amplitude  $3.0v \pm .1v$  to  $.1v \pm .1$ .
- 5.3.4 Observe the output at Z42-6. It should be at one half the frequency of Z43-6, amplitude  $2.2v \pm .1v$  to  $.1v \pm .1$ .
- 5.3.5 Observe the output at Z40-6. It should be a positive pulse 200  $\mu$ sec wide at a repetition rate of one half Z44-18. Amplitude  $.1v \pm .1v$  to  $2.2v \pm .1v$ .
- 5.3.6 Observe pulse at Z19-6. It should be a negative going pulse  $3.0v \pm .1v$  to  $.1v \pm .1$  and approximately 20  $\mu$ sec wide and at the same rate as described in Section 5.3.5.
- 5.3.7 Monitor Z41-5. If not at  $.1v \pm .1v$ , momentarily ground Pin 5. The output should return to  $2.2v \pm .1$  on the leading edge of Z40-6.
- 5.3.8 Monitor Z40-6.
- 5.3.8.1 Connect P3-15 to Ground. The pulses in Section 5.3.8 should disappear.
- 5.3.9 Remove Ground from P3-10.
- 5.3.10 Observe Z42-6. If it is not at  $.1v \pm .1v$ , momentarily ground pin 6 of Z42.
- 5.3.11 Momentarily Ground P3-17 and Z42-6 should return to  $2.2v \pm .1v$ .
- 5.3.12 Momentarily connect P3-16 to 3.0v and Z42-6 should return to  $.1v \pm .1v$ .

RELEASE	DATE	1965	TITLE	<b>MARSHALL LABORATORIES</b>
PREPARED			Digital Readout and Commands Board Surveyor Ejecta Detector, ML 260-1 Test Procedure for	
CHECKED				
APPROVED				
S40534				SHEET 6 OF 6

1. USE 2. REWORK		PARTS DISPOSITION 3. CANNOT BE REWORKED 4. RECORD			5. ....  S40535	
REVISIONS						
DISP	EFF	SYM	DESCRIPTION		BY	DATE
Large empty area for revisions						

SHEET INDEX	REV																
	SHEET	1	2	3	4	5											
RELEASE		DATE		TITLE													
PREPARED		FEB 1 1965		Power Supply Board, CSE - Surveyor Test Specification for													
CHECKED		Feb 165															
APPROVED		FEB 2 1965															
		2-4-65															
		2-4-65															

**MARSHALL  
LABORATORIES**

NO.  
S 40535  
SHEET 1 OF 5

## 1.0 SCOPE

1.1 This procedure describes the tests required to verify the proper operation of the power supply board (Assem. 51328) this is part of the Surveyor's ground support equipment.

## 2.0 APPLICABLE DRAWINGS

- 2.1 Board Assembly, Power Supply GSE, 51328
- 2.2 Schematic diagram, micrometeorite ejecta detector, GSE Surveyor 51287.
- 2.3 Mylar Matrix, 51305-101.

## 3.0 TEST EQUIPMENT

- 3.1 Oscilloscope, Tektronix, Model 535A.
- 3.2 Plug-in pre-amp., Type CA.
- 3.3 Power Supply, Harrison Laboratory, Model 865B.
- 3.4 Resistor Decade Box, General Radio, Type K132L.
- 3.5 Digital Voltmeter, Cubic model, V-71.
- 3.6 Transistors, 2N1485, 3 ea

RELEASE	DATE	TITLE	<b>MARSHALL LABORATORIES</b>
PREPARED	FEB 4 1965	Power Supply Board, GSE - Surveyor, Test Specification for	
CHECKED			
APPROVED			
S 40535			
SHEET 2 OF			




Figure 1.

#### 4.0 TEST PROCEDURE

- 4.1 Check continuity from P8 connector to board as per print 51287.
- 4.2 Temporarily install nominal values for R103, R104, and R114.
- 4.3 Make test hook up as in Figure 1.
- 4.4 Limit input current to 400 ma  $\pm$  25 ma.
- 4.5 Apply 13.3 volts  $\pm$  0.13v to P8 - 13 (+) and P8 - 14 (-).
- 4.6 Select R102 for 11.0 volts  $\pm$  0.1v at Z101-17 (+) and Z101-2 (-).
- 4.7 Select R103's value for a 2400 cps  $\pm$  100 cps square wave and an amplitude of 22 volts  $\pm$  .5v at the converter transformer SP 30279 Pin 1 and 13.3 volt return.
- 4.8 Adjust the external loads.

3 volts at 10 ma

RELEASE	DATE	1965	TITLE	Power Supply Board GSE - Surveyor, Test Specification for	MARSHALL LABORATORIES
PREPARED					
CHECKED					
APPROVED					
S 40535				SHEET 3 OF	

22 volts at 50 ma

28 volts at 20 ma

30 volts at 10 ma

4.9 28 Volts Supply

4.9.1 Adjust R110 to Mid position

4.9.2 Select R114 for 28 volts  $\pm .25v$ , maintain a 22 ma load.

4.9.3 Check range of R110 from min.  $26.5 \pm 0.0v - .3v$  to max.  $28.5 \text{ volts} \pm .3v - 0.0v$ . Select R114 for this range of R110.

4.9.4 Tack solder R114 in place and record value.

4.9.5 Maintain a 20 ma load on the 28 volt line for balance of test.

4.10 3.volt supply

4.10.1 Measure voltage at P8 - 7 and ground with a 10 ma load. This should be 3.0 volts  $\pm 5\%$ .

4.10.2 Remove external load. The voltage will still be 3.0 volts  $\pm 5\%$ .

4.10.3 Reconnect 10 ma load for balance of test.

4.11 Heater voltage (22 volts)

4.11.1 Adjust R115 for 22 volts  $\pm 0.1v$  across P8 - 16 (+) and P8-4 (-) with an external load of 50 ma.

4.11.2 Maintaining a 50 ma load, vary R110 from min. of  $16.5 \pm 200 \text{ mv}$  to a maximum of  $26.5 \pm 200 \text{ mv}$ .

4.11.3 Return to 22 volts at 50 ma for balance of test.

4.11.4 Insert an am-meter in series of emitter of Q105. This should read not more than 10 ma.

4.11.5 Caution: Set meter to 60 ma scale. Remove external load, emitter current will jump to 50 ma  $\pm 1\%$ . If needed, reselect R112 for proper emitter current.

4.11.6 Reconnect 50 ma external load. Restore emitter circuit.

RELEASE	LEASED	FF	DATE	1965	FILE	Power Supply Board, GSE - Surveyor, Test Specification for	MARSHALL LABORATORIES
PREPARED							
CHECKED							
APPROVED							
						S 40535	
						SHEET 4 OF	

4.12 30 volt supply.

4.12.1 Select R104 for 30 volts  $\pm .1v$  as read across P8-1 (+) and P8-2 (-) with a 10 ma load.

4.12.2 Tack solder R104 in place and record.

4.12.3 Vary load from 8 ma to 12 ma. Voltage regulation shall be 30 volts  $\pm .1v$ .

4.12.4 Return load to 10 ma for balance of test.

4.13 Total Current

4.13.1 Vary input to power supply board from 12.0 volts to 14.6 volts. The voltage across Z101-17 + and Z101-2 shall remain at 11.0 volts  $\pm .1v$ .

4.13.2 Record total input current at 12.0 volts and at 14.6 volts.

RELEASE	DATE	BY
PREPARED		
CHECKED		
APPROVED		

Power Supply Board,  
GSE - Surveyor,  
Test Specification for

**MARSHALL  
LABORATORIES**

S 40535

SHEET 5 OF 5

1. USE 2. REWORK		PARTS DISPOSITION 3. CANNOT BE REWORKED 5..... 4. RECORD			S40536	
REVISIONS						
DISP	RFP	SYN	DESCRIPTION		BY	DATE
Empty space for revisions						

SHEET INDEX	REV	1	2	3	4	5										
	SHEET															

RELEASE Released PREPARED D. Rose/go CHECKED <i>Don Rose</i> APPROVED <i>W. H. Kamm</i>	DATE 10/29/64 10/29/64 11/17/64 11/17/64	TITLE Sensor Stimulus Board Surveyor Ejecta Detector ML 260-1 Test Specification For	MARSHALL LABORATORIES
NO. S40536			SHEET 1 OF 5



CHG LTR  
S40536

1.0 SCOPE

This procedure describes the test required to verify proper operation of the electronics on the Sensor Stimulus Board. This Assembly 51326 is a portion of the Surveyor Ejecta Detector ML 260-1.

2.0 APPLICABLE DRAWINGS

- 2.1 51326 Assembly, Sensor Stimulus
- 2.2 51287 Sht. 3 Schematic
- 2.3 51324-101 Matrix

3.0 TEST EQUIPMENT

3.1 The following standard test equipment, or equivalent, shall be used to check out the module.

- 3.1.1 Oscilloscope - Tektronix, Model 535A.
- 3.1.2 Plug-In Unit - Tektronix, Type CA.
- 3.1.3 Digital Voltmeter, Non-Linear Systems, Model 481.
- 3.1.4 Volt-Ohmmeter, Triplet Model 630NA.
- 3.1.5 Pulse Generator - Intercontinental Instruments Incorporated, PG-2.
- 3.1.6 Power Supply - Harrison Laboratories, Model 865B.

4.0 PRELIMINARY TEST

- 4.1 Make a continuity check from all pins on P6 to proper module pins.
- 4.2 Apply 3.0v to J6-13 and ground to J6-41.

5.0 STIMULUS TIMING

- 5.1 Apply a 1.5v negative going pulse, 100μsec pulse width and 5 cps repetition rate to J6-19.

NOTE: All amplitude and timing measurements should be within  $\pm 20\%$  unless otherwise specified.

RELEASE	DATE	TITLE	MARSHALL LABORATORIES	
PREPARED D. Rose/go	10/29/64	Sensor Stimulus Board Surveyor Ejecta Detector ML 260-1 Test Specification For		
CHECKER			NO.	
APPROVED			S40536	
			SHEET	2 OF

- 5.1.1 The output at Z45-6 should be a  $2.2v \pm .1v$  positive pulse 50 $\mu$ sec wide.
- 5.1.2 The output at Z46-6 should be a  $2.2v \pm .1v$  positive pulse 450 $\mu$ sec wide.
- 5.1.3 The output at Z47-6 should be a  $2.2v \pm .1v$  positive pulse 45 msec wide.
- 5.1.4 The output at Z48-6 should be a  $2.2v \pm .1v$  positive pulse 20  $\mu$ sec wide.
- 5.1.5 The output at Z49-8, Z50-8, and Z51-8 should be a  $2.8v \pm .1v$  negative going pulse 20  $\mu$ sec wide.
- 5.2 Connect the following wires to gnd.: P6-3, 6, 30, 40.
- 5.2.1 The output at Z58-6 should be positive pulse  $2.2v \pm .1v$  delayed from the leading edge of the pulse described in Section 5.1 by less than 5  $\mu$ sec, and a pulse width of 200  $\mu$ sec.
- 5.2.2 Disconnect gnd. from P6-3, and observe pulse as described in Section 5.2.1.
- 5.2.3 Disconnect gnd. from P6-6, and observe pulse as described in Section 5.2.2. In addition a pulse should appear delayed by 500  $\mu$ sec  $\pm$  50  $\mu$ sec.
- 5.2.4 Disconnect gnd. from P6-30, and observe pulse as described in Section 5.2.3. In addition a pulse should appear delayed by 50 ms  $\pm$  5 ms.
- 5.3 Connect the following to gnd.: P6-8, 7, 1, 25.
- 5.3.1 The output at Z66-6 should be positive pulse  $2.2v \pm .1v$  delayed from the leading edge of the pulse described in Section 5.1 by less than 5  $\mu$ sec., and a pulse width of 5 ms  $\pm$  .5 ms.
- 5.3.2 Disconnect gnd. from P6-8, and observe pulse as described in Section 5.3.1.
- 5.3.3 Disconnect gnd. from P6-7, and observe pulse as described in Section 5.3.2.
- 5.3.4 Disconnect gnd. from P6-1, and observe pulse as described in Section 5.3.3. In addition a pulse should appear delayed by 50 m sec.  $\pm$  5 msec.

RELEASE	DATE	TITLE	<b>MARSHALL LABORATORIES</b>
PREPARED		Sensor Stimulus Board	
D. Rose/co	10/29/64	Surveyor Ejecta Detector	
CHECKED		ML 260-I	
APPROVED		Test Specification For	
			S40536 SHEET 3 OF 3

CMG LTR  
S40536

- 5.4 Connect the following to gnd. P6-9, 29, 2.
- 5.4.1 The output at Z71-6 should be a positive pulse  $2.2v \pm .1v$  delayed from the leading edge of the pulse described in Section 5.1 by less than  $5 \mu sec.$ , and a pulse width of  $5 msec \pm .5 msec.$
- 5.4.2 Disconnect gnd. from P6-9 and observe pulse as described in section 5.4.1.
- 5.4.3 Disconnect gnd. from P6-29, and observe pulse as described in section 5.4.2.
- 5.4.4 Disconnect gnd. from P6-2, and observe pulse as described in section 5.4.3.
- 5.5 Remove all wires that have not been removed previously, except B+ and B+ return.
- 5.6 Place scope across P6-15 and 16, scope return on P6-16.
- 5.6.1 Apply 3v to P6-14, and gnd. to P6-25.
- 5.6.2 Apply a positive pulse  $1.5v$ ,  $10 \mu sec.$ , pulse width, and 5 cps repetition rate to pins P6-20, 4, 5, 23 one at a time while observing a pulse on the scope.
- 5.6.3 The signal as seen on scope should be negative going  $0.1$  to  $-3.0v$ , pulse width  $\approx 400 \mu sec$  with  $\approx 100 \mu sec$  rise time. The fall time  $< 2.0 \mu sec.$
- 5.6.4 Connect P6-18 to gnd. The signal in section 5.6.2 should disappear.
- 5.7 Repeat section 5.5
- 5.8 Place scope across P6-17 and 34, scope return on P6-34.
- 5.8.1 Apply 3v to P6-28.
- 5.8.2 Apply pulse as in section 5.6.2 except to pins P6-20, 4, 24, 25.
- 5.8.3 The signal should be  $\approx 2.0 Msec.$ ,  $0.1$  to  $-3.0v$ ,  $\approx 1 ms$  rise time. Fall time should be  $< 2.0 \mu sec.$
- 5.8.4 Connect P6-18 to gnd. The signal in section 5.8.3 should disappear.
- 5.8.5 Remove connection made in section 5.8.4. The signal should again disappear when grounding P6-33.
- 5.9 Remove gnd on P6-33. Replace scope on P6-27 and 34 scope return on P6-34.

RELEASE	DATE	TITLE	MARSHALL LABORATORIES	
PREPARED D. Rose/go	10/29/64	Sensor Stimulus Board Surveyor Ejecta Detector ML 260-1 Test Specification For		
CHECKED			NO.	S40536
APPROVED			SHEET	4 OF

5.9.1 The signal should be as in section 5.8.3.

5.9.2 Connect P6-18 to gnd. The signal in section 5.9.1 should disappear.

5.9.3 Remove connection made in section 5.9.2. The signal should again disappear when grounding P6-32.

6.0 Remove gnd. on P6-32. Replace scope on P6-39 and 22 scope return on P6-22.

6.1 Repeat section 5.8.2, through section 5.8.5.

6.2 Remove gnd on P6-33. Replace scope on P6-21 and 22 scope return on P6-22.

6.2.1 The signal should be as in section 5.8.3.

6.2.2 Connect P6-18 to gnd. The signal in section 6.2.1 should disappear.

6.2.3 Remove gnd on P6-18. The signal should disappear when grounding P6-32.

RELEASE	DATE	TITLE	MARSHALL LABORATORIES	
PREPARED D. Rose/go	10/29/64	Sensor Stimulus Board Surveyor Ejecta Detector ML 260-1 Test Specification For		
CHECKED			NO.	
APPROVED			S40536	
			SHEET 5 OF 5	

MFG. CODE NUMBER 13126

FORM ML 77



CMS DTR

S40519

- 1.0 SCOPE
  - 1.1 This procedure describes the tests required to verify proper operation of the electronics in the Surveyor Power Supply Blivet. This assembly, 51122, is a portion of the Surveyor Micrometeorite Electa Detector, ML 185-1.
- 2.0 APPLICABLE DRAWINGS
  - 2.1 Marshall Laboratories 51122 Housing Assembly, Power Supply
  - 2.2 Marshall Laboratories 51114 Schematic
  - 2.3 Matrix Mylars - T51210-1, T51215-1, -2.
- 3.0 TEST EQUIPMENT (Equivalent units are acceptable).
  - 3.1 Oscilloscope - Tektronix, Type 535A.
  - 3.2 Plug-In Unit, Tektronix, Type CA.
  - 3.3 Digital Voltmeter, Non-Linear Systems, Model 481.
  - 3.4 Volt-Ohmmeter, Triplet, Model 630NA.
  - 3.5 True RMS Voltmeter - Ballantine Model 320.
  - 3.6 Pulse Generator, Marshall Laboratories Model 246-1.
  - 3.7 Power Supply, Harrison Laboratories, Model 865B.
- 4.0 PRELIMINARY TESTS
  - 4.1 Perform visual inspection on parts and welds.
  - 4.2 Using Triplet Volt-ohmmeter on 1K scale, check continuity of pins of connectors 252J02 and J3 to proper terminations.
- 5.0 POWER SUPPLY
  - 5.1 Install the nominal value of resistors R1 (27K 1/4w 5%), R2 (EM 1/10 4.99K 1%), and R3 (EM 1/10 4.99K 1%).

RELEASE Released	DATE 9/16/64	TITLE Surveyor Power Supply Blivet Test Specification For	MARSHALL LABORATORIES
PREPARED H. Rosenberg/gc	9/16/64		
CHECKED			
APPROVED			
			NO. S40519
			SHEET 2 OF 3



5.7.1 The ripple on the +12v line should be less than 1.5 mv RMS measured on the Ballantine RMS voltmeter.

5.8 Select the value of R3 so that the voltage at Z83-1 is  $-7.00 \pm .070v$ .

5.8.1 The ripple on the -7v line should be less than 1.5 mv RMS measured on the Ballantine RMS voltmeter.

5.9 B Supply Monitor

5.9.1 The voltage at J2-25 should be  $+2.04 \pm .041v$ .

6.0 TELEMETRY AND READOUT

6.1 Select values.

6.1.1 Select C7 and C9 (2000 pf NOM), which attach to Z24-3, 9 and Z24-10, 17 so that the clock output at Z24-18 is  $100 \pm 1$  cps. The amplitude of this square wave should be  $.1v \pm .1v$  to  $2.9v \pm .1v$ .

6.2 The output of Z21, pin 6, should be a positive going pulse  $100 \pm 2\mu s$  wide,  $.1 \pm .1v$  to  $2.2 \pm .1v$  occurring every  $10 \pm 0.1$  ms.

6.2.1 A negative pulse should also be observed at Z18-12, the amplitude should be  $0.1 \pm 0.1v$  to  $+3.0 \pm 0.1v$ .

6.3 Apply a +3v to 0v negative pulse at a 1 cps rate to J3-14. The pulse at Z18-12 (6.2.1) should no longer appear. This pulse should now appear at Z19-6. Note. Applied pulse has a pulse width of 100  $\mu sec$ .

6.4 Sequence.

6.4.1 The output of Z16, pins 3 and 5, should be a 50 cps (period = 20 ms) square wave whose amplitude varies from  $+2.1 \pm 0.1v$  to  $0.1 \pm 0.1v$  for a duration of 190 ms.

6.4.2 The output of Z15, pins 3 and 5, should be a 25 cps (period = 40 ms) square wave whose amplitude varies from  $+2.1 \pm 0.1v$  to  $0.1 \pm 0.1v$  for 190 ms.

6.4.3 The output of Z12, pins 3 and 5, should be a 12.5 cps (period = 80 ms) square wave whose amplitude varies from  $+2.1 \pm 0.1v$  to  $0.1 \pm 0.1v$  for 190 ms.

6.4.4 The output of Z13, pins 3 and 5, should be a 6.25 cps (period = 160 ms) square wave whose amplitude varies from  $+2.1 \pm 0.1v$  to  $0.1 \pm 0.1v$ .

RELEASE	DATE	TITLE	MARSHALL LABORATORIES
Released	9/16/64	Surveyor Power Supply	
PREPARED	9/16/64	Blivet	
CHECKED		Test Specification For	
APPROVED			
			NO. S40519
			SWEET 4 OF

MFG. CODE NUMBER 13126

FORM ML 77



6.4.5 The output of Z14, pins 3 and 5, should be a 3.125 cps (period = 320 ms) square wave whose amplitude varies from  $+2.1 \pm 0.1$  v to  $0.1 \pm 0.1$  v for 190 ms.

6.5 Sync the scope on the negative going edge being applied to J3-14. Load J3-1 with a resistor and capacitor in series to ground. The resistor should be 5K and the capacitor should be 2000 pf. The output pulse at J3-1 should be delayed no more than .6  $\mu$ s. The output itself should be a negative going  $+3.0 \pm 0.1$  v to  $0.1 \pm 0.1$  v, 10  $\mu$ s + 10  $\mu$ s, and -0  $\mu$ sec. pulse occurring at a 1 cps rate.


6.6 Readout.

6.6.1 Sync the scope positively on Z16 pin 5.

6.6.2 Connect scope to Z 1 - 11.

6.6.3 Information Output.

6.6.3.1 The output at Z1-11 should be at 0v for 25 ms and rise to 6.0v for 5 ms and return to 0v until T = 195 ms, at that time the output will be a 100 cycle square wave until the next readout pulse.



6.6.3.2 Connect J3-9 to ground. The output at Z1-11 should have a 5 ms pulse at T = 35 ms in addition to that described in 6.6.3.1.

6.6.3.3 Remove ground from J3-9 and connect it to J3-22. The output at Z1-11 should have a 5 ms pulse at T = 45 ms in addition to that described in 6.6.3.1.

6.6.3.4 Remove ground from J3-22 and connect it to J3-2. The output at Z1-11 should have a 5 ms pulse at T = 55 ms in addition to that described in 6.6.3.1.

6.6.3.5 Remove ground from J3-2 and connect it to J3-25. The output at Z1-11 should have a 5 ms pulse at T = 65 ms in addition to that described in 6.6.3.1.

RELEASE	Released	9/16/64	TITLE	Surveyor Power Supply	MARSHALL LABORATORIES
PREPARED	H. Rosenberg/go	9/16/64	Blivet		
CHECKED			Test Specification For		
APPROVED					
					S40519
				SHEET	5 OF

6.6.3.6 Remove ground from J3-25 and connect it to J3-6. The output at Z1-11 should have a 5 ms pulse at T = 75 ms in addition to that described in 6.6.3.1.

6.6.3.7 Remove ground from J3-6 and connect it to J3-21. The output at Z1-11 should have a 5 ms pulse at T = 85 ms in addition to that described in 6.6.3.1.

6.6.3.8 Remove ground from J3-21 and connect it to J3-20. The output at Z1-11 should have a 5 ms pulse at T = 95 ms in addition to that described in 6.6.3.1.

6.6.3.9 Remove ground from J3-20 and connect it to J3-23. The output at Z1-11 should have a 5 ms pulse at T = 105 ms in addition to that described in 6.6.3.1.

6.6.4.0 Remove ground from J3-23 and connect it to J3-3. The output at Z1-11 should have a 5 ms pulse at T = 115 ms in addition to that described in 6.6.3.1.

6.6.4.1 Remove ground from J3-3 and connect it to J3-24. The output at Z1-11 should have a 5 ms pulse at T = 125 ms in addition to that described in 6.6.3.1.

6.6.4.2 Remove ground from J3-24 and connect it to J3-5. The output at Z1-11 should have a 5 ms pulse at T = 135 ms in addition to that described in 6.6.3.1.

6.6.4.3 Remove ground from J3-5 and connect it to J3-32. The output at Z1-11 should have a 5 ms pulse at T = 145 ms in addition to that described in 6.6.3.1.

6.6.4.4 Remove ground from J3-32 and connect it to J3-26. The output at Z1-11 should have a 5 ms pulse at T = 155 ms in addition to that described in 6.6.3.1.

6.6.4.5 Remove ground from J3-26 and connect it to J3-4. The output at Z1-11 should have a 5 ms pulse at T = 165 ms in addition to that described in 6.6.3.1.

RELEASED	9/17/64	WILE	Surveyor Power Supply Blivet Test Specification For	MARSHALL LABORATORIES
PREPARED H. Rosenberg/go	9/16/64			
CHECKED				
APPROVED				
				S40519
			ONE	6 OF

6.6.4.6 Remove ground from J3-4 and connect it to J3-8. The output at Z1-11 should have a 5 ms pulse at T = 175 ms in addition to that described in 6.6.3.1.

6.6.4.7 Remove ground from J3-8 and connect it to J3-7. The output at Z1-11 should have a 5 ms pulse at T = 185 ms in addition to that described in 6.6.3.1.

6.6.4.8 Remove ground from J3-7.

6.6.5 SCO Driver

6.6.5.1 The output at J2-13 should be a 0v for 25 ms, rise to +6.0v for 5 ms, fall to 0v for 165 ms, and then return to a +3.0v 100 cps square wave. The rise and fall time should be  $\approx 400 \mu\text{sec}$ .

6.6.6 Mic Accumulator Inhibit

6.6.6.1 The output at J3-33 should be at +3.0v for the first 120 ms of the readout, fall to 0v for 30 ms, and then return to +3.0v.

6.6.7 Film Accumulator Inhibit

6.6.7.1 The output at J3-30 should be at +3.0v for the first 150 ms of the readout, fall to 0v for 40 ms, and then return to +3.0v.

6.6.8 Detect End of Readout

6.6.8.1 The output at J3-27 should be at +3.0v for the whole readout of 200 ms. At 200 ms, a negative going pulse 100 ms wide every 10 ms should appear at J3-27.

7.0 COMMANDS

7.1 Calibrate Command

7.1.1 Apply to J2-10 a positive going 20 ms 0 to 15v pulse with a 2ms rise time and a .1 ms fall time. At j3-31 the output pulse should be a negative going pulse  $2.3v \pm .1$  to  $.1v \pm .1v$ , pulse width of  $20 \text{ ms} \pm 2 \text{ ms}$ .

RELEASE Released	DATE 9/16/64	TITLE Surveyor Power Supply Blivet Test Specification For	<b>MARSHALL LABORATORIES</b>
PREPARED H. Rosenberg/go	9/16/64		
CHECKED			
APPROVED			
			S40519
			SHEET 7 OF

7.2 Clear Command

7.2.1 Apply to J2-11 a positive going 20 ms, 0 to 15v pulse with a 2 ms rise time and a .1 ms fall time. The output at J3-28 should be a positive going pulse, from 0.1v,  $\pm 0.1v$  to  $2.3v \pm .1v$ , and  $1.5 ms \pm .15 ms$  in duration.

7.3 Readout Command

7.3.1 Apply to J2-22 a positive going, 20 ms, 0 to +15v pulse with a 2 ms rise time and a .1 ms fall time.

7.3.2 The output at Z23-11 should be a negative pulse,  $2.3v \pm .1v$  in amplitude and  $20 ms \pm 2 ms$  duration.

7.3.3 The output at Z1-11 should be as described in 6.6.3.1.

RELEASE Released	DATE 9/16/64	TITLE Surveyor Power Supply Blivet Test Specification For	<b>MARSHALL LABORATORIES</b>
PREPARED H. Rosenberg/go	9/16/64		
CHECKED			
APPROVED			
			S40519
			SHEET 8 OF 8

S40548

## 1.0 SCOPE

This procedure describes the tests required to verify proper operation of the electronics in the Surveyor Digital Blivet. This assembly, 51237, is a portion of the Surveyor Micrometeorite, Ejecta Detector, ML 185-1.

## 2.0 APPLICABLE DRAWINGS

- 2.1 Marshall Laboratories 51237 Housing Assembly, Digital Blivet.
- 2.2 Marshall Laboratories 51114 Schematic.
- 2.3 Matrix Mylars TS 1212, TS 1213

## 3.0 TEST EQUIPMENT

- 3.1 Oscilloscope, Tektronix Type 535A
- 3.2 Plug-In Unit, Tektronix, Type CA.
- 3.3 Digital Voltmeter, Non-Linear Systems, Model 481.
- 3.4 Volt. Ohmmeter, Triplet, Model 630-NA.
- 3.5 True R. M. S. Voltmeter, Ballantine Model 320.
- 3.6 Pulse Generator, Intercontinental Instruments Incorporated, PG-2
- 3.7 Power Supply, Harrison Lab., Model 865B.

## 4.0 PRELIMINARY PROCEDURE

- 4.1 Using a Triplet Ohmmeter, check the resistances between the pins A & B in Table I, use 1K scale, positive lead on A.

RELEASED	DATE	TITLE	MARSHALL LABORATORIES	
PREPARED	10/6/64	Test Specification for Surveyor Digital Blivet	S40548	
CHECKED			SHEET 2 OF	
APPROVED				

CH3 LTR

S40548

Resistance Between

Resistance Should Be

A	B	( $\Omega$ )			
P3-16	P3-11	>50K	P3-36	J1-5	0
P3-16	P3-36	>10K	P3-19	J1-8	0
P3-16	P3-19	>10K			
P3-11	P3-36	>10K			
P3-19	P3-11	>9K			
P3-36	P3-19	>8K			
P3-13	J1-7	-0-			
P3-16	J1-13	-0-			
P3-11	J1-15	-0-			

4.2 Record all final select components in Laboratory Notebook.

4.3 Refer to Sec. 2.2 for types and tolerances of all select components.

## 5.0 MIC PULSE HEIGHT ANALYZER

## 5.1 Select Values

5.1.1 Install the following resistors and capacitors from Table II(a).

R or C	Value
R7	1.00K
R8	4.99K
C35	360 pf
C22	1000 pf
C23	1000 pf
R11	1.0K
R13	1.0K

TABLE II(a) - Select Values in the  
Mic PHA:

RELEASE Released	DATE 10/6/64	TITLE Test Specification for Surveyor Digital Blivet	MARSHALL LABORATORIES
PREPARED			
CHECKED			
APPROVED			
			S40548
			SHEET 3 OF

CHK LTR

S40548

### 5.1.2 Power

- 5.1.2.1 Connect  $+12.00 \pm .1V$  to P3-16.
- 5.1.2.2 Connect  $+ 6.00 \pm .06V$  to P3-36.
- 5.1.2.3 Connect  $+ 3.0 \pm .03V$  to P3-19.
- 5.1.2.4 Connect  $- 7.0 \pm .07 V$  to P3-11.
- 5.1.2.5 Connect the commons of the above supplies together and to P3-13.




FIGURE 1.

RELEASE Released	DATE 10/6/64	TITLE Test Specification for Surveyor Digital Blivet	MARSHALL LABORATORIES
PREPARED			
CHECKED			
APPROVED			
			NO. S40548
			SHEET 4 OF

MFG. CODE NUMBER 13126



S40548

CMG LTR

- 5.2 For the checkout and calibration of the Mic PHA, two Rutherford Pulse Generators are used in conjunction with a sine wave generator through a gate circuit to provide the Mic Amplifier Simulation, Data Reset Pulse, and detect end of readout pulse. See Figure I for connections.
- 5.2.1 Set P1 for a negative-going +2.0 to 0V, 1.5ms pulse occurring once every 130 ms.
- 5.2.2 Set P2 to trigger external on the leading edge of P1. Set pulse delay for 50 $\mu$  sec, Amplitude 2.0V to 0V negative-going, and pulse width for 1.5ms.
- 5.3 Apply power making sure that none of the supplies are shorted.
- 5.4 Make the connections shown in Figure I.
- 5.4.1 Set up the sine wave generator to a 4.0V p-p, 100KC wave and observe at the emitter of the gate transistor a 2V p-p, 1.5 ms burst of a 100KC sine wave occurring once every 130 ms.
- 5.4.2 Check to see that the Data Reset pulse (the negative going 1.5 ms. gating pulse) appears at Z26-8, Z27-8, Z28-8, Z51-9, Z53-10, Z32-8, Z34-8, Z35-8, Z36-8, and Z37-8.
- 5.4.3 A negative going +2.9  $\pm$  .1V to .1  $\pm$  .1V 100 $\mu$ s pulse should appear at Z53-8 occurring once every 130 ms.
- 5.5 Observe Z50-6. Adjust C15 until the output is a 2.2  $\pm$  0.2V to 0.1  $\pm$  0.1V, 100  $\pm$  2 $\mu$ s pulse.
- 5.5.1 At Z48-16, the output should be as in Figure 2.
- 5.6 Reduce the amplitude of the 100 KC sine wave to 0V. The output at Z52-6 should rise from 0V to + 3.0  $\pm$  0.1V for 100  $\mu$ s and return to 0V.
- 5.6.1 Increase the amplitude of the sine wave until the comparator output, Z44-7, remains in the up state for 250  $\mu$ s. The output of Z51, Z51-3.5, should also rise to + 2  $\pm$  0.2V for 250  $\mu$ s.

RELEASE	RELEASED	DATE	10/6/64	TITLE	<p>Test Specification for Surveyor Digital Blivet</p>	MARSHALL LABORATORIES	
PREPARED						NO.	
CHECKED						S40548	
APPROVED						SHEET	5 OF

CHK LTR

S40548

- 5.6.2 With the input sine wave as in 5.61, the output of Z49, Z49-6, should remain at OV for 100  $\mu$ s, rise to  $+2 \pm 0.2V$  for 30 ms, and return to OV.
- 5.6.3 A positive going pulse should appear at P3-14 for as long as the delay between P1 and P2.
- 5.6.4 Modules Z31 through Z29 should be counting the simulated mic hits. Pins 3 and 5 of these modules should vary between  $0.1 \pm 0.1V$  and  $+2.2 \pm 0.1V$ .
- 5.6.5 Further increase the sine wave amplitude until the comparator output, Z44-7, is in the up-state for 1ms. Pins 3 and 5 of modules Z28 through Z26 should change from  $+0.1 \pm 0.1V$  to  $+2.2 \pm 0.1V$ .




FIGURE 2. Detector Output

- 5.6.6 Remove signal from P-3 pins 1 and 27. By-pass delay.
- 5.7 Adjust the 100 kc generator so that the peak amplitude (positive going) at Z48-17 is  $100 \pm 1$  mv.
  - 5.7.1 Select and record the value of R8 which causes the comparator (Z45 and Z44) to change from  $0.1 \pm 0.1V$  to  $6.0 \pm 2V$  measured at Z44-7.
- 5.8 Short out pins 4 and 6 of Z51 to ground.

RELEASE Released	DATE 10/6/64	TITLE Test Specification for Surveyor Digital Blivet	MARSHALL LABORATORIES	
PREPARED			S40548	
CHECKED				
APPROVED				
			SHEET 6 OF	

CWG LTR

S40548

5.9 Adjust C22 and C23 until the frequency of Z42 is as close as possible to 8KC.

5.10 Apply a  $+ 2.5 \pm 0.01V$  peak burst of the 100 KC sine wave to Z48-17. Select and record the value of R7 that just causes seven clock pulse to occur. Where this setup is complete, the  $\tau$  of the detector output, Z48-16, should be greater than 250  $\mu s$  and less than 300  $\mu s$ .

5.10.1 If the value of R7, for any reason, does not satisfy the conditions of 5.8, the clock (Z42) frequency may be varied a minimum amount in order to satisfy 5.9.

5.11 Reduce the amplitude of the sine wave to OV. Slowly increase the sine wave amplitude until the first clock pulse appears at Z42-15. Continue to increase the sine wave amplitude. If the clock pulse disappears and again reappears, the size of C35 should be increased. This process should be repeated until the first false clock pulse does not appear.

5.11.1 Another indication, other than the first clock appearing and disappearing, of a false clock pulse is that it will occur within 100  $\mu s$  after the comparator has changed state.

## 6.0 FILM PULSE HEIGHT ANALYZER CALIBRATION

6.1 Select Values.

6.1.1 Install the following nominal value select resistors and capacitors from Table 3.

Part No.	Value
R15, R18	4.99K EM 1/10 1%
R11, R13	1.00K EM 1/10 1%
C20, C21	1000 pf

TABLE 3. SELECT PARTS FOR THE FILM PHA

RELEASE Released	DATE 10/6/64	TITLE Test Specification for Surveyor Digital Blivet	MARSHALL LABORATORIES
PREPARED			
CHECKED			
APPROVED			
			NO. S40548
			CHECKY 7 OF

- 6.2 For the checkout and calibration of the film PHA, a I.I.I. PG-2 Pulse Generator is used in conjunction with the network shown in Figure 3 to generate the film pulse, the Data Reset Pulse and the detect end of Readout Pulse.




FIGURE 3. Film PHA Test Connectors

- 6.2.1 Set the pulse generator to put out a positive going 200 ms pulse at a 1 cps rate.
- 6.2.2 Before connecting the setup to the unit, check that the  $\tau$  at point A is about 30  $\mu$ s.
- 6.3 Apply power to the unit as in 5.1.2
- 6.4 8 KC Clock
- 6.4.1 Connect Z63-11 to + 3V.
- 6.4.2 By adjusting C20 and C21, set the clock frequency to 8000  $\pm$  80 cps.

RELEASED	Released	DATE	10/6/64	Test Specification for Surveyor Digital Blivet	MARSHALL LABORATORIES
PREPARED					
CHECKED					
APPROVED					
				S40548	
				SHEET 8 OF	

CHG L7#  
S40548

6.4.3 Every 125  $\mu$ s a positive-going 20  $\mu$ s pulse should appear at Z85-6.

6.4.4 St Z35 - 3, 5, a 4 KC square wave should appear.

6.4.5 At Z34 - 3, 5, a 2KC square wave should appear.

6.4.6 At Z33 - 3, 5, a 1KC square wave should appear.

6.4.7 At Z32 - 3, 5, a 500 CPS square wave should appear.

6.4.8 Disconnect + 3V from Z63-11.

6.5 Connect the pulse generator setup as shown in Figure 3. connecting point A to J1-14.

6.5.1 Adjust the pulse generator to a nominal output of + 2V.

6.5.1.1 At P3-14, there should be a negative-going + 3V to OV pulse.

6.5.1.2 The voltage at Z65-4 should fall from + 2.2  $\pm$  0.1V to 0.1  $\pm$  0.1V.

6.5.1.3 The voltage at Z36-6 should fall from +2.2  $\pm$  0.1V to 0.1  $\pm$  0.1V. The voltage at Z37-6 should remain at + 2.2  $\pm$  0.1V.

6.5.1.4 The voltage at Z68-6 should fall from + 3.0V to OV.

6.5.1.5 The voltage at Z70-6 should fall from + 3.0V to OV.

6.5.1.6 Modules Z41 through Z38 should be counting the 1CPS pulses from the pulse generator. Pins 3 and 5 of each module should vary between + 0.1  $\pm$  0.1V and + 2.2  $\pm$  0.1V.

6.5.1.7 The voltage at Z84-6 should fall from + 3.0 to OV.

6.5.2 Disconnect point A of Figure 2 from J1-14 and reconnect it to J1-6.

6.5.2.1 Same as 6.5.1.1.

6.5.2.2 The voltage at Z61-4 should fall from +2.2  $\pm$  0.1V to 0.1  $\pm$  0.1V.

RELEASE Released	DATE 10/6/64	TITLE Test Specification for Surveyor Digital Blivet	MARSHALL LABORATORIES NO. S40548 SHEET 9 OF
PREPARED			
CHECKED			
APPROVED			

CNS LTR

S40548

6.5.2.3 The voltage at Z37-6 should fall from  $+2.2 \pm 0.1V$  to  $0.1 \pm 0.1V$ . The voltage at Z36-6 should remain at  $+2.2 \pm 0.1V$ .

6.5.2.4 The voltage at Z68-6 should fall from  $+3.0V$  to  $0V$ .

6.5.2.5 The voltage at Z70-6 should fall from  $+3.0V$  to  $0V$ .

6.5.2.6 Modules Z41 through Z38 should be counting the 1CPS pulses from the pulse generator. Pins 3 and 5 of each module should vary between  $+0.1 \pm 0.1V$  and  $+2.2 \pm 0.1V$ .

6.5.2.7 The voltage at Z84-12 should fall from  $+3.0V$  to  $0V$ .

## 6.6 Threshold and Calibration.

6.6.1 Remove signals to P-3. Connect point A in Figure 3 to J1-6. Ground Z65-9.

6.6.1.1 Reduce the amplitude of the pulse generator until the peak amplitude at Z69-13 is  $+50 \pm 1$  mv.

6.6.1.2 Select the bias resistor, R13, so that one clock pulse appears at Z63-15. Record the value of R13.

6.6.1.3 Adjust the amplitude of the pulse generator such that the peak amplitude at Z69-13 is  $1.703 \pm 0.17V$ . Select R18 such that twelve clock pulses occur at Z63-15.

6.6.1.3.1 If the proper resistor, R18, is not available, the clock frequency may be adjusted a minimum amount to generate the 12 clock pulses.

6.6.1.4 The  $\tau$  of the detector output, Z69-16, should be approximately 400  $\mu s$ .

6.6.2 Disconnect point A from J1-6, connect A to J1-14. Remove ground from Z65-9 and ground Z61-9.

6.6.2.1 Reduce the amplitude of the pulse generator until the peak amplitude at Z58-13 is  $+50 \pm 1$  mv.

6.6.2.2 Select the bias resistor, R-11, so that one clock pulse appears at Z63-15. Record the selected value of R1-1.

RELEASED	Released	DATE	10/76/64	TITLE	MARSHALL LABORATORIES
PREPARED				Test Specification for Surveyor Digital Blivet	
CHECKED					
APPROVED					
S40548					
PAGE 10 OF					

CHS LTR  
S40548

6.6.2.3 Increase the amplitude of the pulse generator until the peak amplitude at Z58-13 is  $+1.703 \pm 0.17V$ . Select R15 such that twelve clock pulses occur at Z63-15.

6.6.2.3.1 If the proper resistor, R15, is not available, the clock frequency may be adjusted a minimum amount to generate the twelve clock pulses.

6.6.2.4 The  $\tau$  of the detector output, Z58-16, should be approximately 400  $\mu s$ .

#### 6.7 Noisy Film Circuit

6.7.1 Set input level to 1.7V. J1-6 and 14. Increase pulse rep rate until the output at Z75-6 goes from 3.0V to 0V.

6.7.2 Measure rep rate at Z74-6. It should be  $\approx 10$  ms.

RELEASE	Released	DATE	10/6/64	TITLE	<b>MARSHALL LABORATORIES</b> NO. S40548 SHEET 11 OF 11
PREPARED				Test Specification for Surveyor Digital Blivet	
CHECKED					
APPROVED					

[illegible]



## 1.0 SCOPE

This procedure describes the test required to verify proper operation of the electronics in the Surveyor Sensor, ML 256-1. This assembly, 51225-101, is a portion of the Surveyor Micrometeorite Ejecta Detector, ML 185-1.

## 2.0 APPLICABLE DRAWINGS

- 2.1 Marshall Laboratories, 51254, Assembly-Sensor Electronics
- 2.2 Marshall Laboratories, 51114, Schematic Diagram, Lunar Ejecta Detector
- 2.3 Marshall Laboratories, 51225-101, Matrix Assembly

## 3.0 TEST EQUIPMENT (Equivalent Units are Acceptable)

- 3.1 Power Supply, Hewlett-Packard, Model 721A, four required
- 3.2 Pulse Generator, Rutherford, Model B-15
- 3.3 Oscilloscope, Tektronix, Type 545-A
- 3.4 Plug-In Unit, Tektronix, Type CA.
- 3.5 Resistor Decade, General Radio, Type No. 1432-L.

## 4.0 TEST PROCEDURE

4.1 Using the schematic diagram (51114) and the mylars (51225-101) as references, connect  $+6v \pm 0.1v$  to the terminal brought out on the board for connection to J01 - Pin 4. Similarly, connect  $-7v \pm 0.1v$ ,  $+3v \pm 0.1v$ ,  $+12v \pm 0.2v$  and common to terms J01-7, -11, -12 and 2 respectively.

4.2 Before applying power, verify continuity between all terminals brought out on the board and their respective points of connection to elements on the board.

4.3 To terminal J01 - Pin 8, apply a negative going pulse  $1.5v \pm .1v$  in amplitude,  $1ms \pm 0.1ms$  pulse width and  $20pps \pm 2pps$ .

4.4 Sync. the scope externally on the negative going edge of the input pulse.

RELEASED	DATE	TITLE	<b>MARSHALL LABORATORIES</b>
PREPARED	FEB 25 1965	Surveyor Sensor Blivet,	
CHECKED		Test Specification for	
APPROVED			
			S 40660
			SHEET 2 OF

4.5 The voltage at Z13 Pin 7, Z12 Pins 3 & 10, Z11 Pins 3 & 10 shall be a positive going pulse  $2.8\text{v} \pm 0.2\text{v}$  in amplitude,  $20\text{ pps} \pm 2\text{ pps}$  and  $10\text{ ms} \pm 2\text{ ms}$  Pulse Width.

4.6 The voltage at Z12 pins 4, 5, & 8, and Z11 Pins 4, 5 & 8, shall be a square wave  $2.8\text{v} \pm 0.2\text{v}$  in amplitude,  $10\text{ pps} \pm 1\text{ pps}$ .

4.7 The voltage at Z12 Pins 7, 9 & 11, and Z11 Pins 7, 9 & 11, shall be the same as in Paragraph 4.6, except inverted.

4.8 Temporarily install  $R6 = 1\text{K}$ ,  $R10 = 1\text{K}$ ,  $R14 = 5.1\text{K}$  and  $R11 = 1\text{K}$ , using  $1/4$  watt 5% resistors. Production Department will install flags for this purpose.

4.9 The voltage at TP8 shall be, alternately, a negative going pulse  $20\text{ mv} \pm 5\text{ mv}$  in amplitude, and negative going pulse  $140\text{ mv} \pm 15\text{ mv}$  in amplitude. The pulse rate shall be  $20\text{ pps} \pm 2\text{ pps}$ .

4.10 The voltage at Z16 pin 6 shall be a negative going pulse  $70\text{ mv} \pm 15\text{ mv}$  in amplitude,  $10\text{ pps} \pm 1\text{ pps}$ .

4.11 The voltage at Z17 Pin 6 shall be a negative going pulse  $8\text{ mv} \pm 2\text{ mv}$  in amplitude,  $10\text{ pps} \pm 1\text{ pps}$ .

4.12 Apply a positive going pulse  $2.8\text{ v} \pm 0.2\text{v}$  in amplitude, a rate of  $20\text{ pps} \pm 2\text{ pps}$  and a  $10\text{ ms} \pm 2\text{ ms}$  pulse width to J1 - Pin 5. (Sync. the scope positive).

4.13 Repeat Paragraphs 4.3 and 4.4

4.14 The voltage at J1 - Pin 1 shall be a positive pulse  $1750\text{ mv} \pm 375\text{ mv}$  in amplitude at a  $10\text{ pps} \pm 1\text{ pps}$  rate.

4.15 The voltage at J1 - Pin 9 shall be a positive pulse  $200\text{ mv} \pm 50\text{ mv}$  in amplitude at a  $10\text{ pps} \pm 1\text{ pps}$  rate.

RELEASE DATE	FEB 1965	TYPE	
PREPARED		Surveyor Sensor Blivet Test Specification for	MARSHALL LABORATORIES
CHECKED			
APPROVED			
			S 40660
			SHEET 3 OF 3

S40682

## REVISIONS

NO.	OFF	OWN	DESCRIPTION	BY	DATE	CH'D	APPROVAL

S40682

[illegible]

## 1.0 SCOPE

- 1.1 This specification contains a description of the functions and operation of the Surveyor Ejecta Detector GSE ML 260-1.

## 2.0 APPLICABLE DRAWINGS

- 2.1 Marshall Laboratories, 51287, Schematic Diagram Micrometeorite Ejecta Detector, (GSE - Surveyor)
- 2.2 Marshall Laboratories, 51444, Jacks-in-a-Box (Surveyor - GSE) ML 270-1.

## 3.0 FUNCTIONAL DESCRIPTION OF THE EJECTA DETECTOR GSE

- 3.1 The Ejecta Detector GSE is a portable test set which supplies all electrical power and signals necessary to check the Lunar Ejecta Detector ML 185-1 for proper operation. The test set provides a readout display instantaneously upon initiating the stimulus for the Lunar Ejecta Detector experiment. The operator now has a visual check of the experiment data correlated with the input parameters which are selected on the front panel.

In addition the Ejecta Detector GSE may be used in conjunction with the spacecraft to supply only experiment stimulus, while the spacecraft or simulator is to provide telemetry signals and readout display.

- 3.2 The Ejecta Detector GSE can be operated on an external 12-volt battery, or operated from 115-volt A.C. line. Terminals for the battery are located on the rear panel. To conserve power while in battery mode, panel lights may be turned off by use of a switch on the rear panel. This does not interfere with the readout display.

DESIGNED	DATE	TITLE	<b>MARSHALL LABORATORIES</b>
DRAWN	FEB 10 1965	Ejecta Detector	
CHECKED		(GSE - Surveyor)	
APPROVED		ML 260-1	
		Operational Manual	
			NO.
			S40682
			SHEET 2 OF

S40682

- 3.3 Specific functions of the Ejecta Detector GSE are to:
- A. Provide spacecraft power to the experiment.
  - B. Provide heater power to the experiment.
  - C. Provide simulated sensor signals to the experiment.
  - D. Provide simulated telemetry signals:
    - 1. CALIB command
    - 2. CLEAR command
    - 3. READOUT command
  - E. Provide storage of the serial binary readout data, binary to decimal conversion, and display.
  - F. Provide a monitor for the experiment temperature.
  - G. Provide a monitor for experiment power supply voltages.
  - H. Provide a monitor for experiment input current.
  - I. Provide monitor of all input and output signals of the experiment.

#### 4.0 CABLING

- 4.1 There are five (5) cables supplied with the Ejecta Detector GSE which may be stored in the cable compartment located behind the rear panel.
- 4.2 Cable description:
- A. Payload to GSE
  - B. Sensor to Payload
  - C. Sensor to GSE
  - D. A.C. Line Power
  - E. GSE to Jack Box

DATE	FEB 1965	TITLE	MARSHALL LABORATORIES	
APPROVED		Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	NO.	
REVIEWED			S40682	
TESTED			SHEET	3 OF
REVISIONS				

- 4.3 The sensor to payload and sensor to GSE cables are made of special high temperature cable.
- 4.4 A small shielded attenuator box is installed in the (sensor to GSE) cable to prevent any possible cross talk to other signal lines and provide optimum signal transmission levels.
- 4.5 The GSE to jack box cable was designed to not only relieve front panel congestion, but also to provide a means of disconnecting possible noise receiving cables when jacks are not in use.
- 4.6 Connectors on the rear panel of the GSE are designed to mate with only the proper cables to ensure intended interconnection.

## 5.0 DESCRIPTION OF GSE FRONT PANEL FUNCTIONS

- 5.1 The front panel controls provide simulation of all input parameters to the experiment. In addition there are tests designed to check the logic portion of the experiment.
- 5.2 The front panel may be divided into four groups, 1) readout display, 2) monitoring meter, 3) selection of input parameters with pushbutton switches, and 4) VERNIER/PRESET controls for sensor stimulus.
- 5.3 Pushbutton switches are lighted to indicate the selected input parameters.
- 5.4 Four pushbutton switches are used for indicating power modes.
- A. POWER - GSE power on.
  - B. EXP POWER - experiment power on
  - C. BATTERY-LINE - GSE power supplied by 115V, 60 cycle A.C. or external D.C. battery
  - D. HEATER POWER - 22V power for experiment heater located in sensor housing.
- 5.5 The operational limits on the line voltage are from 105V to 122V, 60 cps A.C.
- 5.6 The operational limits on the battery mode are from 12.2V to 20V. The battery rating should be a minimum of 300 ma. Polarity must be observed on terminals when connecting external battery although fuse protection is provided in the event of battery polarity reversal.

REVISION	DATE	TITLE	MARSHALL LABORATORIES	
1	FEB 10 1965	Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	NO.	
2			S40682	
3			SHEET	4 OF

MFG. CODE NUMBER 13126

FO... ML 77

S40682

- 5.7 To initiate any one of the three commands (CALIB, CLEAR, or READOUT) the REPEAT/MANUAL switch must be in the MANUAL position. The desired command is selected by depressing one of the three switches. Only one command is to be selected at a time. The lighted switch indicates which command has been selected. The lighted (ENTER COMMAND) switch is depressed momentarily to initiate command after the selection.
- 5.8 The calibrate command provides the in-flight calibration of the MIC PHA and FILM PHA mode of operation. In order to achieve a complete calibration, the CALIB command must be initiated twice. The sequence of the in-flight calibration alternates with every depression of the switch as follows:
- FILM A PHA = 12  
MIC PHA = 6
- FILM B PHA = 6  
MIC PHA = 2
- The results of this command are immediately displayed by the GSE with the appropriate film identification and accumulator information.
- 5.9 The CLEAR command is also a simulated telemetry signal. This command is initiated to clear possible shorts that may have existed on the film plates. The Flight System's clear signal, causes a disturbance in the film amplifiers, which results in an erroneous readout.
- 5.10 The READOUT command is another simulated telemetry signal. This command starts the Flight System readout. The readout command function is used for repeating the readout of the most recent stored information. Repeated readout commands may be used to test the Flight System's susceptibility to noise by observation of the repeated data.

## 6.0 ANALOG SIGNALS

- 6.1 The analog signals are as follows:

- A. MIC
- B. FILM A
- C. FILM B

APPROVED	FEB 27 1965	TITLE	MARSHALL LABORATORIES
PREPARED		Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	
CHECKED			S40682
REVIEWED			SHEET 5 OF 5

S40682

- 6.2 The timing indicated on the switches will be referenced to the time of a pulse generated by the ENTER DATA switch. The ENTER DATA switch initiates the analog sequence.
- 6.3 The MIC analog pulses may be selected at  $T = 0 \mu \text{ sec}$ ,  $T = 50 \mu \text{ sec}$ ,  $T = 500 \mu \text{ sec}$ ,  $T = 50 \text{ M sec}$ , and  $T = 150 \text{ M sec}$ .
- 6.4 To prevent a second MIC pulse from being generated during the pulse height analysis of the first pulse, the selection switches are appropriately interlocked, the left-most switch taking precedence.
- 6.5 With the selection of the MIC  $T = 0 \mu \text{ sec}$ , additional selections are as follows:
- A. MIC  $T = 50 \mu \text{ sec}$  is not allowed
  - B. MIC  $T = 500 \mu \text{ sec}$  is not allowed
  - C. MIC  $T = 50 \text{ M sec}$  generates a pulse during the readout of the MIC PHA bits. No pulse height analysis is made, however, one extra count is added to the MIC accumulator.
  - D. MIC  $T = 150 \text{ M sec}$  generates a pulse after the MIC PHA and MIC ACC have been read out, and before the completion of the entire readout. No analysis is made. One extra count will be added to the accumulator on the next readout.
- 6.6 The FILM A, FILM B signals may be selected at  $T = 0 \mu \text{ sec}$ ,  $T = 50 \mu \text{ sec}$ ,  $T = 500 \mu \text{ sec}$ , and  $T = 50 \text{ M sec}$ .
- 6.7 With the selection of  $T = 0 \mu \text{ sec}$ , on FILM A or FILM B as a reference, additional selections are as follows:
- A. FILM  $T = 50 \mu \text{ sec}$  is not allowed
  - B. FILM  $T = 500 \mu \text{ sec}$  is not allowed
  - C. FILM  $T = 50 \text{ M sec}$ , no analysis is made, however, one extra count is added to the accumulator.
- 6.8 The  $T = 50 \mu \text{ sec}$  and  $T = 500 \mu \text{ sec}$  switches, both MIC and FILM, have other functions. For example, if a hit occurs on the MIC, the FILMS will accept information for  $100 \mu \text{ sec}$ , then film analysis will be inhibited until readout is completed. If a hit occurs on either film, the MIC PHA will be inhibited after  $100 \mu \text{ sec}$ .
- 6.9 For a more detailed example refer to 9.0, Acceptance Test.

DATE FEB 10 1965	TITLE Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	MARSHALL LABORATORIES	
		S40682	
		SHEET 6 OF	



## 7.0 ANALOG SIGNAL MODES

- 7.1 The modes in which the analog signals may be generated are as follows:
- A. REPEAT/MANUAL
  - B. PRESET/VERNIER
- 7.2 The REPEAT mode initiates the data at a rate of .5 cps.
- 7.3 In the MANUAL mode, the data is initiated by momentarily depressing the ENTER DATA switch.
- 7.4 In the PRESET mode, the PHA windows are selected by the use of a thumb wheel switch. The preset number on the switch should correspond to the displayed number in the PHA readout.
- 7.5 The VERNIER mode is used in tests to establish the threshold of the PHA windows.
- 7.6 The vernier potentiometers are calibrated in tens, hundreds, and thousands of millivolts. The largest output is ten volts. The FILM analog signals are calibrated to  $\pm 1\%$  of the dial setting. Before calibrating a Flight System, the  $28V$  must be adjust for  $28V \pm 1\%$ .
- 7.7 The FILM HI-LOW toggle switch, located on the front panel, is used to acquire the desired dynamic range of the analog signal. In the LO position the first eleven (11) PHA steps are produced. In the HIGH position, steps twelve through fifteen are obtained.
- 7.8 The MIC analog signal is attenuated by a factor 62.1:1 from the MIC vernier setting.
- 7.9 Additional pulses to the MIC and FILM amplifiers are generated by the GSE other than those that are selected by the switches. Automatically pulses are generated during the MIC accumulator readout, and FILM accumulator readout. No PHA analysis is made, and no counts are added to the accumulators. These pulses are provided to check the inhibits of the accumulators during readout.

DATE RELEASSED	FEB 17 1965	TITLE	Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	MARSHALL LABORATORIES
APPROVED				
APPROVED				
APPROVED				
NO. S40682			SHEET 7 OF	

## 8.0 METER MONITOR

8.1 The meter provides a check of the following experiment parameters:

- A. TEMP (of sensor unit in °C)
- B.  $I_{PRI}$  (primary current)
- C. 2V
- D. 29V (actually 28V at the experiment)
- E. 3V
- F. 12V
- G. 6V
- H. -7V
- I.  $I_{HTR}$  (sensor heater current)

8.2 The sensor temperature probe is located in the sensor blivet. The meter reads temperature directly in degrees centigrade.

8.3  $I_{PRI}$  is the current drawn by the experiment. The meter reads milliamperes deviation from nominal.

8.4 The 2V B+ monitor is located in the power supply blivet. The meter reads the percentage change in volts from nominal (2.04V).

8.5 In the 29V position the meter indicates the D.C. voltage (from the spacecraft) applied to the experiment. The meter is calibrated to measure the percentage change from the nominal 28V.

8.6 The four (4) experiment power supply voltages -- 3V, 12V, 6V, and -7V, are displayed as percentage changes from nominal.

8.7 The  $I_{HTR}$  scale reads directly in milliamperes the current supplied to the heater in the sensor blivet.

RECEIVED	FEB 24 1963	NOTE	Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	<b>MARSHALL LABORATORIES</b>
PREPARED				
CHECKED				
INDEXED				
				NO. S40682
				SHEET 8 OF

## 9.0 ACCEPTANCE TEST

9.1 POWER ON  
EXP POWER ON  
LINE  
REPEAT  
PRESET

9.1.1 Depress all five (5) switches in MIKE row (upper row).

9.1.2 Rotate the MIC PRESET thumbwheel through all settings. At each setting note that the MIC PHA display corresponds to the setting except that an "8" on the wheel corresponds to a "0" on the display.

OBSERVE: FILM PHA = 00  
FILM ACC = constant  
ID = both at zero (0)

9.1.3 Note that the MIC ACC display advances three (3) counts per readout and cycles from 0 through 7 and back to 0.

OBSERVE: FILM PHA = 00  
FILM ACC = constant  
ID = both at zero (0)

9.1.4 Release the MIC 150 M sec switch and note that MIC ACC display advances two (2) counts at a time.

OBSERVE: FILM PHA = 00  
FILM ACC = constant  
ID = both at zero (0)

9.1.5 Release the MIC 50 M sec switch and observe that the MIC ACC display advances one (1) count at a time.

OBSERVE: FILM PHA = 00  
FILM ACC = constant  
ID = both at zero (0)

RECEIVED	DATE	TITLE	<b>MARSHALL LABORATORIES</b>  S40682 SHEET 9 OF
RECEIVED		Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	
RECEIVED			
RECEIVED			
RECEIVED			

9.1.6 Release the three (3) remaining MIC switches and observe that all readings are constant.

9.2 POWER ON  
EXP POWER ON  
LINE  
REPEAT  
PRESET

9.2.1 Depress the four (4) FILM A switches and rotate the FILM PRESET thumbwheel through settings 0 through 15.

OBSERVE: The FILM PHA display will correspond to each setting on the wheel.

The FILM ACC display advances two (2) counts per readout.

The A-ID is at a 1, the B-ID is at a 0.

MIC PHA = 0

MIC ACC = constant

9.2.2 Release the FILM A 50 Msec switch. Note that now the FILM ACC advances one (1) count per readout. All other readings remain as in paragraph 9.2.1.

9.2.3 Release the remaining three (3) FILM A switches and observe that all readings are constant

MIC PHA = 0

B-ID = 0

9.2.4 Repeat paragraphs 9.2.1 through 9.2.3 replacing FILM A with FILM B.

NOT RELEASED FEB 1965		WVLM	
PREPARED		Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	MARSHALL LABORATORIES
CHECKED			
APPROVED			
			S40682
		SHEET	10 OF

9.3 POWER  
LINE  
EXP POWER  
MANUAL

- 9.3.1 Depress CALIB switch and then momentarily (once) depress the ENTER COMMAND switch and observe sequence FILM A or FILM B. Momentarily depress the ENTER COMMAND switch and observe the other sequence. At each further depression of the ENTER COMMAND switch the display will alternate between FILM A and FILM B.

FILM A

FILM PHA = 12  
FILM ACC = advances one (1) count  
A-ID = 1  
B-ID = 0  
MIC PHA = 6  
MIC ACC = advances one (1) count

FILM B

FILM PHA = 6  
A-ID = 0  
MIC PHA = 2  
MIC ACC = advances one (1) count  
FILM ACC = advances one (1) count  
B-ID = 1

- 9.3.2 Release the CALIB switch and depress the CLEAR. Depress and release the ENTER COMMAND switch.

OBSERVE: Erroneous Readout

DATE FEB 10 1965	TITLE Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	NO. S40682
SHEET 11 OF		

MFG. CODE NUMBER 13126

9.3.3 Release the CLEAR and depress the CALIB. Momentarily depress the ENTER COMMAND and observe sequence FILM A or FILM B. Release CALIB and depress READOUT switch. Momentarily depress the ENTER COMMAND switch and observe that each time the ENTER COMMAND switch is depressed, the display flickers and returns to its original reading (i. e., sequence FILM A or FILM B).

9.4 POWER  
LINE  
EXP POWER  
REPEAT  
PRESET  
MIC PRESET = 5  
FILM PRESET = 11

9.4.1 Set MIC 0  $\mu$ sec switch and depress FILM A 0  $\mu$ sec switch.

OBSERVE: FILM PHA = 11  
FILM ACC = advances one (1) count per R/O  
A-ID = 1  
B-ID = 0  
MIC PHA = 5  
MIC ACC = advances 1/R/O

9.4.2 Release FILM A 0  $\mu$ sec and repeat paragraph 9.4.1 with FILM A 50  $\mu$ sec depressed, then release FILM A 50  $\mu$ sec.

9.4.3 Depress FILM A 500  $\mu$ sec.

OBSERVE: FILM PHA = 0  
FILM ACC = advances one (1) count/R/O  
A-ID = 0  
B-ID = 0  
MIC PHA = 5  
MIC ACC = advances one (1) count/R/O

Release FILM A 500  $\mu$ sec.

RELEASED	FEB 10 1965	FILE	Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	MARSHALL LABORATORIES
RECEIVED				
INDEXED				
FILED				
				S40682
				PAGE 7 12 OF

S40682

9.4.4 Depress FILM A 50 M sec and observe that the displays are as in paragraph 9.4.3.

Release FILM A 50 M sec

Release MIC 0  $\mu$ sec

9.4.5 Depress MIC 50  $\mu$ sec and FILM A 0  $\mu$ sec.

OBSERVE: FILM PHA = 11

FILM ACC = advances one (1) count/R/O

A-ID = 1

B-ID = 0

MIC PHA = 5

MIC ACC = advances one (1) count/R/O

Release MIC 50  $\mu$ sec

9.4.6 Depress MIC 500  $\mu$ sec.

OBSERVE: FILM PHA = 11

FILM ACC = advances one (1) count/R/O

A-ID = 1

B-ID = 0

MIC PHA = 0

MIC ACC = advances one (1) count/R/O

Release MIC 500  $\mu$ sec

9.4.7 Depress MIC 50 M sec and observe same display as in paragraph 9.4.6.

Release MIC 50 M sec

9.4.8 Depress MIC 150 M sec and observe same display as in paragraph 9.4.6.

Release MIC 150 M sec

9.4.9 Repeat paragraphs 9.4.1 through 9.4.9, replacing FILM A with FILM B in each step.

FEB 1965		TITLE	MARSHALL LABORATORIES	
REVISION		Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	S40682	
DATE			SHEET 13 OF	

S40682

OBSERVE: FILM PHA = 14  
FILM ACC = advances one (1) count/R/O  
A-ID = 1  
B-ID = 0  
MIC PHA = 0  
MIC ACCUM = constant

9.5.2 Depress FILM B 500  $\mu$ sec

OBSERVE: FILM PHA = 14  
FILM ACC = advances one (1) count/R/O  
A-ID = 1  
B-ID = 0  
MIC PHA = 0  
MIC ACCUM = constant

9.5.3 Repeat paragraphs 9.5.1 and 9.5.2 interchanging FILM B and FILM A.

FILM PHA = 1  
FILM ACC = advances two (2) counts/R/O

DATE RECEIVED	FREE DATE 1985	TITLE	MARSHALL LABORATORIES	
APPROVED		Ejecta Detector (GSE - Surveyor) ML 260-1 Operational Manual	NO.	
DATE			S40682	
APPROVED			SHIPPED	14 OF



MDL 5117

# MASTER DRAWING LIST

## MARSHALL LABORATORIES

IDENTIFYING NAME ELECTRONICS ASSY. - MICROMETEORITE EJECTA DETECTOR MODEL ML 185-1

ISSUE DATE 11/6/64 (SURVEYOR) REVISION DATE EFFECTIVITY SHEET 1 OF 3

LIST NO.	ASSEMBLY POSITION	DRAWING NUMBER	CHG. LTR.	DRAWING TITLE	
1	1	51117-101		Electronics Assy.	
2	2	L50677		Layout	
3	3	50678		Envelope	
4	4	50685		Electrical Interface	
5	5	51114		Schematic Diagram	
6	6				
7	7	51122-101		Housing Assy. - Power Supply	
8	8	T51210-101		Matrix Assy.	
9	9	T51210-1		Matrix	
10	10	T51215-101		Positioning Board	
11	11	T51215-2		Hook-up Board	
12	12	T51215-1		Support Board	
13	13	T51214-1		Spacer - Matrix	
14	14				
15	15	SP30245-1		Housing	
16	16				
17	17	W4157X1		Module (Command L. R.)	
18	18	W2131X7		Module (DIN)	
19	19	W2031X7		Module (DN)	
20	20	W4170X1		Module (SGO Driver)	
21	21	W133X11		Module (IM)	
22	22	W131X8		Module (JM)	
23	23	W233X7		Module (I/S)	
24	24	W4153X1		Module (Sure Start Clock)	
25	25	W730X7		Module (AC Driver)	
26	26	W4162X1		Module (Spec. Rect.)	
27	27	W4163X1		Module (Full Wave Rect. & Diode)	
28	28	W4070N2		Module (AC Volt. Conv.)	
29	29	W4161X1		Module (112 Volt. Dividers Reg.)	
30	30	W4165X1		Module (-77.5 Volts Reg.)	
31	31				
32	32	SP301493-1		Warranty Certificate	
33	33	SP30126-1		"	
34	34	SP30175		Envelope	
35	35	SP30219		Envelope	
36	36				

# MASTER DRAWING LIST

MARSHALL ISOTOPIES

IDENTIFYING NAME ELECTRONICS ASSY. - MICROMETEORITE EJECTA DETECTOR MODEL ML 185-1

ISSUE DATE 11/6/61 (SURVEYOR) REVISION DATE EFFECTIVITY SHEET 2 OF 3

LIST	ASSEMBLY POSITION	DRAWING NUMBER	CHG. LTR.	DRAWING TITLE		
37	1 2 3 4 5 6 7 8 9					
38	1	51237-101		Housing Assy. - Digital		
39	1	T51212-101		Matrix Assy.		
40	1	T51212-1		Matrix		
41	1	T51213-101		Positioning Board		
42	1	T51213-2		Hook-up Board		
43	1	T51213-1		Support Board		
44	1	T51214-1		Spacer - Matrix		
45	1					
46	1					
47	1	SP30246-101		Housing (Sub Assy.)		
48	1	SP30246-1		Housing		
49	1					
50	1	W130X7		Module (DIM)		
51	1	W133X7		Module (DIM)		
52	1	W134X7		Module (DIM)		
53	2	W131X8		Module (DIM)		
54	2	W4154X1		Module (A)		
55	1	W4155X1		Module (PA)		
56	1	W4172X1		Module (Integrator)		
57	2	W4176X1		Module (Detector)		
58	1	W4157X1		Module ( gated Clock)		
59	3	W4153X1		Module (Comp. Out)		
60	3	W4152X1		Module (Comp. In.)		
61	1	W169X1		Module (Gain Of 2 Amp.)		
62	1	W4165X1		Module (Amplifier & Hold)		
63	1	W4167X1		Module (Detector)		
64	3	W233X7		Module (I/S)		
65	1	W4171X1		Module (Trigger)		
66	1	W231X7		Module (DPN)		
67	2	W2051X7		Module (DN)		
68	1					
69	1	SP30247-1		Cover		
70	1	SP30247-2		Cover		
71	P	SP30253-1		Jig - Matrix		
72						

51117

# MASTER DRAWING LIST

# MAZSIL LABORATORIES

IDENTIFYING NAME ELECTRONICS ASSY. - MICROMETER EJECTA DETECTOR MODEL ML 185-1

RECEIVED DATE 11/6/66 (SURVEYOR)

ELVO NOIS/EEU

## EFFECTIVITY

[illegible]

LIST NO.	ASSEMBLY POSITION								DRAWING NUMBER	CHG. LTR.	DRAWING TITLE
	1	2	3	4	5	6	7	8			
73											
74	R										Thermal Unit
75											Circuit Board Assy. - Power Supply
76											Circuit Board
77											Circuit Board Assy. - Digital
78											Circuit Board
79											Housing
80											Housing
81											Cover
82											Cover
83											
84											
85											
86											
87	R										Manufacturing Spec.
88	R										Assembly Spec.
89	R										Connector Coding Spec.
90	R										Location Spec.
91	R										Matrix Spec.
92	R										Gold Plating Spec.
93	R										Wire & Ribbon Spec.
94	R										Bonding Spec.
95	R										Lockile Spec.
96	R										Spot-Def Spec.
97	R										Glass-Bead Peening Spec.

**WILLIAM B. COLLIER**

## MASTER DRAWING LIST

## MARSHALL LABORATORIES

IDENTIFYING NAME MICROMETEORITE EJECTA DETECTOR (GSE - SURVEYOR) MODEL ML 260-1  
 ISSUE DATE 6 November 1964 REVISION DATE EFFECTIVITY S/N 1 & Up SHEET 1 OF 6

LIST	ASSEMBLY POSITION								DRAWING NUMBER	CHG. LTR.	DRAWING TITLE			
	1	2	3	4	5	6	7	8	9					
1	1								51304-101		Micrometeorite Ejecta Detector Assy.			
2	R								51287		Schematic Diagram			
3														
4	R								S40533		Test Spec. for 51304-101			
5														
6	1								51273-1		Support - Chassis			
7	1								51273-2		Support - Chassis			
8	1								51279-1		Bezel - Switch			
9	1								51280		Front Panel			
10	1								51281-1		Bezel, Light			
11	1								51282-1		Escutcheon Plate			
12									51284		Master Panel			
13														
14	1								51285-1		Chassis - Power Supply			
15	1								51283		Flare Ring - Push Button Switch			
16	1								51289-101		Temp. Board Assy. - A/C Line Rectifier			
17	1								51289-1		Temp. Board			
18														
19	1								51291		Enclosing - Front Panel			
20	1								51335-1		Plate - Support			
21	1								51290		Enclosing - Escutcheon Plate			
22	1								51336-101		Cable - Relay Assy.			
23	1								51336-1		Frame			
24	1								51336-2		Cover			
25	1								51337		Back Panel			
26														
27	1								51327-101		Ckt. Bd. Assy. - Digital Readout & Commands			
28	1								51311-101		Matrix Assy.			
29	R								51311		Matrix A/W			
30	1								51312-101		Positioning Bd. Assy.			
31	1								51312-1		Positioning Bd. - Digital Readout & Commands			
32	1								51312-2		Hook-up Bd.			
33	1								51312		Pos Hook-up Bd. A/W			
34	2								51313-1		Spacer A/W			
35	R								51313		Spacer A/W			
36									PP 30253-5		Fig. Matrix			

MDI

51304

## MASTER DRAWING LIST

## MARSHALL LABORATORIES

IDENTIFYING NAME MICROMETEORITE EJECTA DETECTOR (GSE - SURVEYOR) MODEL ML 260-1

ISSUE DATE 6 November 1964 REVISION DATE EFFECTIVITY S/N 1 &amp; Up SHEET 2 OF 6

LIST NO.	ASSEMBLY POSITION	DRAWING NUMBER	CHG. IJR.	DRAWING TITLE	
37	1 2 3 4 5 6 7 8 9				
38	3	GW 130X7		Module (IIM)	
39	R	S40210		Test Spec. for GW130X7	
40	2	GW530X7		Module (INV.)	
41	R	S40222		Test Spec. for GW530X7	
42					
43	3	GW132X7		Module (IIM, S.T.)	
44	R	S40458		Test Spec. for GW132X7	
45	6	GW233X7		Module (One Shot)	
46	R	S40319		Test Spec. for GW233X7	
47	2	GW2030X7		Module (Nand Logic Gate)	
48	R	S40279		Test Spec. for GW2030X7	
49	2	GW730X7		Module (A/C Driver)	
50	R	S40175		Test Spec. for GW730X7	
51	4	GW133X7		Module (IM.R. T)	
52	R	S40358		Test Spec. for GW133X7	
53	16	GW134X7		Module (IIM, T)	
54	R	S40359		Test Spec. for GW134X7	
55	3	GW4155X1		Module (P/T)	
56	R	S40316		Test Spec. for GW4155X1	
57	1	GW2031X7		Module (Dual Nand)	
58	R	S40176		Test Spec. for GW2031X7	
59	1	GW4158X1		Module (Sharp Start Clock)	
60	R	S40329		Test Spec. for GW4158X1	
61	R	S40534		Test Spec. for 51327-101	
62					
63					
64	1	51328-101		Ckt. board Assy. - Tower Supply	
65	1	51292-101		Positioning " "	
66	1	51292-2		Positioning Board " "	
67	1	51292-1		Clock up Board " "	
68	R	51292		Power Reg. Sec. A/W Tower Supply	
69	2	51306-1		Spacer " "	
70	R	51306		Spacer A/W " "	
71					
72					

## MASTER DRAWING LIST

## MARSHALL LABORATORIES

IDENTIFYING NAME MICROMETEORITE EJECTA DETECTOR (GSE - SURVEYOR) MODEL ML-260-1  
ISSUE DATE November 1964 REVISION DATE EFFECTIVITY S/N 1 & Up SHEET 3 OF 6

LIST	ASSEMBLY POSITION					DRAWING NUMBER	CIG. LIB.	DRAWING TITLE		
	1	2	3	4	5					
73	1	2	3	4	5	51305-101		Matrix Assy. - Power Supply		
74	1	1				51305-1		Matrix - Power Supply		
75			R			T51305		Matrix A/W - Power Supply		
76		R				SP30253-4		JIG - Matrix		
77										
78										
79						GW4213X1		Module (11V. Regulator)		
80						S40241		Test Spec. for GW4213X1		
81						GW4070X3		Module (100/AC Converter)		
82			R			S40163		Test Spec. for GW4070X3		
83						GW4163X2		Module (100/4 Doubler)		
84						S40159		Test Spec. for GW4163X2		
85						GW4164X2		Module (22V. Regulator)		
86						S40162		Test Spec. for GW4164X2		
87						SP30202		Transformer		
88										
89						SP30279		Transformer		
90										
91						S40535		Test Spec. for SP30279-101		
92										
93										
94										
95						51326-101		Circuit Board Assy. - Sensor Electronics		
96						51323-101		Post Tooling Board Assy.		
97						51323-2		Post Tooling Board		
98						51323-1		Tooling Board		
99						T51323		Post Tooling Board Assy. - Sensor Electronics		
100						51324-101		Matrix Assy. - Sensor Electronics		
101						51324-1		Matrix		
102						T51324		Matrix A/W		
103						51325-1		Spacer		
104						T51325		Spacer A/W		
105										
106						5230253-6		Final Index		
107										
108										

17111

51304

# MASTER DRAWING LIST

## MARSHALL LABORATORIES

IDENTIFYING NAME MICROMETER TYPE EJECTA DETECTOR (GSE SURVEYOR) MODEL MI.260-1  
 ISSUE DATE 6 November 1964 REVISION DATE EFFECTIVITY S/N 1 & Up SHEET 4 OF 6

LIST NO.	ASSEMBLY POSITION	DRAWING NUMBER	CHG. LTR.	DRAWING TITLE
100	1			
101	2			
102	3			
103	4			
104	5			
105	6			
106	7			
107	8			
108	9			
109	10			
110	11			
111	12			
112	13			
113	14			
114	15			
115	16			
116	17			
117	18			
118	19			
119	20			
120	21			
121	22			
122	23			
123	24			
124	25			
125	26			
126	27			
127	28			
128	29			
129	30			
130	31			
131	32			
132	33			
133	34			
134	35			
135	36			
136	37			
137	38			
138	39			
139	40			
140	41			
141	42			
142	43			
143	44			
144	45			

MASTER DRAWING LIST

MARSHALL LABORATORIES

IDENTIFYING NAME MICROMETERITE ELECTA DETECTOR (CASE SURVEYOR) MODEL ML-260-1  
ISSUE DATE 6 November 1964 REVISION DATE EFFECTIVITY S/N 1 & Up SHEET 5 OF 6

LIST NO.	ASSEMBLY DETAIL					DRAWING NUMBER	CHG. LTR.	DRAWING TITLE			
	1	2	3	4	5						
145											
146						51321-102		Terminal Board Assy - Film			
147						51321-101		Terminal Board Assy - Film			
148						51321-1		Terminal Board - Film			
149											
150						51321-103		Terminal Board Assy - Mic			
151						51321-101		Terminal Board Assy - Mic			
152						51321-1		Terminal Board - Mic			
153											
154											
155						SP30150-A-4-16-157		Spacer - Threaded			
156						SP30286-A-4-16-180-32-4		Spacer - Threaded			
157											
158						SP30263-1		Digital Readout			
159						SP30263-7		Digital Readout			
160											
161						SP30264-15		Digital Readout			
162											
163											
164											
165						51340-102		Line In Filter Assy			
166						51340-101		Terminal Board			
167						51340-1		Board			
168						51340-2		Can			
169						SP30278		R.F. Choke			
170											
171											
172											
173						51341-101		Terminal Board Assy - Tie Point			
174						51341-1		Terminal Board - Tie Point			
175											
176											
177						SP30154-102		Cable			
178											
179											
239											



51304

1977 06/07/77 15:15/77

SECRET//NOFORN

IDENTITY NAME MICROMETEORITE EJECTA DETECTOR (GSE SURVEYOR) MODEL ML 260-1

ISSUE DATE 6 November 1964 REVISION DATE EFFECTIVITY S/N 1 & Up SHEET 6 OF 6

[illegible]

2000

MASTER DRAWING LIST

MARSHALL LABORATORIES

IDENTIFYING NAME    SENSOR ASSY. - MICROMETEORITE EJECTA DETECTOR (SURVEYOR)    MODEL    ML 256-1

ISSUE DATE    6 Nov. 1964    REVISION DATE    EFFECTIVITY    SHEET 1 OF 2

LIST NO.	ASSEMBLY POSITION	DRAWING NUMBER	CHG. LTR.	DRAWING TITLE		
1	1	51259-101		Sensor Assy.		
2	R	L50677		Layont		
3	R	51270		Envelope		
4	R	51114		Schematic Diagram		
5						
6	1	51254-101		Sensor Electronics		
7	1	SP30255-101		Housing (Sub-Assy.)		
8	1	SP30255-1		Housing		
9	1	SP30256-1		Cover		
10	1	SP30256-2		Cover		
11	1	T51225-101		Matrix Assy.		
12	1	T51225-1		Matrix		
13	1	T51226-102		Positioning Board		
14	1	T51226-1		Support Board		
15	1	T51226-101		Positioning Board		
16	1	T51226-2		Look-up Board		
17	2	T51227-1		Spacer-Matrix		
18	1	W4221X7		Module (Mic. Calib.)		
19	2	W4222X7		Module (Film Clear)		
20	1	W4223X7		Module (Film Calib.)		
21	1	W4223X8		Module ( " " )		
22	2	W4156X1		Module (Cap. Amp.) (Deleted)		
23	2	W2131X9		Module (DPN)		
24	1	W134X7		Module (BIN)		
25	1	W233X7		Module (I/S)		
26	1	W4145X1		Module (Hcenter) (Deleted)		
27	1	T51433-1		Support Board		
28	1	51247-101		Mic. Amp. Assy.		
29	1	T51232-1		Look-up Board		
30	2	W4151X1		Module (r, v Level Amp.)		
31	1	W4160X1		Module (Hi Level Amp.)		
32	1	SP30252-1		Filter		
33	1	T51245-1		Insulator		
34	R	T51238-101		Mold Form		
35	1	W4242-1		Module (Cap. Amp.)		
36						

MASTER DRAWING LIST

CHARSHALL LABORATORIES

IDENTIFIED IMAGE SENSOR ASSY. - MICROMETERORITE EJECTA DETECTOR (SURVEYOR) DEL ML 256-1

ISSUE DATE		6 November 1964		REVISION DATE		EFFECTIVITY		SHEET 2 OF 2	
LIST	ASSEMBLY POSITION	DRAWING NUMBER	CUG	DRAWING TITLE					
31	1								
32	1	51253-1		Impact Plate					
33	R	51253-2		Cap - Impact Plate					
34		51255-1		Shield - Cable					
35				Shield - Cable					
36									
37									
38									
39									
40									
41	R	51271-101		Thermal Unit					
42	1	51271-1		Circuit Board Assy.					
43		T51267-1		Circuit Board					
44	1	51271-2		Circuit Board Assy.					
45	1	T51268-1		Circuit Board					
46	1	SP30255-101		Housing - (Sub-Assy.)					
47	1	SP30255-1		Housing					
48	1	SP30256-1		Cover					
49	1	SP30256-2		Cover					
50									
51	R	S40072		Manufacturing Spec.					
52	R	S40071		Assembly Spec.					
53	R	S40091		Conformal Coating Spec.					
54	R	S40092		Flaming Spec.					
55	R	S40109		Bonding Spec. (Conductive Epoxy)					
56	R	S40113		Protective Finish Spec.					
57	R	S40120		Cold Plate Spec.					
58	R	S40133		Wire & Ribbon Spec.					
59		S40140		Bonding Spec. (Epoxy)					
60	R	S40091		Matrix Spec.					
61	1	S10214		Locite Spec.					
62	R	S10319		Spot-Pot Spec.					
63	R	S40394		Classified Packaging Spec.					